

Industrial Valves and Cathode Ray tubes

DATA HANDBOOK

Associated Electrical Industries Ltd
Radio Components Department
155 Charing Cross Road, London, WC 2

CONTENTS

HIGH POWER VALVES

(i.e. Valves with an anode dissipation greater than 100W)

| | | | | _ | | , | | | | | | |
|------------------|----------|---------|----------|--------------|--------------|-----------|---------|---------|---------|---------|--------------|--|
| | | | | Nun of Po | nber ages | | | | | | nber ages | |
| Application N | otes | on th | ie use | | | 16J12 | | | | | 2 | |
| vapour-coole | | | | | 3 | 16P12 | | | | | 4 | |
| | ata or | | olete | and | 0 | 16P13 | | | | | 3 | |
| replacement | | | | | 2 | ES833 | | | | | 4 | |
| Selection chart | | | ••• | | 1 | ESA1002 | | ••• | | ••• | 5 | |
| 14D12 | ••• | ••• | • • • | • • • | 6 | ESA1500 | | • • • • | ••• | *** | 2 | |
| | *** | ••• | • • • | • • • | | | ••• | ••• | ••• | ••• | | |
| 14D13 | *** | | | | 1 | ESA5000 | • • • • | • • • • | • • • • | • • • • | 8 5 | |
| 15D12 | ••• | *** | • • • | • • • | 8 | ESV1002 | | ••• | ••• | ••• | | |
| 15J12 | ••• | ••• | • • • • | • • • | 5 | ESV1500 | | ••• | ••• | ••• | 3 | |
| 15P12 | • • • | ••• | • • • | • • • • | 6 | ESW5000 | | • • • • | ••• | ••• | 7 | |
| 15V12 | ••• | ••• | • • • | • • • | 4 | V1505 | | | ••• | ••• | 4 | |
| LOW POWI | R V | ALVE | 5 | | | | | | | | | |
| (i.e. Valves wit | h an ai | node d | lissipat | ion le | ss tha | an 100W) | | | | | | |
| Condensed Date | ta on r | eplace | ment t | ypes | 1 | 11E16 | | | | | 5 | |
| 6F17 | | | | | 4 | 12E1 . | | | | | 6 | |
| 6F21 | | | | | 5 | 12E12 . | | | | | 4 | |
| 6F33 | | | | | 6 | 12E13 . | | | * | | 11 | |
| 6P17 | | | | | 3 | 12E14 . | | | | | 2 | |
| 11A1 | | | | | 2 | 13E1 . | | | | | 7 | |
| 11D12 | ••• | | | | 3 | 13E12 . | | | | | 2 | |
| 11E3 | | | | | 6 | ES85 . | | | | | 4 | |
| 11E13 | | | | | 4 | ES1101 . | | | | | 3 | |
| 11E15 | | | | | 5 | ES1102 . | | | | | 4 | |
| | | | | | | | | | | | | |
| RECTIFIERS | |) TH | YRAT | RON | | | | | | | | |
| Selection chart | | • • • • | ••• | | 1 | ESU200. | | | ••• | ••• | 2 | |
| Condensed D | ata o | n ob | solete | and | | ESU575. | | | | ••• | 2 | |
| replacement | rectific | ers | | | 1 | ESU673. | | | | ••• | 2 | |
| High vacuum | rectif | iers | | | | ESU866. | | | | | 3 | |
| 1001 | | | | | 3 | ESU872. | | | | | 1 | |
| 40117 | ••• | ••• | ••• | ••• | 3 | ESU8008 | | | | | 1 | |
| | ••• | • • • | ••• | ••• | | | | | | | | |
| 19H12 | ••• | ••• | ••• | • • • | 6 | Thyratron | 15 | | | | | |
| ESU74 | ••• | ••• | • • • • | | 3 | 20A2 . | | | | | 3 | |
| ESU77 | | ••• | • • • • | ••• | 2 | | | | | | 3 | |
| Gas-filled rec | tifiers | | | | | 21A1 . | | • • • | ••• | • • • | 5 | |
| ESU101 | | | | • • • • | 3 | 21B12 . | | | | ••• | 4 | |
| ESU103 | ••• | ••• | | | 2 | | | | • • • • | | 2 | |
| ESU106 | ••• | | | | 3 | 21N12 . | | | | | 4 | |
| ESU107 | ••• | | | | 3 | 21N13 . | | | | | 5 | |
| ESU111 | | | • • • • | | 3 | 21N14 . | | | | | 5 | |
| ESU115 | ••• | *** | • • • | **** | 2 | 21N15 . | | | | | 7 | |
| | | | | | | | | | | | | |

| SPECIA | L Q | JALIT | Y V | ALVES | | | | | | | | | | |
|-------------|---------|-------|--------|----------|------|------|----------------|--------|---------|---------|---------|---------|------|---|
| | | | | | Nur | mber | | | | | | Nur | nber | |
| | | | | | of P | ages | | | | | | of P | ages | ; |
| S2P20 | | | | | | 6 | S6F17F | | | | | | 5 | |
| S2P21 | | | | | | 4 | S6F33 | | | | | | A7 | |
| S6F12 | | | | | | 3 | S11E12 | | | | | | 7 | |
| S6F17 | | | | | | 3 | S19G6F | | | | | | 4 | |
| 30117 | | | | | ••• | • | 017001 | | | | | 4 | - | |
| | | | | | | | | | | | | | | |
| ELECTR | | OPTI | CAL | DEVIC | ES | | | | | | | | | |
| Photo-ce | ells | | | | | | Cathode | -ray t | ubes | | | | | |
| 27A12 | | | | | | 3 | Phosphor | s for | Indust | rial | Cathode | e-ray | | |
| 27C12 | | | | | | 3 | tubes | | | | | | 14 | |
| 27J12 | | | | | | 3 | Reference | Line | Gauges | | | | 5 | |
| PE50 | • • • | | | | | 3 | 30B1 | | | | | | 3 | |
| PE51 | | | | | | 3 | 30C2 | | | | | | 4 | |
| PE52 | | | | | | 2 | 30C3 | | | | | | 4 | |
| PE54 | | • • • | | | | 2 | 30C9 | | | | | | 3 | |
| PE55 | | | | | | 2 | 30E6 | | | | | | 4 | |
| | | | | | | | 30E11 | • • • | • • • | ••• | ••• | • • • • | 3 | |
| | | | | | | | 31B81 | ••• | • • • • | ••• | • • • • | • • • • | 6 | |
| Photom | ultipli | ers | | | | | 31B82 | • • • | | ••• | • • • • | ••• | 6 | |
| Notes | | | | | | 4 | 31C12 | • • • | • • • | • • • | • • • | • • • | 2 | |
| 27M1 | | | | | | 5 | 31C13 | • • • | | • • • | • • • | • • • | 2 | |
| 27M2 | | | | | | 5 | 31C14 | ••• | • • • • | • • • • | ••• | • • • • | 2 | |
| 27M3 | | | | | | 4 | 31C81 | • • • | • • • • | • • • • | ••• | ••• | 6 | |
| 27M12 | | | | | | 5 | 31D12 | ••• | ••• | • • • • | ••• | • • • | 2 | |
| 27M12/ | 4 | | | | | 3 | 31D13 31D15 | ••• | ••• | ••• | • • • | • • • | 2 | |
| 27M13 | | | | | | 6 | 31E12 | ••• | ••• | ••• | | • • • • | 2 | |
| | | | | | | | 31E12 | ••• | ••• | ••• | ••• | | 2 | |
| | | | | | | | 31E13 | • • • | ••• | ••• | ••• | | 2 | |
| | | | | | | | 31F12 | | | • • • | ••• | • • • • | 2 | |
| | | | | | | | 31G12 | | | | | | 2 | |
| MISCEL | LANI | ous | | | | | 01012 | , | | ••• | | | 2 | |
| Application | | | Vacuur | n Thor | mal | | 24T12 | | | | | | 2 | |
| Delay S | | | vacuui | ii ineri | nai | 1 | DRG36 | /2 | • • • • | ••• | *** | | 6 | |
| DLS10 | | | | | | 2 | 6H1 | / 2 | | | | | 4 | |
| DLS15/ | | | | | | 2 | 22M1 | | | | | | 2 | |
| DLS19 | | | | | | 2 | 29C1 | | | | | | 4 | |
| DLS23 | | | | | | 2 | Condense | 170707 | | | | | 2 | |
| DLS24 | | | | | | 2 | Condense | | | | | | 1 | |
| | | | | | - | _ | | | | | 640 | | 8 1 | |

October, 1962

Associated Electrical Industries Limited

Radio Components Department Tel.: GERrard 9797

(i.e., Valves with an anode dissipation greater than 100 w)

EDISWAN



APPLICATION NOTES ON THE USE OF VAPOUR COOLED VALVES

DESIGN CONSIDERATIONS

The limiting value of V_a allows for the use of poorly regulated H.T. supplies or for those with appreciable ripple. In extreme cases of poor regulation or in the presence of large ripple values the maximum design value of V_a may have to be reduced to ensure that the absolute maximum rating is not exceeded during any part of the low frequency cycle or when the H.T. rises off load.

With 3-phase full wave or half wave rectification of normal regulation the typical operating conditions can be used directly.

In analyses care must be taken when using H.T. supplies of large ripple content that allowance is made for the increase in effective voltage, current and power. In the single phase full wave unsmoothed case the increase in power approaches 23% as compared with the product of mean current and voltage.

It is recommended that a resistor of 2.5 ohms for each 1 kV of anode voltage is included between the H.T. source and the valve anode as a surge limiter.

COOLING

The Vapotron system lends itself to four different methods of cooling, each with its own characteristics and advantages.

(a) Boiler with convection cooled heat exchangers: This requires a minimum of 0.75 sq. ft. in a horizontal plane for each kilowatt of input power to the boiler. This rating is based on a 30-in. chimney, 30°C. ambient



APPLICATION NOTES ON THE USE OF VAPOUR COOLED VALVES

air temperature, 70°C. maximum condensate temperature and a recommended design of heat exchanger. This system is attractive where the minimum of moving parts is desirable, where water is at a premium, and where dust-laden atmospheres, or noise, prohibit the use of forced air.

- (b) Boiler with forced air-cooled heat exchanger: Proprietary equipments consisting of a heat exchanger and fan are available with adequate steam handling capacity. This arrangement is to be preferred where both space and water are at a premium and noise is no objection.
- (c) Boiler with water-cooled heat exchanger:

 Standard types of water-cooled heat exchanger can be used but their suitability for use with steam should be checked. An efficient heat exchanger of a recommended type will require 0.3 of a litre per minute for each kilowatt of input power to the boiler assuming 20°C. inlet water temperature and 70°C. condensate and outlet water temperature. This system is attractive where water is available and uses the minimum amount possible. Scaling troubles are practically eliminated and the necessity for long lengths of insulating hose disappears. This is probably the most compact arrangement.
- (d) Boiler Condenser: This system employs a water-cooled heat exchanger within the boiler, and the same water flow is required as for (c). This is a very compact arrangement, but the special anti-electrolytic fittings supplied must be used to overcome the effects of leakage currents through the water.



APPLICATION NOTES ON THE USE OF VAPOUR COOLED VALVES

SAFETY

The Vapotrons are fitted with three low-temperature soldered pull-out lugs in the supporting rim, which are intended to be connected by an insulating cord to a switch which is actuated should loss of water allow the temperature of the rim to rise above that of the solder melting point. This temperature is low enough to preclude damage to the valve.

Dangerous steam pressures are not possible using the boilers, as the blockage in the steam outlet will only result in the valve being lifted off its seating. This occurs at a pressure of the order of 1-2 lbs per sq. in.

In the boiler condenser system the valve is positively fixed to the seating and a sensitive pressure switch is fitted as well as pull-out lugs, so that in case of cooling water failure and consequent rise in steam pressure, a switch will operate and trip the equipment long before any dangerous pressures can be set up. The pull-out lugs will still operate in the event of loss of water from the boiler condenser.

The foregoing are the essential safety precautions which should be taken with every Vapotron installation, but for convenience others could be added, and it is recommended that water level indicators are used with boilers, though these can take an extremely simple form merely by arranging a sight glass on the vertical portion of the condensate return tube. The boiler condensers have a level indication incorporated in the casing.



NEWLOATION NOTES ON THE USE OF VAROUN COQUED VALVES

amorniquestavol signés sobre desail pro processo del soft era ellore unus potrengone de religió deservo processo amores e el bern gran entirel, els planes como sel sos balancias, amorniquest una entire patent la socia como fer por ello la principación motiva que la porte como como entre ollo la elle con opporte ella como en porte a está el como como per con elle con opporte ella como en porte a está el como como per con .

they was the production or responded in the factor of the section of the section

hard recovering at solving with matter, represents a real at the last format brack of extension and appears to represent a beauty or most for a supply most format beauty or most or a supply most format and appears of the following or most or most and a sixty processors of the supply of the suppl

the recogning on the reservation of the presentation of the form of the first plant of th



Condensed Data on Obsolete Types

| Туре | Class | Vh (volts | lh (amps) | lk(em) (amps) | Va(max) (kV) | Pa(max) (watts) | 3 | f(max) at full rating (Mc/s) | ra (KΩ) |
|--------------|---|--------------|--------------|------------------|-----------------|--------------------|----|---------------------------------------|------------|
| EHF350 | Triode R | 22.0 | 16.0 | 2.5 | 4 | 200 | 43 | 09 | 13.5 |
| EHZ350/1 | Triode R | 22.0 | 16.0 | 2.5 | 2 | 750 | 43 | 09 | 13.5 |
| ES15 | Triode R | 16.5 | 17.5 | 3.4 | 4 | 200 | 20 | 9 | 12.5 |
| ES207 | Triode R | 16.5 | 18.0 | 1.6 | 2 | 800 | 20 | 75 | 8.2 |
| ES250M | Triode R | 11.0 | 4.0 | 4.0 | 2 | 250 | 15 | 2 | 4.0 |
| ES253 | Triode R | 16.5 | 16.5 | 1.2 | 12 | 800 | 20 | 9 | 20.0 |
| ES357 | Triode R | 10.0 | 10.0 | | 4 | 350 | 32 | 100 | 5.3 |
| ES450 | Triode R | 17.0 | 5.65 | | 7 | 450 | 30 | - | 20.0 |
| ES450X | Triode R | 18.0 | 5.15 | | 2 | 450 | 30 | - | 20.0 |
| ES1500 | Triode R | 15.5 | 24.0 | 7.5 | 7.5 | 1,500 | 45 | - | 20.0 |
| ES1500A | Triode R | 15.5 | 24.0 | 1.5 | 7.5 | 1,500 | 45 | 20 | 20.0 |
| ES1500A/1 | Triode R | 15.5 | 24.0 | 1.5 | 7.5 | 1,500 | 45 | 20 | 20.0 |
| ES1500B | Triode R | 17.0 | 27.5 | 2 | 7.5 | 1,500 | 37 | 2 | 16.0 |
| ES1500B/1 | Triode R | 17.0 | 27.5 | 2 | 7.5 | 1,500 | 37 | 2 | 16.0 |
| ES1500C/1 | Triode R | 14.5 | 28.0 | 2 | 7.5 | 1,500 | 35 | 2 | 16.0 |
| ESW204 | Triode R | 11.0 | 6.5 | 2 | 2 | 250 | 20 | 09 | 0.6 |
| ESW207 | Triode W | 22.0 | 52.0 | 6 | 15 | 10,000 | 20 | 1.6 | 3.5 |
| ET30 | Triode R | 12.5 | 6.3 | | 2 | 250 | 56 | 20 | 19.0 |
| ALL | Abuse of the Balistian Cooled W. Water Cooled | 000 | W . Pol | Water | Polocy | | | | |
| ADDI CYIACIO | ווא י וואמרוופ | | | 1 4 4 6 6 6 1 | | | | | |
| | | | | | | | | | |

August, 1962

Page 1, Issue 2

Condensed Data on Replacement Types

RADIATION COOLED TRIODES

| Type Number | V _f (V) | I _f (A) | V _{a(max)} (kV) | i _{k(pk)max} (A) | Pa(max) (W) | f_{max}^* (Mc/s) | g _m (mA/V) | μ |
|----------------|-----------------------|--------------------|-----------------------------|---------------------------|----------------|--------------------|--------------------------|----|
| EHZ350 | 22 | 16 | 5.0 | 2.5 | 750 | 60 | 3.2 | 43 |
| ES204A | 11 | 6.3 | 3.0 | 4.0 | 250 | 2 | 3.5 | 25 |
| ES204 X | 11 | 6.3 | 3.0 | 4.0 | 250 | 2 | 3.5 | 38 |
| ES275 | 17 | 2.5 | 2.5 | 1.25 | 275 | 1.5 | 7.3 | 16 |
| ES1001 | 10 | 18 | 5.0 | 6.0 | 1,000 | 30 | 8.0 | 40 |
| ESI500C | 14.5 | 28 | 7.5 | 2.0 | 1,500 | 2 | 2.2 | 35 |

RADIATION COOLED TETRODE

| ESG250 | 11.25 | 8.0 | 5.0 | _ | 250 | 1.0 | 100 |
|--------|-------|-----|-----|---|-----|---------|-----|
| | | | | | | | |

RADIATION COOLED PENTODE

| ESP450 | 10 | 13 | 3.0 | - | 450 | 10 | 6.5 | _ |
|--------|----|----|-----|---|-----|----|-----|---|

FORCED AIR COOLED TRIODES

| ESA891 22 60 10 8.5 4,000 1.6 — | 8·5 |
|-----------------------------------|-----|
| ESA892 22 60 10 8.5 4,000 1.6 7.5 | 48 |
| ESA2500 8 80 7.5 4.5 2,500 40 5.5 | 55 |

WATER COOLED TRIODES

| ESW891 | 22 | 60 | 12 | 8.5 | 6,000 | 1.6 | _ | 8.5 |
|---------|-----|----|-----|-----|--------|-----|-----|-----|
| ESW892 | 22 | 60 | 13 | 8.5 | 10,000 | 1.6 | 7.5 | 48 |
| ESW3000 | 8.0 | 80 | 7.5 | 4.5 | 3,000 | 10 | 5.5 | 55 |

^{*} At full ratings



High Power Valves


SELECTION CHART

| P _{a(max)} | f _{max} at full | | Cool | ling | |
|---------------------|-----------------------------|-----------|-------------------|-------------------|---------|
| (kW) | rating (Mc/s) | Radiation | Forced Air | Water | Vapour |
| 0.275 | 1.5 | V1505 | | | |
| 0.3 | 1.5 | 14D13 | | | |
| 0.3 | 30 | ES833 | | | |
| 0.45 | 10 | ESP450 | | | |
| 0.5 | 60 | 14D12 | | | |
| 0.65 | 60 | | | 15P12* | |
| 0.75 | 1.5 | 14D14 | | | |
| 0.8 | 60 | 15D12 | | | |
| 1.0 | 40 | ES1001 | | | |
| 1.3 | 60 | | 15J12 | | 15V12 |
| 3.0 | 40 | | {16J12 ESA1500 | {16P12* 16P13* | |
| 4.0 | 1.6 | | ESA892 | | |
| 5.0 | 40 | | ESA5000 | | ESV1500 |
| 5.0 | 50 | | | ESW5000 | |
| 10 | 1.6 | | | ESW892 | ESV892 |
| 12 | 40 | | 17J12 | | |
| 25 | 40 | | | | 17V12 |

^{*} Limited by water connections to 10 Mc/s.

August, 1962

Page 1, Issue 2



GENERAL

The 14D12 is a radiation cooled triode with a graphite anode and a directly heated thoriated tungsten filament. It is intended for use in r.f. heating, modulating and transmitting equipment.

RATINGS*

| Filament voltage | V_{f} | 5·0± | 5% V |
|------------------------------|------------------------|--------|------|
| Filament current (approx) | I _f | 32.5** | Α |
| Maximum anode voltage | $V_{a(max)}$ | 6.0 | kV |
| Maximum d.c. grid voltage | $V_{g(max)}$ | 1000 | V |
| Maximum anode dissipation | Pa(max) | 500† | W |
| Maximum grid dissipation | Pg(max) | 50 | W |
| Maximum peak cathode current | ik(pk)max | 3.0 | A |
| Maximum operating frequency | f_{max} | 60 | Mc/s |
| Maximum bulb temperature | T _{bulb(max)} | 250 | °C |
| Maximum seal temperature | $T_{seal(max)}$ | 200 | °C |

- * Limiting values are absolute maximum values.
- ** The filament is suitable for direct switching.
- † At this dissipation the anode runs bright red at approximately 870°C (Pyrometer reading).

INTER-ELECTRODE CAPACITANCES

| Anode/grid | c _{a-g} | 6.0 | pF |
|----------------|------------------|-----|----|
| Grid/filament | C _{g-f} | 11 | pF |
| Anode/filament | c _{a-f} | 0.4 | pF |

CHARACTERISTICS

| Anode voltage | V_a | 4.0 | kV |
|--|----------------|-----|------|
| Anode current | la | 120 | mA |
| Mutual conductance | g _m | 3.6 | mA/V |
| Amplification factor | μ | 22 | |
| Valve anode resistance $(\delta v_a/\delta i_a)$ | ra | 6.1 | kΩ |

Notes

Cooling is by low velocity air blast necessary under all conditions of valve service other than filament dissipation alone.

August, 1962 Page 1, Issue 1

Radiation Cooled Triode (



TYPICAL OPERATION—At maximum operating conditions.

Class C r.f. power amplifier—unmodulated or frequency modulated.

| D.C. anode voltage | V_a | 4.0 | 5.0 | 6.0 | kV |
|-------------------------|-------|-----|-----|-----|----|
| D.C. grid voltage | V_g | 280 | 400 | 500 | V |
| Peak r.f. drive voltage | | 570 | 690 | 790 | V |
| D.C. anode current | la | 585 | 530 | 500 | mA |
| D.C. grid current | lg | 175 | 155 | 145 | mA |
| Driving power | | 90 | 100 | 110 | W |
| Power output | Pout | 1.8 | 2.2 | 2.5 | kW |

TYPICAL OPERATION—At maximum operating conditions ($f_{max} = 60 Mc/s$) Class C self oscillator—anode supply d.c. or 3-phase full-wave rectified.

| D.C. anode voltage | V_a | 4.0 | 5.0 | 6.0 | kV |
|---|---------|------|------|-----|----|
| D.C. anode current | la | 585 | 530 | 500 | mA |
| D.C. grid current | lg | 175 | 155 | 145 | mA |
| Grid resistance | R_g | 1.6 | 2.6 | 3.4 | kΩ |
| Power input | Pin | 2.3 | 2.6 | 3.0 | kW |
| Power output | Pout | 1.7 | 2.0 | 2.4 | kW |
| Power output at 85% transfer efficiency | Pout | 1.45 | 1.75 | 2.0 | kW |
| Maximum anode dissipation | Pa(max) | 500 | 500 | 500 | W |
| Grid dissipation | Pg | 45 | 40 | 35 | W |

TYPICAL OPERATION—At maximum operating conditions ($f_{max} = 60 \text{ Mc/s}$) Class C self oscillator—single-phase full-wave rectified, unsmoothed anode supply.

| A.C. anode voltage (r.m.s.) | $V_{a(r.m.s.)}$ | 4.25 | kV |
|---|-----------------|------|----|
| Mean anode voltage | $V_{a(av)}$ | 3.8 | kV |
| D.C. anode current | la | 405 | mA |
| D.C. grid current | lg | 105 | mA |
| Grid resistance | R_g | 2.0 | kΩ |
| Power input | Pin | 1.9 | kW |
| Power output | Pout | 1-4 | kW |
| Power output at 85% transfer efficiency | Pout | 1.2 | kW |
| Maximum anode dissipation | Pa(max) | 500 | W |
| Grid dissipation | Pg | 20 | W |
| | | | |



TYPICAL OPERATION—At maximum operating conditions ($f_{max} = 60 \text{ Mc/s}$) Class C self oscillator—with a.c. anode supply.

| A.C. anode voltage (r.m.s.) | V _{a(r,m,s,)} | 4.25 | kV |
|---|------------------------|------|----|
| Mean anode voltage | $V_{a(av)}$ | 1.9 | kV |
| Mean anode current | $I_{a(av)}$ | 290 | mA |
| Mean grid current | $I_{g(av)}$ | 62 | mA |
| Grid resistance | Rg | 325 | Ω |
| Power input | Pin | 1.4 | kW |
| Power output | Pout | 0.8 | kW |
| Power output at 85% transfer efficiency | Pout | 0.7 | kW |
| Maximum anode dissipation | Pa(max) | 500 | W |
| Grid dissipation | Pg | 15 | W |

TYPICAL OPERATION—At maximum operating conditions per valve.

Class B1 audio amplification—push pull operation.

| Anode voltage | V_a | 6.0 | kV |
|-----------------------------|-----------------|------|----|
| A.C. anode current (r.m.s.) | $I_{a(r.m.s.)}$ | 0.25 | A |
| Power input | Pin | 1.0 | kW |
| Power output | Pout | 0.5 | kW |
| Anode dissipation | Pa | 0.5 | kW |
| Anode efficiency | | 50 | % |
| Bias signal | V_g | -220 | V |
| Peak signal voltage | Vsig(pk) | 220 | V |

MOUNTING POSITION—Vertical, anode upwards.

TOP CAP-Anode.

BASE—Special.

August, 1962 Page 3, Issue 1



OPERATING INSTRUCTIONS

Installation

The valve should be mounted vertically with the anode upwards. Connections should always make good electrical contact to prevent overheating pins and seals, particularly by r.f. current.

It is essential that connection be made to both grid pins when running at higher frequencies to reduce current taken by each pin. The valve must be protected against excessive vibration and shock.

Cooling

Forced air blast is recommended for all conditions of valve service except filament dissipation alone.

An air flow of 50 cu. ft./min. directed vertically upwards on to the grid and filament pins is ample.

The anode connector should be designed to keep the temperature of the anode seal below the maximum temperature stated.


Operation

The operating data list conditions for maximum output for respective classes of service at the relevant anode voltage. Linear interpolation between anode voltage steps is admissible. As these conditions utilize some or all of the maximum valve ratings, close control of conditions has to be maintained.

In Class C self oscillator service, precautions should be taken against excessive mains voltage variation. Current overload trips should be included in anode and grid circuits as well as an under current trip in the grid circuit.

In industrial r.f. heating it is not usual that all precautions can be taken, and under these conditions some reductions in operating conditions have to be made so that widely fluctuating loads, poor h.t. regulation, and mains variations can be accommodated. Each type of variation brings its own problems and no set rules are practicable.

AEI Radiation Cooled Triode




All dimensions in millimetres.

August, 1962 Page 5, Issue 1

Tel: GERrard 9797



CONSTANT CURRENT CHARACTERISTICS





RADIATION COOLED TRIODE

GENERAL

The 14D13 is a directly heated Radiation Cooled Triode which is mechanically and electrically identical to the V1505. It has a graphite anode and a thoriated tungsten filament. It is intended for use in Relay and Vibrator Amplifiers, also other low R.F. and A.F. service.

RATING—Absolute Values

| Filament Voltage | Vf | 14± | 5% V |
|------------------------------|-----------|-----|------|
| Filament Current | lf . | 7.0 | A |
| Maximum Anode Voltage (D.C.) | Va(max) | 3.0 | kV |
| Maximum Peak Cathode Current | ik(pk)max | 4.0 | A |
| Maximum Anode Dissipation | | | |
| (continuous) | Pa(max) | 300 | W |
| Maximum Operating Frequency | | | |
| at full ratings | f(max) | 1.5 | Mc/s |

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid | ca-g | 18 |
|----------------|------|-----|
| Grid/Filament | Cg-f | 14 |
| Anode/Filament | ca-f | 9.0 |

DIMENSIONS

| Maximum Overall Length | 345 | mm |
|------------------------|-----|----|
| Maximum Diameter | 90 | mm |
| Maximum Seated Height | 322 | mm |

MOUNTING POSITION—Vertical, base down

CHARACTERISTICS

| Anode Voltage | Va | 2.0 | kV |
|------------------------|----|--------|-----|
| Anode Current | la | 150 | mA |
| Mutual Conductance | gm | 8.0 m/ | A/V |
| Amplification Factor | μ | 16 | |
| Valve Anode Resistance | ra | 2.0 | kΩ |

December, 1961



RADIATION COOLED TRIODE

TYPICAL OPERATION—Class AB2, two valves

Values for one valve unless otherwise stated.

| Anode Voltage (d.c.) (no signal) | Va | 2.68*kV |
|---|------------|---------|
| Anode Voltage (d.c.) (maximum signal) | Va | 2.5 kV |
| Grid Voltage (d.c.) (approx) | Vg | —160 V |
| Grid Voltage (r.m.s.) (A.F. Sine Wave) | Vg(r.m.s.) | 180 Y |
| Anode Current (d.c.) (no signal) | la | 100 mA |
| Anode Current (d.c.) (maximum signal) | la | 350 mA |
| Grid Current (d.c.) (maximum signal) (approx) | lg | 25 mA |
| Grid Current (peak) (approx) | ig(pk) | 400 mA |
| Driving Power (maximum signal) (approx) | | 6-0 W |
| Maximum Anode Dissipation | Pa(max) | 300 W |
| Anode/Anode Load (two valves) | (, | 10 kΩ |
| Power Output (maximum signal) (two valves) | Pout | >1.2 kW |
| Distortion (total at maximum signal) (two valves) | D | <5 % |
| | | |

^{*} Based on 10% h.t. supply regulation.

BASE—Special 4 pin



RADIATION COOLED TRIODE

Directly heated

GENERAL

The 15D12 is a directly heated radiation cooled triode. It has a graphite anode, a thoriated tungsten filament and is intended for use in r.f. heating equipment.

RATING

| Filament Voltage | Vf | 6.3 | V |
|------------------------------|------------------------|--------|------|
| Filament Current | lf | 31-34* | A |
| Maximum Peak Anode Voltage | Va(pk)max | 6.0 | kV |
| Maximum Anode Dissipation | Pa(max) | 800** | W |
| Maximum Grid Dissipation | Pg(max) | 60 | W |
| Maximum Peak Cathode Current | ik(pk)max | 4.0 | Α |
| Maximum Operating Frequency | fmax | 60 | Mc/s |
| Maximum Seal Temperature | T _{seal(max)} | 200 | °C |
| Maximum Bulb Temperature | Tbulb(max) | 250 | °C |

^{*} The filament is suitable for direct switching without additional current limitations and will withstand fluctuations in voltage of $\pm 5\%$.

All limiting values are Absolute, not Design Centres.

INTER-ELECTRODE CAPACITANCES

| Anode/Grid | ca-g | 6.5 | pF |
|----------------|------|-----|----|
| Grid/Filament | cg-f | 13 | pF |
| Anode/Filament | ca-f | 0.5 | pF |

CHARACTERISTICS

| Anode Voltage | Va | 4.0 kV |
|----------------------------|----------------|----------|
| Anode Current | la | 200 mA |
| Mutual Conductance | g _m | 5.6 mA/V |
| Amplification Factor | μ | 23 |
| Anode Resistance (δva/δia) | ra | 4·1 kΩ |

February, 1962

^{**} At this dissipation the anode runs at approximately 900°C (Optical reading)

RADIATION COOLED TRIODE

Directly heated

TYPICAL OPERATION—At maximum operating conditions per valve.

Class B1 audio amplification—push pull operation.

| Anode Voltage | Va | 6.0 | kV |
|-----------------------------|------------|------|----|
| A.C. Anode Current (r.m.s.) | la(r.m.s.) | 0.4 | Α |
| Power Input | Pin | 1.5 | kW |
| Power Output | Pout | 0.7 | kW |
| Anode Dissipation | Pa | 0.8 | kW |
| Anode Efficiency | | 48 | % |
| Bias Voltage | Vg | -225 | ٧ |
| Peak Signal Voltage | Vsig(pk) | 225 | V |
| | | | |

TYPICAL OPERATION—At maximum operating conditions.

Class C self oscillator—single phase full wave rectified (no smoothing)

| Class C sell oscillator single pliase | run wave rec | , | 0, | | |
|---|--------------|------|--------|------|----|
| | | Mean | R.M.S. | Peak | |
| Anode Voltage | Va | 3.8 | 4.25 | 6.0 | kV |
| Bias Voltage | Vg | -150 | | | ٧ |
| Positive Grid Voltage | Vsig | 180 | | | ٧ |
| Grid Resistor | 11112 313 | 1.05 | | | kΩ |
| Anode Current | la | 625 | | 1700 | mA |
| Grid Current | lg | 140 | | 800 | mA |
| Cathode Current | lk | 2.55 | 2.8 | 4.0 | A |
| Anode Dissipation | Pa | 800 | | | W |
| Grid Drive Power | | 55 | | | W |
| Grid Dissipation | Pg | 25 | | | W |
| Anode Efficiency | - | 72 | | | % |
| Power Output (amplifier) | Pout | 2.1 | | | kW |
| Power Output (oscillator) at 100% Transfer Efficiency | Pout | 2.05 | | | kW |
| Power Output (oscillator) at 85% Transfer Efficiency | Pout | 1.75 | | | kW |
| | | | | | |

February, 1962



I5DI2 RADIATION COOLED TRIODE Directly heated

TYPICAL OPERATION—At maximum operating conditions.

Class C self oscillator-3-phase full wave rectified or d.c.

| | | Mean | R.M.S. | Peak | |
|--|--------------|------|--------|------|----|
| Anode Voltage | Va | 4.0 | 5.0 | 6.0 | kV |
| Bias Voltage | Vg | -260 | -340 | -500 | V |
| Positive Grid Voltage | Vsig | 260 | 260 | 240 | V |
| Grid Resistor | | 1.2 | 1.65 | 3.35 | kΩ |
| Mean Anode Current | la(av) | 815 | 780 | 660 | mA |
| Mean Grid Current | lg(av) | 220 | 205 | 150 | mA |
| Peak Cathode Current | ik(pk) | 4.0 | 4.0 | 4.0 | Α |
| Peak Anode Current | ia(pk) | 2.8 | 2.8 | 3.0 | A |
| Peak Grid Current | ig(pk) | 1.2 | 1.2 | 1.0 | A |
| Anode Dissipation | Pa | 800 | 800 | 800 | W |
| Grid Drive Power | | 105 | 115 | 105 | W |
| Grid Dissipation | Pg | 50 | 45 | 30 | W |
| Anode Efficiency | 1 10 20 10 4 | 76 | 79 | 80 | % |
| Power Output (amplifier) | Pout | 2.5 | 3.1 | 3.2 | kW |
| Power Output (oscillator) at 100% Transfer Efficiency | Pout | 2.4 | 3.0 | 3.1 | kW |
| Power Output (oscillator) at 85% Transfer Efficiency | Pout | 2.0 | 2.5 | 2.6 | kW |

TYPICAL OPERATION—At maximum operating conditions.

Class C self oscillator-single phase self rectified.

| Anode Voltage | Va | 1.9 | 3.0 | 6.0 | kV |
|--|------|------|-----|-----|----|
| Bias Voltage | Vg | -20 | | | V |
| Positive Grid Voltage | Vsig | 120 | | | V |
| Grid Resistor | | 195 | | | Ω |
| Anode Current | la | 430 | | 900 | mA |
| Grid Current | lg | 100 | | 500 | mA |
| Cathode Current | lk | 1.25 | 2.0 | 4.0 | A |
| Anode Dissipation | Pa | 800 | | | W |
| Grid Drive Power | | 31 | | | W |
| Grid Dissipation | Pg | 29 | | | W |
| Anode Efficiency | | 63 | | | % |
| Power Output (amplifier) | Pout | 1.25 | | | kW |
| Power Output (oscillator) at 100% Transfer Efficiency | Pout | 1.2 | | | kW |
| Power Output (oscillator) at 85% Transfer Efficiency | Pout | 1.0 | | | kW |

February, 1962

RADIATION COOLED TRIODE

Directly heated

DIMENSIONS

Maximum Overall Length Maximum Diameter 254 mm

152 mm

MOUNTING POSITION-Vertical, anode upwards.

TOP CAP-Anode

BASE-Special

OPERATING INSTRUCTIONS

Installation

The valve should be mounted vertically with the anode upwards. Connections should always make good electrical contact to prevent overheating pins and seals, particularly by r.f. current.

It is essential that connection be made to both grid pins when running at higher frequencies to reduce current taken by each pin. The valve must be protected against excessive vibration and shock.

Cooling

Forced air blast is recommended for all conditions of valve service except filament dissipation alone.

An air flow of 50 cu. ft./min. directed vertically upwards on to the grid and filament pins is ample.

The anode connector should be designed to keep the temperature of the anode seal below the maximum temperature stated.

Operation

The operating data list conditions for maximum output for respective classes of service at the relevant anode voltage. Linear interpolation between anode voltage steps is admissible. As these conditions utilize some or all of the maximum valve ratings, close control of conditions has to be maintained.


In Class C self oscillator service, precautions should be taken against excessive mains voltage variation. Current overload trips should be included in anode and grid circuits as well as an under current trip in the grid circuit.

In industrial r.f. heating it is not usual that all precautions can be taken, and under these conditions some reductions in operating conditions have to be made so that widely fluctuating loads, poor h.t. regulation, and mains variations can be accommodated. Each type of variation brings its own problems and no set rules are practicable.

February, 1962



Radiation Cooled Triode




All dimensions in mm.

Radiation Cooled Triode (AEI




CONSTANT CURRENT CHARACTERISTICS





CHARACTERISTIC CURVES: Va/Ig




August, 1962

Page 7, Issue 1



CHARACTERISTIC CURVES: Ia/Va





15J12 FORCED AIR COOLED TRIODE Directly heated

TENTATIVE

GENERAL

The 15J12 is a forced air cooled triode which has a directly heated thoriated tungsten filament. It is intended for use in r.f. heating equipment.

RATING

| Filament Voltage | Vf | 6.3 | V |
|---|------------------|-------|-------|
| Filament Current | lf | 32.5 | A |
| Maximum Anode Voltage | Va(max) | 7.0 | kV |
| Maximum Anode Dissipation | Pa(max) | 1.3 | kW |
| Minimum Air Flow for Maximum Anode Dissipation | | 60 ft | 3/min |
| Maximum Peak Cathode Current | ik(pk)max | 4.0 | A |
| Maximum Operating Frequency at Full Rating | f _{max} | 60 | Mc/s |

INTER-ELECTRODE CAPACITANCES

| Anode/Grid | ca-g | 11 | pF |
|----------------|------|-----|----|
| Grid/Filament | cg-f | 13 | pF |
| Anode/Filament | ca-f | 0.6 | pF |

CHARACTERISTICS

| Anode Voltage | Va | 4.0 kV |
|----------------------|-------|----------|
| Anode Current | la | 190 mA |
| Mutual Conductance | gm | 5-1 mA/V |
| Amplification Factor | μ | 22 |

February, 1962



15J12 FORCED AIR COOLED TRIODE Directly heated

TENTATIVE

TYPICAL OPERATION—Maximum operating conditions per valve

Class B1 audio amplifier—push-pull operation

| Class Di addio ampinio | don pan operation | | |
|----------------------------|-------------------|------|-----|
| Anode Voltage | V _a | 6.0 | kV |
| Anode Current R.M.S. | a(r.m.s.) | 0.6 | A |
| Power Input | Pin | 2.2 | kW |
| Power Output | Pout | 0.9 | kW |
| Anode Dissipation | Pa | 1.3 | kW |
| Anode Efficiency | | 40 | 9/6 |
| Negative Grid Bias Voltage | Vø | -225 | V |
| Peak Signal Voltage | Ysig(pk) | 225 | V |
| | | | |

TYPICAL OPERATION—Maximum operating conditions

Class C-single phase full wave (no smoothing)

| | | Mean | R.M.S. | Peak |
|---|--------|------|--------|--------|
| Anode Voltage | Va | 3.8 | 4.25 | 6.0 kV |
| Negative Grid Bias Voltage | Vg | -80 | | V |
| Positive Grid Voltage | Vsig | 154 | | V |
| Grid Resistance | Rg | 0.7 | | kΩ |
| Mean Anode Current | la(av) | 730 | | mA |
| Mean Grid Current | lg(av) | 120 | | mA |
| Peak Cathode Current | ik(pk) | 2.5 | 2.8 | 4-0 A |
| Peak Anode Current | ia(pk) | 1.9 | | A |
| Peak Grid Current | ig(pk) | 0.6 | | A |
| Anode Dissipation | Pa | 1.3 | | kW |
| Grid Drive Power | | 30 | | W |
| Grid Dissipation | Pg | 20 | | W |
| Anode Efficiency | | 61 | | % |
| Power Output (amplifier) | Pout | 2.1 | | kW |
| Power Output (oscillator) at 100% Transfer Efficiency | Pout | 2.1 | | kW |
| Power Output (oscillator) at 85% Transfer Efficiency | Pout | 1.8 | | kW |

February, 1962



FORCED AIR COOLED TRIODE Directly heated

TENTATIVE

TYPICAL OPERATION—Maximum operating conditions

Class C-3-phase rectified or d.c.

| Anode Voltage | V_a | 4.0 | 5.0 | 6.0 | kV |
|-----------------------------|--------|------|------|------|----|
| Negative Grid Bias Voltage | Vg | -140 | -220 | -300 | V |
| Positive Grid Voltage | Vsig | 270 | 270 | 270 | V |
| Grid Resistance | Rg | 553 | 982 | 1400 | Ω |
| Mean Anode Current | la(av) | 1068 | 993 | 930 | mA |
| Mean Grid Current | lg(av) | 253 | 224 | 204 | mA |
| Peak Cathode Current | ik(pk) | 4.0 | 4.0 | 4.0 | A |
| Peak Anode Current | ia(pk) | 3.0 | 3.0 | 3.0 | Α |
| Peak Grid Current | ig(pk) | 1.0 | 1.0 | 1.0 | A |
| Anode Dissipation | Pa | 1.3 | 1.3 | 1.3 | kW |
| Grid Drive Power | | 104 | 100 | 108 | W |
| Grid Dissipation | Pg | 60 | 50 | 48 | W |
| Anode Efficiency | . 0 | 69 | 73 | 76 | % |
| Power Output (amplifier) | Pout | 2.9 | 3.6 | 4.2 | kW |
| Power Output (oscillator) | | | | | |
| at 100% Transfer Efficiency | Pout | 2.8 | 3.5 | 4.1 | kW |
| Power Output (oscillator) | | | | | |
| at 85% Transfer Efficiency | Pout | 2.4 | 3.0 | 3.5 | kW |
| | | | | | |

DIMENSIONS

| Maximum | Overall Length | 200 | mm |
|---------|----------------|-----|----|
| Maximum | Diameter | 102 | mm |

MOUNTING POSITION—Vertical, anode upwards

ANODE-External

BASE-Special

February, 1962

I5JI2 FORCED AIR COOLED TRIODE Directly heated

TENTATIVE

OPERATING INSTRUCTIONS

Installation

The valve should be mounted vertically with anode upwards. Connections should always make good electrical contact to prevent overheating of pins and seals, particularly by r.f. current.

It is essential that connection be made to both grid pins when running at higher frequencies, to reduce current taken by each pin.

The valve must be protected against excessive vibration and shock.

Cooling

A minimum forced air blast of 60 cu.ft/min, directed horizontally at the anode, is required when running this valve.

At higher frequencies, etc. a low velocity air blast directed on to the filament and grid pins is recommended.

Operation

The operating data list conditions for maximum output for respective classes of service at the relevant anode voltage.

Linear interpolation between anode voltage steps is admissible. As these conditions utilize some or all of the maximum valve ratings, close control of conditions has to be maintained. In Class C self oscillator service precautions should be taken against excessive mains voltage variations. Current overload trips should be included in anode and grid circuits as well as an under current trip in the grid circuit.


In industrial r.f. heating it is not usual that all precautions can be taken, and under these conditions some reductions in operating conditions have to be made so that widely fluctuating loads, poor h.t. regulation, and mains variations can be accommodated. Each type of variation brings its own problems and no set rules are practicable.



15J12


FORCED AIR COOLED TRIODE Directly heated

TENTATIVE



All dimensions in mm.

February, 1962





15P12

WATER COOLED TRIODE

TENTATIVE

GENERAL

The 15P12 is a Water Cooled Triode with a directly heated thoriated tungsten filament. It is intended for use in R.F. heating equipment.

RATING—Absolute Values

| Filament Voltage | Vf | 5 | V |
|---------------------------|---------|-------------|-------|
| Filament Current | lf . | 32.5 | A |
| Maximum Anode Voltage | Va(max) | 7 | kV |
| Maximum Anode Dissipation | Pa(max) | 65 0 | W |
| Minimum Water Flow for | | | |
| Maximum Anode Dissipation | | 1 | L/min |
| Maximum Water Outlet | | | |
| Temperature | | 55 | oC |

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid | ca-g1 | 10.5 |
|----------------|-------|------|
| Grid/Filament | cg1-f | 11 |
| Anode/Filament | Ca-f | 0.5 |

DIMENSIONS

| Maximum Overall Length | 180 | mm |
|--------------------------|-----|----|
| Maximum Diameter (Glass) | 80 | mm |

MOUNTING POSITION-Vertical, base down.

CHARACTERISTICS

| Anode Voltage | Va | 4 k1 | 1 |
|----------------------|-------|---------|---|
| Anode Current | la | 120 m/ | 4 |
| Mutual Conductance | gm | 3-3mA/V | |
| Amplification Factor | μ | 21 | |


ANODE-External

BASE—Special

December, 1961

I5P12 WATER COOLED TRIODE

TENTATIVE



All dimensions in millimetres unless otherwise shown.

December, 1961



GENERAL

The 15P12 is a water cooled triode with a directly heated thoriated tungsten filament. It is intended for use in r.f. heating equipment.

RATINGS*

| Filament voltage | V_{f} | 5.0 | V |
|--|---------------------|------|-------|
| Filament current | l _f | 32.5 | A |
| Maximum anode voltage | V _{a(max)} | 7.0 | kV |
| Maximum anode dissipation | Pa(max) | 650 | W |
| Minimum water flow for maximum anode dissipation | () | 1 | L/min |
| Maximum water outlet temperature | | 55 | °C |
| Maximum peak cathode current | ik(pk)max | 3.0 | . A |
| Maximum operating frequency at full ratings | fmax | 60† | Mc/s |
| | | | |

^{*} Limiting values are absolute maximum values.

INTER-ELECTRODE CAPACITANCES

| Anode/grid Grid/filament Anode/filament | C _{a-g} C _{g-f} C _{a-f} | 10·5 11 0·5 | pF pF |
|---|--|-------------------|----------|
| | -4-1 | | - |

CHARACTERISTICS

| Anode voltage | Tegs. | 2 | Va | 4.0 | kV |
|----------------------|-------|---------|----------------|-----|------|
| Anode current | - 1 | C. Sand | l _a | 120 | mA |
| Mutual conductance | | | gm | 3.3 | mA/V |
| Amplification factor | | | μ | 21 | |

TYPICAL OPERATION—Maximum operating conditions per valve Class B1 audio amplification—push-pull operation.

| Maximum anode voltage | | Va | 6.0 | kV |
|-----------------------|------------|------------|------|----|
| Anode current r.m.s. | | la(r.m.s.) | 0.3 | A |
| Power input | | Pin | 1.2 | kW |
| Power output | X 1100 100 | Pout | 0.6 | kW |
| Anode dissipation | | Pa | 0.6 | kW |
| Anode efficiency | | | 50 | % |
| Bias voltage | | Vg | -220 | V |
| Peak signal voltage | | Vsig(pk) | 220 | V |

August, 1962 Page 1, Issue 1

Tel: GERrard 9797

[†] Limited by water connections to 10 Mc/s.



TYPICAL OPERATION—Maximum operating conditions Class C—3-phase full-wave rectified or d.c.

| Anode voltage | V_a | 4.0 | 5.0 | 6.0 | kV |
|-----------------------------|--------------------|------|-------|------|----|
| Bias voltage | Vg | -220 | -300 | -400 | V |
| Positive grid voltage | Vsig | 280 | 280 | 280 | v |
| Grid resistor | Rg | 1.75 | - 1.9 | 3.1 | kΩ |
| Mean anode current | I _{a(av)} | 620 | 600 | 550 | mA |
| Mean grid current | $I_{g(av)}$ | 130 | 160 | 130 | mA |
| Peak cathode current | ik(pk) | 3.0 | 3.0 | 3.0 | A |
| Peak anode current | ia(pk) | 2.0 | 2.0 | 2.0 | A |
| Peak grid current | ig(pk) | 1.0 | 1.0 | 1.0 | A |
| Anode dissipation | Pa | 630 | 640 | 650 | W |
| Grid drive power | | 60 | 85 | 85 | W |
| Grid dissipation | Pg | 28 | 38 | 30 | W |
| Anode efficiency | | 75 | 78 | 80 | % |
| Power output (amplifier) | Pout | 1.8 | 2.3 | 2.65 | kW |
| Power output (oscillator) | | | | | |
| at 100% transfer efficiency | Pout | 1.7 | 2.2 | 2.6 | kW |
| Power output (oscillator) | | | | | |
| at 85% transfer efficiency | Pout | 1.5 | 1.9 | 2.2 | kW |

TYPICAL OPERATION—Maximum operating conditions Class C—single-phase full-wave rectified (no smoothing).

| | | Mean | R.M.S. | Peak | |
|-----------------------------|------------------------------------|------|--------|------|----|
| Anode voltage | V_a | 3.8 | 4.25 | 6.0 | kV |
| Bias voltage | V _g V _{sig} | -140 | | | V |
| Positive grid voltage | Vsig | 184 | | | V |
| Grid resistor | Rg | 1.6 | | | kΩ |
| Mean anode current | I _{a(av)} | 460 | | | mA |
| Mean grid current | Ig(av) | 89 | | | mA |
| Peak cathode current | ik(pk) | 1.9 | 2.1 | 3.0 | A |
| Peak anode current | ia(pk) | 1.4 | | | A |
| Peak grid current | ig(pk) | 0.5 | | | A |
| Anode dissipation | Pa | 650 | | | W |
| Grid drive power | | 23 | | | W |
| Grid dissipation | Pg | 7 | | | W |
| Anode efficiency | | 70 | | | % |
| Power output (amplifier) | Pout | 1.5 | | | kW |
| Power output (oscillator) | | | | | |
| at 100% transfer efficiency | Pout | 1.5 | | | kW |
| Power output (oscillator) | | | | | |
| at 85% transfer efficiency | Pout | 1.3 | | | kW |
| | | | | | |

MOUNTING POSITION—Vertical, anode upwards

ANODE—External

BASE-Special

OPERATING INSTRUCTIONS

Installation

This valve should be mounted vertically with anode upwards. Connections should always make good electrical contact to prevent overheating of pins and seals, particularly by r.f. currents.

It is essential that connection be made to both grid pins when running at high frequencies, to reduce current taken by each pin.

The valve must be protected against excessive vibration and shock.

Cooling

Water cooling is required for all conditions of service including filament dissipation alone.

The minimum water flow for maximum output is 1 litre/min. The hose connecting the water supply to the valve should not be less than 20 ft long, this also applies to the return hose. Lengths shorter than 20 ft. will result in loss of power.

Cold water should be fed into the lower end of the copper spiral and the outlet temperature from the top of the spiral must not exceed 60°C .

A low velocity air blast directed on filament and grid pins is recommended when running at full power at the higher frequencies.

Operation

The operating data, list conditions for maximum output for respective classes of service at the relevant anode voltage.


Linear interpolation between anode voltage steps is admissible. As these conditions utilize some or all of the maximum valve ratings, close control of conditions has to be maintained.

In Class C Self Oscillator service precautions should be taken against excessive mains voltage variation. Current overload trips should be included in anode and grid circuits as well as an under current trip in the grid circuit.

In industrial r.f. heating it is not usual that all precautions can be taken, and under these conditions, some reductions in operating conditions have to be made so that widely fluctuating loads, poor h.t. regulation and mains variations can be accommodated. Each type of variation brings its own problems and no set rules are practicable.


Page 3, Issue 1





All dimensions in millimetres unless otherwise shown.


CONSTANT CURRENT CHARACTERISTICS





WATER FLOW/DISSIPATION CHART

TEMPERATURE DIFFERENCE BETWEEN OUTGOING AND INCOMING WATER (°C)





15V12

VAPOUR COOLED TRIODE

Directly heated

TENTATIVE

GENERAL

The 15V12 is a directly heated vapour cooled triode intended for use in r.f. heating equipment. It has a thoriated tungsten filament and a maximum operating frequency at full ratings of 60 Mc/s.

| Filament Voltage | Vf | 6.3 | V |
|---|---------|------|------|
| Filament Current | lf. | 32.5 | A |
| Maximum Anode Voltage | Va(max) | 7.0 | kV |
| Maximum Anode Dissipation | Pa(max) | 1.3 | kW |
| Maximum Operating Frequency at Full Ratings | f(max) | 60 | Mc/s |

INTER-ELECTRODE CAPACITANCES

| Grid/Filament | cg-f | 13 pF |
|----------------|------|--------|
| Anode/Grid | ca-g | 11 pF |
| Anode/Filament | ca-f | 0.6 pF |

CHARACTERISTICS

| Anode Voltage | V_a | 4.0 | kV |
|----------------------|-------|-----|------|
| Anode Current | la | 190 | mA |
| Mutual Conductance | gm | 5.1 | mA/V |
| Amplification Factor | μ | 22 | |

TYPICAL OPERATION—Maximum operating conditions per valve

Class B1 audio amplifier—push pull operation

| Anode Voltage | | Va | 6.0 | kV |
|----------------------------|--|-----------|------|-----|
| Anode Current R.M.S. | | a(r.m.s.) | 0.6 | . A |
| Power Input | | Pin | 2.2 | kW |
| Power Output | | Pout | 0.9 | kW |
| Anode Dissipation | | Pa | 1.3 | kW |
| Anode Efficiency | | | 40 | % |
| Negative Grid Bias Voltage | | Vg | -225 | V |
| Peak Signal Voltage | | Vsig(pk) | 225 | V |

February, 1962



15V12

VAPOUR COOLED TRIODE

Directly heated

TENTATIVE

TYPICAL OPERATION—Maximum operating conditions

Class C-single phase full wave (no smoothing) Mean R.M.S. Peak 3.8 4-25 6.0 Anode Voltage kV Vg Vsig Negative Grid Bias Voltage -80 Positive Grid Voltage 154 V Grid Resistance Rg 0.7 kΩ Mean Anode Current 730 la(av) mA Mean Grid Current 120 mA g(av) Peak Cathode Current 2.5 ik(pk) Peak Anode Current 1.9 A ia(pk) Peak Grid Current 0.6 A ig(pk) Anode Dissipation Pa 1.3 kW Grid Drive Power 30 W Grid Dissipation 20 W Pg Anode Efficiency 61 Power Output (amplifier) Power Output (oscillator) Pout 2.1 at 100% Transfer Efficiency 2.1 kW Pout Power Output (oscillator) at 85% Transfer Efficiency Pout 1.8 kW

TYPICAL OPERATION—Maximum operating conditions

Class C-3-phase rectified or d.c.

| Anode Voltage | Va | 4.0 | 5.0 | 6.0 | kV |
|-----------------------------|------------|------|------|------|-----|
| Negative Grid Bias Voltage | Vg | -140 | -220 | -300 | V |
| Positive Grid Voltage | Vg Vsig | 270 | 270 | 270 | V |
| Grid Resistance | Rg | 553 | 982 | 1400 | Ω |
| Mean Anode Current | la(av) | 1068 | 993 | 930 | mA |
| Mean Grid Current | lg(av) | 253 | 224 | 204 | mA |
| Peak Cathode Current | ik(pk) | 4.0 | 4.0 | 4.0 | A |
| Peak Anode Current | ia(pk) | 3.0 | 3.0 | 3.0 | A |
| Peak Grid Current | ig(pk) | 1.0 | 1.0 | 1.0 | A |
| Anode Dissipation | Pa | 1.3 | 1.3 | 1.3 | kW |
| Grid Drive Power | Fa | 104 | 100 | 108 | W |
| Grid Dissipation | Pg | 60 | 50 | 48 | W |
| Anode Efficiency | r B | 69 | 73 | 76 | % |
| Power Output (amplifier) | Pout | 2.9 | 3-6 | 4.2 | kW |
| Power Output (oscillator) | · Out | - / | | 4.2 | KTT |
| at 100% Transfer Efficiency | Pout | 2.8 | 3.5 | 4-1 | kW |
| Power Output (oscillator) | · Out | | | 7. | KTT |
| at 85% Transfer Efficiency | Pout | 2.4 | 3.0 | 3.5 | kW |
| | | | | | |

February, 1962



15V12

VAPOUR COOLED TRIODE

Directly heated

TENTATIVE

DIMENSIONS

Maximum overall length Maximum diameter 200 mm 80 mm

MOUNTING POSITION—Vertical, base up

BASE-Special

Operating Instructions

Installation

The valve should be mounted vertically with anode downwards in a specially designed boiler (type LM287). Connections should always make good electrical contact to prevent overheating of pins and seals, particularly by r.f. current.

It is essential that connections be made to both grid pins when running at higher frequencies so as to reduce current taken by each pin.

Cooling

The valve is immersed in water and at the higher frequencies, a low velocity air blast must also be directed on to the filament and grid pins.

Operation

The operating data list conditions for maximum output for respective classes of service at the relevant anode voltage.

Linear interpolation between anode voltage steps is admissible. As these conditions utilize some or all of the maximum valve ratings, close control of conditions has to be maintained. In Class C self oscillator service precautions should be taken against excessive mains voltage variations. Current overload trips should be included in anode and grid circuits as well as an under current trip in the grid circuit.

In industrial r.f. heating it is not usual that all precautions can be taken, and under these conditions some reductions in operating conditions have to be made so that widely fluctuating loads, poor h.t. regulation, and mains variations can be accommodated. Each type of variation brings its own problems and no set rules are practicable.

February, 1962

. . .

SCIONT CALDED RUDAN A MARKA (MARKA (MARKA)

DISCUSSION OF THE

5.41

STATE OF THE PARTY OF THE PARTY

20.00

the state of the s

margin at the second of the se

AND AND THE STATE OF THE STATE

TENTATIVE

GENERAL

The 16J12 is a directly heated forced air cooled triode. It has a thoriated tungsten filament and is intended for use in transmitting equipment. The filament is suitable for direct switching.

RATINGS

| Filament voltage | V_{f} | 8.0 | -5% V |
|------------------------------|----------------|-----|-------|
| Filament current | I _f | 26 | A |
| Maximum d.c. anode voltage | $V_{a(max)}$ | 7.5 | kV |
| Maximum peak cathode current | ik(pk)max | 6-0 | A |
| Maximum anode dissipation | Pa(max) | 3.0 | kW |
| Maximum operating frequency | fmax | 40 | Mc/s |

MOUNTING POSITION—Vertical, base upwards

CHARACTERISTICS


| Anode voltage | \vee_a | 7 kV |
|----------------------|----------|----------|
| Anode current | la | 400 mA |
| Mutual conductance | gm | 6.5 mA/V |
| Amplification factor | μ | 55 |


ANODE-External

BASE—Special

Forced Air Cooled Triode (AEI







All dimensions in millimetres unless otherwise shown



WATER COOLED TRIODE

Directly heated

TENTATIVE

GENERAL

The 16P12 is a directly heated, water cooled triode with integral cooling. It has a thoriated tungsten filament and is intended for use in induction heating equipment. The filament is suitable for direct switching.

RATING

| Filament Voltage | Vf | 8.0±5% V |
|--------------------------------|---------------------|----------|
| Filament Current | lf. | 26-0 A |
| Maximum d.c. Anode Voltage | V _{a(max)} | 8.0 kV |
| Maximum Peak Cathode Current | ik(pk)max | 6-0 A |
| Maximum Anode Dissipation | Pa(max) | 3-0 kW |
| Maximum Operating Frequency | | |
| (Limited by water connections) | f(max) | 10 Mc/s |
| (Limited by valve) | f(max) | 40 Mc/s |

INTER-ELECTRODE CAPACITANCES

| Anode/Grid | ca-g | 11.5 pF |
|----------------|------|---------|
| Grid/Filament | cg-f | 14-5 pF |
| Anode/Filament | ca-f | 0.8 pF |

CHARACTERISTICS

| Anode Voltage | V_a | 5.0 | k٧ |
|----------------------|-------|--------|----|
| Anode Current | la | 400 m | nΑ |
| Mutual Conductance | 8m | 7-5 mA | /٧ |
| Amplification Factor | 14 | 24 | |

DIMENSIONS

| Maximum | Overall | length | 211 mm |
|---------|---------|--------|--------|
|---------|---------|--------|--------|

MOUNTING POSITION—Vertical, base upwards

ANODE-External

BASE-Special


February, 1962



WATER COOLED TRIODE

Directly heated

TENTATIVE



February, 1962




WATER COOLED TRIODE

Directly heated

TENTATIVE

CHARACTERISTIC CURVES: Vg/Va
CONSTANT CURRENT CHARACTERISTICS




February, 1962

WATER COOLED TRIODE

Directly heated

TENTATIVE

WATER FLOW/DISSIPATION CHART



February, 1962



3R/167E

16P13

WATER COOLED TRIODE

Directly heated

TENTATIVE

GENERAL

The 16P13 is a directly heated Water Cooled Triode with integral cooling and union connectors. It is intended for use as an R.F. Oscillator in eddy current heating apparatus, etc. This valve is the water cooled version of the ESA1500 and is identical to the 16P12 except that it has unions attached to the ends of the water cooling tube. The thoriated tungsten filament is suitable for direct switching.

RATING

| Filament Voltage | Vf | 8·0±5% | V |
|--|---------------------|--------|------|
| Filament Current | l _f | 26 | A |
| Maximum Anode Voltage (D.C.) | V _{a(max)} | 8 | kV |
| Maximum Peak Cathode Current | k(pk)ma | x 6 | Α |
| Maximum Anode Dissipation | Pa(max) | | kW |
| Maximum Operating Frequency (Limited by water connections) | f(max) | 10 | Mc/s |
| Maximum Operating Frequency (Limited by valve) | f(max) | 40 | Mc/s |

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid | ca-g | 11.5 |
|----------------|------|------|
| Anode/Filament | ca-f | 0.8 |
| Grid/Filament | Cg-f | 14-5 |

DIMENSIONS

| Maximum Overa | Il Length | 211 | mm |
|---------------|-----------|-----|----|
| Haximum Overa | II Length | 411 | |

UNION CONNECTORS—to suit 1 o.d. Tube to BS2051.

MOUNTING POSITION—Vertical with base up.

Electronic Components Division Tel.: GERrard 9797



I6PI3 WATER COOLED TRIODE Directly heated TENTATIVE

CHARACTERISTICS

| Anode Voltage | Va | 5 kV |
|----------------------|----|---------|
| Anode Current | la | 400 mA |
| Mutual Conductance | 8m | 7.5mA/V |
| Amplification Factor | μ | 24 |

ANODE-External.


BASE-Special.




WATER COOLED TRIODE

Directly heated

TENTATIVE



February, 1962





ES833

RADIATION COOLED TRIODE

GENERAL.

The ES.833 is a high mu triode particularly suitable for use as an R.F. Power Amplifier, Oscillator or Class B modulator.

The anode and grid connections are brought out at the top and are taken through metal to glass seals to heavy current terminals. As a result of this construction the value is exceptionally efficient at higher radfo frequencies and may be operated under class 'C' CW conditions at a maximum input of 1.8 kW at frequencies up to 30Mcs, with forced air cooling. At reduced input rating it is possible to operate the valve as high as 75Mcs.

RATING

Filament Voltage (volts) ٧r 10.0 Filament Current (amps) Ir 10.0 Maximum Anode Voltage (volts) Va(max) • 3,000 Maximum Anode Dissipation (watts) Wa(max) • 300 Amplification Factor 35 Maximum Operating Frequency at Full Rating \$ 30 Mc/8

- The Maximum Anode Voltage may be increased to 4,000v, and the Anode dissipation to 400w providing the valve is forced-air cooled at a rate of 40 cu.ft/min., on top of bulb between anode and grid seals, directed through a 2" nozzle.
- \$ At higher frequencies the maximum permissible anode voltages and inputs must be reduced.

INTER-ELECTRODE CAPACITANCES

Anode/Grid (µµF) Ca-gl 6.3 Anode/Filament (µµF) 8.5 Ca-f Grid/Filament (µµF) 12.3 81-1

DIMENSIONS

8.812 ins Maximum Overall Length Maximum Diameter Approximate Nett Weight 4.594 ins : 116 mm Approximate Nett Weight (1bs) Approximate Packed Weight (1bs) 31


MOUNTING POSITION - Vertical

Indicates a change -Issue 1, Page 1

December, 1961

ES833

RADIATION COOLED TRIODE



December, 1961


Indicates a change
Issue 1, Page 2

Associated Electrical Industries Limited



ES833 RADIATION COOLED TRIODE


AVERAGE CHARACTERISTIC CURVES ANODE CURRENT IN AMPS





ES833
RADIATION COOLED TRIODE

AVERAGE CHARACTERISTIC CURVES: Ig/Va





ESA1002

FORCED AIR COOLED TRIODE

GENERAL

The ESA1002 is a forced air cooled triode having a directly heated thoriated tungsten filament. It has a maximum anode dissipation of 12 kW and a maximum anode voltage rating of 10 kV, the maximum operating frequency at full rating being 40 Mc/s.

RATING

| Filament Voltage | (volts) | Vf | 8.0 |
|--|---------|-----------------------|------|
| Filament Current | (amps) | lf | 124 |
| Maximum Anode Voltage | (kV) | $V_{a(max)}$ | 10.0 |
| Maximum Anode Dissipation | (kW) | Pa(max) | 12.0 |
| Maximum Cathode Current (Peak) | (amps) | l _{k(max)pk} | 33-0 |
| Maximum Grid Dissipation | (watts) | Pg(max) | 800 |
| Mutual Conductance | (mA/V) | gm | 35 |
| Amplification Factor | | μ | 28 |
| Anode Impedance | (ohms) | ra | 800 |
| Maximum Operating Frequency (full rating) | (Mc/s) | f(max) | 40 |
| Maximum R.F. Power Output | (kW) | Pout | 35 |
| | | | |

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid | ca-g1 | 40 |
|----------------|-------|-----|
| Anode/Filament | ca-f | 1.3 |
| Grid/Filament | cg1-f | 56 |

December, 1961 Issue 1, Page 1

Electronic Components Division
Tel.: GERrard 9797



EDISWAN

ESA1002


FORCED AIR COOLED TRIODE

AIRFLOW-400 cu. ft. min.

DIMENSIONS Maximum Overall Length (ins) 1358 Maximum Diameter (ins) 716 Approximate Nett Weight (lbs) 28 Approximate Packed Weight (lbs) 84



ESA1002 FORCED AIR COOLED TRIODE




All dimensions in mm unless stated otherwise.

ESA1002

FORCED AIR COOLED TRIODE

TYPICAL CHARACTERISTIC CURVES: Ia/Va






ESA1002

FORCED AIR COOLED TRIODE

TYPICAL CHARACTERISTIC CURVES: Ig/Va







1001/425

RECUIT DESCRIPTION FOR QUE CO.

No.

GENERAL

The ESA1500 is a forced air cooled triode having a directly heated thoriated tungsten filament. It is intended for use in induction and dielectric heating equipment.

RATINGS*

| Filament voltage | V_{f} | 8.0 | V |
|--|-----------------------|-----|----------------------|
| Filament current | If | 26† | Α |
| Maximum anode voltage | $V_{a(max)}$ | 6.0 | kV |
| Maximum anode dissipation | Pa(max) | 3.0 | kW |
| Maximum peak cathode current | i _{k(pk)max} | 6.0 | Α |
| Maximum operating frequency at maximum ratings | f_{max} | 40 | Mc/s |
| Minimum air flow for maximum dissipation | | 300 | ft ³ /min |

^{*} Limiting values are absolute values.

INTER-ELECTRODE CAPACITANCES

| Anode/grid | C _{a-g} | 11.5 | pF |
|----------------|------------------|------|----|
| Anode/filament | C _{a-f} | 8.0 | pF |
| Grid/filament | c _{g-f} | 14.5 | pF |

CHARACTERISTICS

| Anode voltage | V_a | 5.0 | kV |
|----------------------|----------------|------|----------------------|
| Anode current | l _a | 400 | mA |
| Anode impedance | ra | 3.2 | kΩ |
| Mutual conductance | gm | 7.5 | mA/V |
| Amplification factor | μ | 24 | |
| Perveance | | 0.56 | $mA/V^{\frac{3}{2}}$ |

COOLING

This is by forced air blast, and should be employed for all conditions of valve service, including filament dissipation only.

It is recommended that a minimum air flow of 300 $\rm ft^3/min$ at maximum power output be used. Direction of flow is through the anode cooler and over the glass bulb.

At the higher frequencies grid connectors should be designed to assist cooling, and both connections should be made to reduce the current taken by each pin.

Care should be taken to ensure all connections to the valve make good electrical contact to avoid overheating pins and seals.

August, 1962 Page 1, Issue 1
Associated Electrical Industries Limited

[†] The filament is suitable for direct switching without additional current limitation in the circuit.



TYPICAL OPERATION (See "Notes" below)

| Anode voltage | V_a | 5-0 | 6.0 | kV |
|---|--------------------|------|------|----|
| Mean anode current | la(av) | 1.55 | 1.5 | Α |
| Mean grid current | $I_{g(av)}$ | 145 | 135 | mA |
| Bias voltage | Vg | 250 | 350 | V |
| Bias resistor | Rg | 1.75 | 2.6 | kΩ |
| Peak cathode current | i _{k(pk)} | 6.0 | 6.0 | Α |
| Peak anode current | i _{a(pk)} | 5.0 | 5.0 | Α |
| Peak grid current | i _{g(pk)} | 1.0 | 1.0 | Α |
| Anode dissipation | Pa | 2.5 | 2.5 | kW |
| Grid dissipation | Pg | 70 | 65 | W |
| Anode efficiency | | 69 | 72 | % |
| Power output (oscillator) | Pout | 5.3 | 6.3 | kW |
| Power output at 85% transfer efficiency | Pout | 4.5 | 5.35 | kW |

NOTES

The typical operating conditions given, are for valve service as a class C self oscillator and are calculated assuming a d.c. or three-phase full-wave rectified anode voltage. Where conditions of service make the valve liable to excessive mains variation, poor regulation of supplies, or power supplies with a high peak to mean ratio, care should be taken to see that the limiting values are not exceeded.

It is recommended that a protective resistance of $10\Omega/kV$ be connected between the h.t. supply and the valve anode to avoid damage to the valve in the event of intermittent flash over.

Some cases (e.g., intermittent operation where the duty factor is suitable) allow increased anode dissipation and peak cathode current. Each case should be treated on its merits and more information on this type of duty may be had on request.

MOUNTING POSITION—Vertical, anode down

BASE-Special



ESA5000

FORCED AIR COOLED TRIODE

(Previously EHA.5000)

GENERAL

The ESA5000 is a three electrode valve designed for use as a Radio Frequency Amplifier or Oscillator. The anode is fitted with a special radiator and cooling is obtained by forced air. The design minimises lead inductance and this valve is particularly suitable for use in R.F. heating equipments. It is the direct equivalent of the American type 889R.

RATING

| Filament Voltage (volts) | Vf | 11.0 |
|----------------------------------|--------------|-----------|
| Filament Current (amps) | lf. | 125 |
| Maximum Anode Voltage (volts) | Va(max) | 8,500 |
| Maximum Filament Emission (amps) | Fem | 9 - |
| Maximum Anode Dissipation (kW) | $W_{a(max)}$ | 5.0 |
| Mutual Conductance (mA/V) | gm | * 10 |
| Amplification Factor | μ | * 20 |
| Anode Impedance (ohms) | ra | *2,000 |
| Maximum Operating Frequency at | | |
| full rating | | † 25 Mc/s |

^{*} Taken at $V_a = 5,000v$; $I_a = 1,000mA$.

INTER-ELECTRODE CAPACITANCES

| Anode/Grid | $(\mu\mu F)$ | ca-gl | 20.7 |
|----------------|--------------|------------------|------|
| Anode/Filament | $(\mu\mu F)$ | ca-f | 2.5 |
| Grid/Filament | $(\mu\mu F)$ | g _{I-f} | 19-5 |

AIR FLOW (MAIN)

500 cubic feet per minute. In addition, 15 cubic feet per minute should be directed on to the seals.

DIMENSIONS

| Maximum Overall Length | (mm) | 298-5 |
|--------------------------|-----------|-------|
| Maximum Diameter | (mm) | 192-0 |
| Approximate Nett Weight | (lbs) | 34.0 |
| Approximate Packed Weigh | tht (lbs) | 72.0 |


MOUNTING POSITION—Vertical.

Indicates a change

[†] At higher frequencies the maximum permissible anode voltages and inputs must be reduced.



FORCED AIR COOLED TRIODE (Previously EHA.5000)



ALL DIMS IN ins UNLESS STATED OTHERWISE


December, 1961

Issue 1, Page 2



ESA5000 FORCED AIR COOLED TRIODE

SUPPORT TYPE G.C.4.



NOTE THIS SUPPORT IS USED WHEN VALVE IS OPERATED
IN AN INVERTED POSITION

ALL DIMS IN ins UNLESS STATED OTHERWISE


December, 1961

Issue 1, Page 3



ESA5000 FORCED AIR COOLED TRIODE

SUPPORT TYPE G.C.3.



ALL DIMS. IN ins UNLESS STATED OTHERWISE


December, 1961

Issue 1, Page 4



FORCED AIR COOLED TRIODE (Previously EHA5000)


AVERAGE CHARACTERISTIC CURVES: I_a/V_a (V_f =11 Volts A.C.)



December, 1961 Issue 1, Page 5

FORCED AIR COOLED TRIODE (Previously EHA5000)

CHARACTERISTIC CURVES: Ig/Va (Vf=11 Volts A.C.)




December, 1961

Issue 1, Page 6 :



FORCED AIR COOLED TRIODE (Previously EHA5000)


AVERAGE CHARACTERISTIC CURVE: I_f/V_f (Cold resistance=0.0003 Ω)



December, 1961

FORCED AIR COOLED TRIODE (Previously EHA5000)

CHARACTERISTIC CURVE: Iem/Vf



Electronic Components Division Tel.: GERrard 9797



VAPOUR COOLED TRIODE

GENERAL

The ESV1002 is a Vapour Cooled Triode having a directly heated thoriated tungsten filament. It has a maximum anode dissipation of 25 kW, and a maximum anode voltage rating of 10 kV, the maximum operating frequency at full rating being 10 Mc/s.

RATING

| Filament Voltage | (volts) | Vf | 8.0 |
|----------------------------|----------|--------------|-------|
| Filament Current | (amps) | lf | 124 |
| Maximum Anode Voltage | (kV) | Va(max) | 11† |
| Maximum Grid Bias Voltage | (volts) | Vg1 - | 1200† |
| Maximum Anode Dissipation | (kW) | Pa(max) | 25† |
| Maximum Cathode Current | (amps) | k(max) | 33† |
| Maximum Grid Dissipation | (watts) | Pg(max) | 800† |
| Mutual Conductance | (mA/V) | gm | 35 |
| Amplification Factor | | μ | 28 |
| Anode Impedance | (ohms) | ra | 800 |
| Maximum Operating Frequenc | y (Mc/s) | f(max) (abs) | 10* |
| Maximum R. F. Power Output | (kW) | Pout | 60 |

^{*} Limited by the boilers and boiler's condensers.

INTER-ELECTRODE CAPACITANCES (pF)

Approximate Nett Weight

Approximate Packed Weight

The maximum operating frequency may not be increased by operation at reduced ratings.

[†] Absolute maximum values which must not be exceeded.

| Anode/Grid | ca-g1 | 40 |
|------------------------|-------|-----|
| Anode/Filament | ca-f | 1.3 |
| Grid/Filament | cg1-f | 56 |
| DIMENSIONS | | |
| Maximum Overall Length | (ins) | 14 |
| Maximum Diameter | (ins) | 61 |

December, 1961 Issue 1, Page 1

(lbs)

(lbs)

36



VAPOUR COOLED TRIODE


| TYPICAL OPER | ATION— Oscill | | R.F. Ar | nplifier | and |
|---|---------------------------------------|------------|---------|----------|-------|
| Anode Voltage | (kV) | Va | 6 | 8 | 10 |
| Grid Bias Voltage | (volts) | Vg1 - | -300 - | -400 - | -450 |
| Grid Positive Voltage (Peak) | (volts) | Vg1(pk) | +520 + | - 520 - | - 520 |
| Grid Bias Resistor | (ohms) | Rg1 | 254 | 380 | 455 |
| Mean Anode Current | (amps) | la | 7-62 | 7-2 | 7-68 |
| Mean Grid Current | (amps) | lg1 | 1.18* | 1-06* | 0-99* |
| Grid Drive r.m.s. Voltage | (volts) | Vg1(rms) | 580 | 650 | 685 |
| Peak Cathode Current | (amps) | lk(pk) | 33 | 33 | 33 |
| Anode Dissipation | (kW) | Pa | 11-6 | 12-1 | 16.4 |
| Grid Drive Power | (watts) | Pdr | 870* | 875* | 860* |
| Grid Dissipation | (watts) | Pg1 | 516* | 453* | 415* |
| Anode Efficiency | % | ηa | 76-4 | 78-6 | 78-6 |
| Anode Output (Amplifier) | (kW) | Pout | 35 | 45-4 | 60-4 |
| Anode Output (Oscillator) | (kW) | Pout | 29 | 37-8 | 50-5 |
| Angle of Anode Current flow | (degrees) | θ_a | 163 | 162 | 166 |
| Minimum Convection Cooler area | on (sq. ft.) | | 9-8 | 10-2 | 13-4 |
| Minimum Water Flow (Water Cooled Types) | (litres/min at 20°C inlet temp. | .) | 4 | 4-1 | 5-4 |

^{*} Approximate values. With lamps as the grid resistor and normal HT regulation, grid dissipation should not rise by more than 25% at \(\frac{1}{8} \) full load anode current.

See "Application Notes on the use of Vapour Cooled Valves."



VAPOUR COOLED TRIODE




All dimensions in mm. unless stated otherwise

December, 1961



VAPOUR COOLED TRIODE


TYPICAL CHARACTERISTIC CURVES: Ia/Va





VAPOUR COOLED TRIODE

TYPICAL CHARACTERISTIC CURVES: Ig/Va



Ct 1733

TOTAL STREET, STREET,

Court French

tally selected to



ESVI500 VAPOUR COOLED TRIODE

GENERAL

The ESV1500 is a Vapour Cooled Triode, having a directly heated thoriated tungsten filament. It has a maximum anode dissipation of 5 kW and a maximum anode voltage rating of 8 kV, the maximum operating frequency at full rating being 10 Mc/s.

| RATING | | | |
|--|----------|------------|---------|
| Filament Voltage | (volts) | Vf | 8-0 |
| Filament Current | (amps) | If | 26-0 |
| Maximum Anode Voltage | (kV) | Va(max) | 8.0 |
| Maximum Anode Dissipation | (kW) | Pa(max) | 5.0 |
| Maximum Filament Emission (Peak) | (amps) | lk(max)pk. | 8.0 |
| Maximum Grid Dissipation | (watts) | Pg(max) | 150 |
| Mutual Conductance | (mA/V) | gm | 7.5 |
| Amplification Factor | | μ | 24 |
| Anode Impedance | (ohms) | ra | 3,200 |
| Maximum Operating Frequency (Full Rating) | (Mc/s) | f(max) | 40 |
| Maximum Operating Frequency (Reduced Rating) | (Mc/s) | f(max)abs. | 80 |
| Maximum R.F. Power Output | (kW) | Pout | 8-0 |
| INTER-ELECTRODE CAPAC | CITANCES | (pF) | |
| Anode/Grid Anode/Filament | ca-g | | 11 1 |

December, 1961

Grid/Filament

Issue 1, Page 1

15

cg-f



VAPOUR COOLED TRIODE

DIMENSIONS


| Maximum Overall Length | (ins) | 9 |
|---------------------------|-------|----|
| Maximum Diameter | (ins) | 41 |
| Approximate Nett Weight | (lbs) | 10 |
| Approximate Packed Weight | (lbs) | 47 |

OPERATION

See "Application Notes on the use of Vapour Cooled Valves"



ESVI500 VAPOUR COOLED TRIODE



All dimensions in mm unless otherwise stated



ESVISOS VAPCUE COOLED TRIODE



Larger as we are a speling from all specing speling in A



WATER COOLED TRIODE

(Previously EHW5000)

GENERAL

The ESW 5000 is a directly heated three electrode power valve designed for use as a radio - frequency amplifier, oscillator or Class'B modulator. It is an exact equivalent to the American GL.889.

RATING

| Filament Voltage (volts) | Vf | 11 |
|--|-------------------|---------|
| Filament Current (amps) | If | 125 |
| Maximum Anode Voltage (volts) | Va(max) | 8,500 |
| Maximum Filament Emission (amps) | Fem | 9 |
| Maximum Anode Dissipation (k.W.) | Wa(max) | 5 |
| Mutual Conductance (mA/V) | g _m | 10 |
| Amplification Factor | μ | 20 |
| Anode Impedance (chms) | ra | 2,000 |
| Maximum Operating Frequency at full rating | | 25 Mc/s |
| R.F. Power Output (kW) | Pout | 10 |
| INTER-ELECTRODE CAPACITANCES | | |
| Anode/Grid (µµF) | c _{a-gl} | 20.7 |
| Anode/Filament (µµF) | Ca-f | 2.5 |
| Grid/Filament (µµF) | C _{gl-f} | 19.5 |

Water Flow (MAIN) 3 - 6 gallons per minute

AIR FLOW 15 cubic feet per minute should be directed on to seels.

DIMENSIONS


| l | Maximum | Overall Length | (mm) | 267 |
|---|---------|----------------|------|-----|
| l | Maximum | Diameter | (mm) | 90 |

Indicates a change



WATER COOLED TRIODE

(Previously EHW5000)



December, 1961

Indicates a change


Associated Electrical Industries Limited

Electronic Components Division Tel.: GERRARD 9797



WATER COOLED TRIODE (Previously EHW5000)

AVERAGE CHARACTERISTIC CURVES




Electronic Components Division
Tel.: GERRARD 9797



WATER COOLED TRIODE

(Previously EHW5000)

AVERAGE CHARACTERISTIC CURVES: I_a/V_a (V_f =11 Volts A.C.)




December, 1961



WATER COOLED TRIODE (Previously EHW5000)

CHARACTERISTIC CURVES: I_g/V_a ($V_f=11 \text{ Volts A.C.}$)



December, 1961




EDISWAN

ESW5000

WATER COOLED TRIODE (Previously EHW5000)

AVERAGE CHARACTERISTIC CURVE: I_f/V_f (Cold resistance=0.0003 Ω)




December, 1961



WATER COOLED TRIODE (Previously EHW5000)

CHARACTERISTIC CURVE: Iem/Vf



Electronic Components Division Tel.: GERRARD 9797 MAC WORK

Annual Control State Street, and and



V1505

RADIATION COOLED TRIODE

GENERAL

The V.1505 is a Directly Heated Thoriated Filament Triode suitable for operation as a Power Amplifier or Oscillator at frequencies up to 1.5 Mc/s.

RATING

| 1011 1140 | | |
|---|----------------|----------------------|
| Filament Voltage (volts) | Vr | 14 |
| Filament Current (amps) | Ir | 6.5 |
| Maximum Anode Voltage (volts) | Va | 3,000 |
| Maximum Filament Emission (amps) | Fem | 4 |
| Maximum Anode Dissipation (watts) | Wa | 275 |
| Mutual Conductance (ma/V) | g _m | • B |
| Amplification Factor | p" | • 16 |
| Anode Impedance (ohms) | ra | • 2,000 |
| Maximum Operating Frequency at Full Rating | u | 1.5 Mc/s |
| Audio Power Output | Pout | 800 watts (2 valves) |

• Taken at $V_a = 2,000 \text{ volts}$; $I_a = 150 \text{ m/A}$


INTER-ELECTRODE CAPACITANCES

| Anode/Grid (µµF) | c _{a-gl} | 18 |
|----------------------|-------------------|----|
| Anode/Filament (ppF) | Ca-f | 9 |
| Grid/Filament (µµF) | Cgl-f | 14 |

DIVENSIONS

Waximum Overall Length (inches) 12.5
Waximum Overall Diameter (inches) 3.54

BASE P 1410 VISOS FILAMENT CAP




December, 1961



EDISWAN

VI505
RADIATION COOLED TRIODE




December, 1961



V1505

RADIATION COOLED TRIODE

GRID CURRENT (AMPS)




Electronic Components Division Tel.: GERRARD 9797



V1505 RADIATION COOLED TRIODE





(i.e., Valves with an anode dissipation less than 100 w)




Condensed Data on Replacement Types

| Туре | Des | cription | | V _h or | | I _h or I _f (A) | V _{a(max)} (kV) | V _{g2(max)} (V) | Pa(max) (W) | g _m (mA/V) | μ |
|---------------------|------------|-----------|----------|-----------------------|-----------------------|--------------------------------------|-----------------------------|--------------------------|---------------|-----------------------|-----|
| 6F32 | R.F. Pento | de | | 6.3 | 3 | 0.63 | 0.25 | 200 | 4.5 | 3.35 | _ |
| Base Connect BO7 | ions | (1) h | (2) k | (3) a | (4) g ₂ | (5) g ₃ | (6) M | . , | B) (TC | :) | |
| IIE2 | Beam Pow | er Amp | lifier | 6.3 | 3 | 0.9 | 12.5 | 550 | 5.0 | _ | _ |
| Base Connect IO | ions | (1) NP | (2) h | (3) NP | (4) g ₂ | (5) g ₁ | (6) NP | | 8) (SC k a |) | |
| AC/SP3/RH | H.F. Pento | ode | | 4. | 0 | 1.0 | 0.25 | 250 | _ | 7.5 | _ |
| Base Connect B7 | ions | (1) M | (2) a | (3) g ₃ | (4) h | (5) h | (6) k | . , | C) | | |
| ES75H | Radiation | Cooled | Triode | 10 | | 4.2 | 1.0 | _ | 75 | 3.4 | 11 |
| Base—special | | | | | | | | | | | |
| ESW205 | Radiation | Cooled | Triode | 10 | | 6.0 | 2.0 | - | 100 | 5.0 | 70 |
| Base—special | | | | | | | | | | | |
| ESW50I | Radiation | Cooled | Triode | 6. | 0 | 4.0 | 1.5 | _ | 60 | 1.3 | 8.0 |
| Base—B4 | | | | | | | | | | | |
| V453 | A.F. Pento | ode | | 4. | 0 | 0.65 | 0.25 | 150 | _ | 2.0 | _ |
| Base Connect BO7 | ions | (1) h | (2) k | (3) a | (4) g ₂ | . , | (6) M | | 8) (TC | * | |

August, 1962

Page 1, Issue 1





6FI7 MINIATURE PULSE & R.F. BEAM TETRODE Indirectly heated—for parallel operation

| RATING | | | | |
|--|-----------------------|---|--------------|--|
| Heater Voltage (volts) Heater Current (amps) Maximum Anode Vcitage (volt Maximum Screen Voltage (vol Mutual Conductance (mA/V) Maximum Anode Dissipation(Maximum Screen Dissipation | uts) | Vh Ih Va(max) Vg2(max Sm Pa Pg2 |) | 6.3 0.3 600 600 • 8.3 ‡ 3.5 |
| Tested under pulse at Va = Vg2 = 250v; | condition Vgl = - | ns and tak 6.25v; Ia= | en ≏64mA. | |
| <pre># If used in a can at must be matt black externally.</pre> | | | | |
| INTER-ELECTRODE CAPACITANCE | ES | ıı | g | 1 |
| Anode/Control Grid (µµF) | Ca-gl | .03 | .033 | .05 |
| Anode/Earth (µµF) | Cout | 6.0 | 7.1 | 5.9 |
| Control Grid/Earth (µµF) | c_{in} | 6.6 | 7.6 | 7.5 |
| Inter-electrode capacitance balance screen. | | | | |
| ¶ Total capacitance holder type 75/828 type 75/832. | including and cyli | Benjamin ndrical so | B7G reen | |
| Total capacitance holder type 75/663 screen. | | | | |
| DIMENSIONS | | | | |
| Maximum Overall Length (mm |) | | | 54 |
| Maximum Diameter (mm) | | | | 19 |
| Maximum Seated Height (mm) | | | | 47.5 |
| Approximate Nett Weight (o | zs) | | | 1 |
| Approximate Packed Weight | (ozs) | | | 2 |
| MOUNTING POSITION - Unre | stricted. | | | |

December, 1961



6FI7 MINIATURE PULSE & R. F. BEAM TETRODE Indirectly heated—for parallel operation

BULB Clear

BASE B7G



Viewed from free end of pins

CONNEXIONS

| Pin | 1 | Control Grid | gl |
|-----|---|--------------|----|
| Pin | 2 | Cathode | k |
| Pin | 3 | Heater | h |
| Pin | 4 | Heater | h |
| Pin | 5 | Anode | а |
| Pin | 6 | Beam Plates | |
| Pin | 7 | Screen Grid | g2 |
| | | | |




MINIATURE PULSE & R, F. BEAM TETRODE

Indirectly heated-for parallel operation

AVERAGE CHARACTERISTIC CURVES

These curves were taken with a short duration pulse having a 400 · I off to on period






MINIATURE PULSE & R. F. BEAM TETRODE

Indirectly heated-for parallel operation

AVERAGE CHARACTERISTIC CURVES

These curves were taken with a short duration pulse having a 400:1 off to on period at Voz=280



ANODE VOLTS



VARIABLE MU H.F. PENTODE

Indirectly heated-for parallel operation

GENERAL

The 6F21 is a miniature based indirectly heated variable mu H.F. Pentode. It is intended for use in H.F. or L.F. Amplifiers having parallel connected heaters.

RATING

| Heater Voltage (volts) | Vh | 6.3 |
|---|-----------|-------|
| Heater Current (amps) | lh | 0.2 |
| Maximum Anode Voltage (volts) | Va(max) | 300 |
| Maximum Screen Voltage (volts) | Vg2(max) | 300 |
| Maximum Anode Voltage (volts) | Va(max) | 500* |
| Maximum Screen Voltage (volts) | Vg2(max) | 300* |
| Mutual Conductance (mA/V) | gm | 2.5†1 |
| Inner μ | μg1,g2 | 30†† |
| Maximum Potential Heater/Cathode (volts DC) | Vh,k(max) | 150 |
| Maximum Anode Dissipation (watts) | Pa(max) | 3.0 |
| Maximum Screen Dissipation (watts) | | 0.7 |
| | | |

^{*} With 5,000 ohms in series with the anode, and 20,000 ohms in series with the screen, $l_a = 0$.

INTER-ELECTRODE CAPACITANCES (pF)

| | | § | ‡ | 11 |
|---------------|-------|--------|--------|--------|
| Anode/Earth | Cout | 7.0 | 8.1 | |
| Gride 1/Earth | cin | 4.7 | 5.8 | |
| Anode/Grid 1 | Ca-g1 | 0.0078 | 0.0098 | 0.0083 |

December, 1961

^{††} $V_a = 250 \text{ v}$; $V_{g2} = 200 \text{ v}$; $V_{g1} = -2.5 \text{ v}$.



VARIABLE MU H.F. PENTODE

Indirectly heated-for parallel operation

- § Inter-electrode capacity with holder capacity balanced out.
- † Total capacity with a Benjamin B7G holder type 75/787R.
- †† Total capacity with a Benjamin type 75/787R holder and a perpendicular shield between pins 2, 3 and 6, 7.
 - "Earth" denotes the remaining earthy potential electrodes, heater and shields connected to tathode.

DIMENSIONS

| Maximum Overall Length | (mm) | 10000 | 54-5 |
|---------------------------|-------|-------|------|
| Maximum Diameter | (mm) | | 19 |
| Maximum Seated Height | (mm) | | 47.5 |
| Approximate Nett Weight | (ozs) | | 1 |
| Approximate Packed Weight | (ozs) | | 1 2 |

MOUNTING POSITION Unrestricted.

TYPICAL OPERATION

| Anode Voltage (volts) | V_a | 250 | 250 |
|--|----------|------|------|
| Screen Voltage (volts) | V_{g2} | 100 | 200 |
| Grid Bias (volts) | Vg1 | -0.5 | -2.5 |
| Anode Current (mA) | la | 4.9 | 7.8 |
| Screen Current (mA) | 1g2 | 1.25 | 2.0 |
| Mutual Conductance (mA/V) | gm | 2.5 | 2.5 |
| Grid Bias for Mutual Conductance of 10 μ A/V (volts) | | | -34 |
| Equivalent Grid Noise Resistance (ΚΩ) | Req | | 7.5 |
| Anode Impedance (MΩ) | ra | | 1.2 |

December, 1961



VARIABLE MU H.F. PENTODE

Indirectly heated-for parallel operation

BULB-Clear.

BASE-B7G.



Viewed from free end of pins

| | 150 | - | 21.4 |
|------|-------|-------|------------|
| | u E C | . 110 | SPK |
| | | - | |

| Pin 1 | Control Grid | 81 |
|-------|----------------------------|------|
| Pin 2 | Cathode | k |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |
| Pin 5 | Anode | a |
| Pin 6 | Suppressor Grid and Shield | g3,s |
| Pin 7 | Screen Grid | 82 |




EDISWAN

6F21

VARIABLE MU H.F. PENTODE Indirectly heated—for parallel operation

AVERAGE SHARACTERISTIC CURVES : I₂/Vg₁ Curves taken at V₂=250V



December, 1961



6F21


VARIABLE MU H.F. PENTODE

Indirectly heated—for parallel operation.

AVERAGE CHARACTERISTIC CURVES : $V_{sig}(pk)$, $gm(eff)/V_g$ $V_a = 250V$ $V_g 2 = 200V$ $V_g 3 = 0V$

 $V_a = 250V$ $V_{g2} = 200V$ $V_{g3} = 0V$ $V_{g3} = 0V$ $V_{g3} = 0$ $V_{g3} = 0$

Initially: $V_{g1} = 2.5V$ $l_a=7.8mA$ Ig2 = 2.0mA



December, 1961




MAWRICE

0.00

DESCRIPTION OF REPORT AND RESIDENCE

nothers is traced-for condited necession.





6F33

SCREENED R.F. PENTODE Indirectly heated

GENERAL

The 6.F.33 has a short cut-off Suppressor Grid characteristic which makes it particularly suitable for use in Modulator, Variable Reactance and Timing Circuits. A diode has been tied to the suppressor in order to prevent "blocking" when this grid is driven positive.

RATING

| v _h | 6.3 |
|-----------------------|--|
| _ | |
| h | 0.35 |
| Va(max) | 250 |
| Vg2(max) | 250 |
| g _m | • 4.35 |
| μg1 g2 | • 38 |
| Pa(max) | 2.5 |
| pg2 | 0.8 |
| V _{h-k(max)} | 100 |
| | Vg2(max) gm Mg1 g2 Pa(max) Pg2 |

• Taken at V_a = 200v; V_{g2} = 100v; V_{g1} = -1.5v; V_{g3} = 0v.

 $\ensuremath{\textit{\text{$\#$1.0}$}}$ § $\ensuremath{\text{$V_{g2}$}}$ with $\ensuremath{\text{$I_a$}}$ constant.

| INTER-ELECTRODE CAPACI | TANCES | | 3 | \$ |
|------------------------|--------|-------|-------|-------|
| Anode/Earth | (ppF) | cout | 4.5 | 5.6 |
| Anode/Control Grid | (ppF) | ca-gl | .0.01 | 0.012 |
| Control Grid/Earth | (ppF) | cin | 7.3 | 8.4 |
| Suppressor Grid/Earth | (µµF) | cg3-E | 10.0 | 11.1 |

- Measured with Benjamin cylindrical screen type 75/832, but holder capacity balanced out.
- \$ Including capacity of Benjamin B7G holder type 75/833 and screen type 25/832.

DIMENSIONS

Maximum Overall Length (mm)
Maximum Diameter (mm)
Maximum Seated Height (mm)
Approximate Nett Weight (czs)
Approximate Packed Weight (czs)

MOUNTING POSITION - Unrestricted.

Indicates a change
Issue 1, Page 1

19



EDISWAN

6F33

SCREENED R.F. PENTODE Indirectly heated

BULB Clear

BASE B.7.G



Viewed from free end of pins

CONNECTIONS

Pin 1 Control Grid gl Pin 2 Cathode k Pin 3 Heater Pin 4 Heater h Pin 5 Anode Pin 6 Suppressor Grid g3 Pin 7 Screen Grid g2

December, 1961



6F33


SCREENED R.F. PENTODE Indirectly heated

CHARACTERISTIC CURVES OF AVERAGE

Curves taken at V_a = 200V.

Anode Current

Key




December, 1961




6F33

SCREENED R.F. PENTODE Indirectly heated

CHARACTERISTIC CURVES OF AVERAGE





December, 1961




6F33

SCREENED R.F. PENTODE Indirectly heated

CHARACTERISTIC CURVES OF AVERAGE





December, 1961




6F33

SCREENED R.F. PENTODE Indirectly heated

CHARACTERISTIC CURVES OF AVERAGE

Curves taken at 1/2 = 2001



December, 1961



6P17

OUTPUT PENTODE

Indirectly heated-for parallel operation

TENTATIVE

GENERAL

The 6P17 is a miniature based Power Output Pentode having a maximum anode dissipation of 4.75 watts and its Suppressor Grid internally tied to the cathode.

It has a maximum operating frequency at full ratings of 100 Mc/s and is intended for use in equipment powered from AC mains.

RATING

| Heater Voltage | (volts) | V_h | 6.3 |
|---|---------|-------------|-------|
| Heater Current | (amps) | lh | 0.2 |
| Maximum Anode Voltage | (volts) | Va (max) | 300 |
| Maximum Screen Voltage | (volts) | Vg2(max) | 275 |
| Maximum Anode Dissipation | (watts) | Pa(max) | 4.75* |
| Maximum Screen Dissipation | (watts) | Pg2(max) | 0.8 |
| Maximum Heater/Cathode Voltage | (volts) | Vh-k(max) | 150† |
| Maximum Grid 1/Grid 2 Voltage (DC) | (volts) | Vg1-g2(max) | 300 |
| Maximum Grid 1/Cathode Voltage (DC) | (volts) | Vg1-k(max) | 100 |
| Maximum Mean Grid 1 Current | (mA) | lg1(max) | 3.3 |
| Mutual Conductance | (mA/V) | gm | 2.6‡ |
| Inner Amplification Factor | | μg1-g2 | 12‡ |
| Maximum Operation Frequency at full ratings | (Mc/s) | f(max) | 100 |

^{*} Valve unscreened with adequate ventilation.

December, 1961

[†] Cathode positive or negative to heater.

 $[\]ddagger$ Measured at Va=Vg2=250 V ; Ia=16 mA ; Vg1=-13.5V.



6P17

OUTPUT PENTODE

Indirectly heated-for parallel operation

TENTATIVE

INTER-ELECTRODE CAPACITANCES (pF)

| Grid 1/Earth | Cin | 4.25 |
|--------------|-------|------|
| Anode/Earth | Cout | 6.5 |
| Anode/Grid 1 | ca-g1 | <0.3 |

Measured cold with an external screen but with holder capacity balanced out.

"Earth" denotes the remaining earthy potential electrodes, heater and shields connected to cathode.

DIMENSIONS

| Maximum Overall Length | (mm) | 54.5 |
|---------------------------|-------|-------------------------|
| Maximum Diameter | (mm) | 19.0 |
| Maximum Seated Height | (mm) | 47.5 |
| Approximate Nett Weight | (ozs) | south south as 1 |
| Approximate Packed Weight | (ozs) | 15005 Pro 1510 Pro 1512 |

MOUNTING POSITION—Unrestricted.

TYPICAL OPERATION—Class A Power Output.

| Anode Voltage | (volts) | Va | 250 |
|--|-------------|------|-----|
| Screen Voltage | (volts) | Vg2 | 250 |
| Cathode Bias Resistance | (ohms) | Rk | 740 |
| Anode Current | (mA) | la | 16 |
| Screen Current | (mA) | lg2 | 2.4 |
| Power Output for 10% Total Harmonic Distortion | (watts) | Pout | 1.4 |
| Anode Load Impedance | $(k\Omega)$ | Ra | 16 |
| Input Voltage Swing (r.m.s.) | (volts) | Vin | 5.3 |

BULB-Clear

December, 1961




6P17

OUTPUT PENTODE Indirectly heated—for parallel operation

TENTATIVE

BASE-B7G



Viewed from free end of pins

VALVE HOLDER

Ediswan Clix VH337/7, VH437/7 and VH17/7 series.

CONNECTIONS

| Pin 1 | Grid 1 | g1 |
|-------|-----------------|------|
| Pin 2 | Cathode, Grid 3 | k,g3 |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |
| Pin 5 | Anode | a |
| Pin 6 | No Connection | N.C. |
| Pin 7 | Grid 2 | g2 |



risa

SOCIAL TUTTO

SVITATMST

- LA



cally has been sored. Accords become to

FIGHE TYPE

All the Charles of the Charles of the Charles of the Charles



IIAI

LOW MU TRIODE Indirectly heated

GENERAL

The 11A1 is a miniature based triode intended for use as a series stabiliser valve. It has a maximum cathode current of 120mA and a maximum anode dissipation of 15 watts. These valves are suitable for operation in parallel.

| RATING | | |
|---|---------------------|------|
| Heater Voltage (volts) | Vh | 6.3 |
| Heater Current (amps) | lh | 0.95 |
| Maximum Anode Voltage (volts) | V _{a(max)} | 300 |
| Maximum Anode Dissipation (watts) | Pa(max) | 15 |
| Maximum Cathode Current (mA) | lk(max) | 120 |
| Maximum Heater/Cathode Voltage (volts) | Vh-k(max) | 250 |
| Mutual Conductance (mA/V) | gm | 12* |
| Amplification Factor | μ | 4.5* |
| Anode Impedance (ohms) | ra | 375* |
| * Measured at $V_a = 150V$; $I_a = 100 mA$ | | |
| INTER-ELECTRODE CAPACITANCES (F | (F)† | |
| Anode/Grid | ca-g | 9.0 |
| Anode/Cathode | ca-k | 4.5 |
| Grid/Cathode | cg-k | 8.5 |
| † Measured without external shield | | |
| | | |
| DIMENSIONS | | |
| Maximum Overall Length | (mm) | 65 |
| Maximum Diameter | (mm) | 22 |
| Maximum Seated Height | (mm) | 58 |
| Approximate Nett Weight | (ozs) | 1 2 |
| Approximate Packed Weight | (ozs) | 34 |

December, 1961



IIAI

LOW MU TRIODE Indirectly heated

MOUNTING POSITION—Unrestricted

TYPICAL OPERATION—Series Regulator (Two valves in parallel)

| Input Voltage (volts) | Vin | 360 |
|----------------------------------|----------------|-----|
| Output Voltage (volts) | Vout | 210 |
| Output Current (total) (mA) | lout (tot) | 200 |
| Stabilisation for ± 7% input (%) | 10 40 70 20 00 | 0.2 |

Small resistors should be inserted in the anode and cathode leads of each valve for balancing purposes.

BASE-Noval (B9A)



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | Internal Connection | IC |
|-------|---------------------|----|
| Pin 2 | Cathode | k |
| Pin 3 | Internal Connection | IC |
| Pin 4 | Heater | h |
| Pin 5 | Heater | h |
| Pin 6 | Grid | g |
| Pin 7 | Internal Connection | IC |
| Pin 8 | Internal Connection | IC |
| Pin 9 | Anode | a |

December, 1961



IIDI2

LOW-MU DOUBLE TRIODE

Indirectly heated

TENTATIVE

GENERAL

The 11D12 is an indirectly heated, low-mu, Power Double Triode with separate cathodes. It is suitable for use in booster scanning circuits, and as a series regulator in DC Power Supply Units.

RATING-Absolute values

| Heater Voltage | Vh | 6.3 | ٧ |
|---------------------------------|------------|-------|-------|
| Heater Current | lh . | 2.5 | A |
| Maximum Anode Supply Voltage | Va(b)max | 550* | V |
| Maximum Anode Voltage | Va(max) | 250* | V |
| Maximum Peak Inverse Voltage | -(| | |
| (Booster) | | 3.0*+ | kV |
| Maximum Negative Control Grid | | 1 | |
| Pulse Voltage (booster) | | 2.3*+ | kV |
| Maximum Cathode Current | k(max) | 125* | mA |
| Maximum Anode Dissipation | Pa(max) | 13* | W |
| Maximum Resistance between Grid | ra(IIIax) | | |
| and Cathode (cathode bias) | | 1.0* | МΩ |
| Maximum Resistance between Grid | | 10 | 1122 |
| | | 0.4*4 | MO |
| and Cathode (fixed bias) | | 0.1*‡ | 14177 |
| Maximum Heater/Cathode Voltage | Vh-k(max) | 300*§ | V |
| Maximum Bulb Temperature | TBulb(max) | 230 | °C |
| * = 1 0 | Dail (max) | | |

^{*} Each Section.

§ Operation is not recommended with a damper pulse between heater and cathode.

[†] Booster scanning service. Maximum pulse duration 15% of one cycle with a maximum duration of 15µs.

 $[\]ddagger$ With fixed bias the anode circuit should contain a protective resistance to provide a minimum drop of 15V D.C. at the normal operating conditions. When two or more sections are used in parallel at dissipations approaching the rated maximum, separate anode and cathode resistors must be used to assist load sharing. When combined fixed and cathode bias is used, the cathode bias portion should have a minimum value of 7.5V D.C. at the normal operating conditions and with grid to cathode resistance of $100 \text{k}\,\Omega$. It is not recommended that fixed bias be used when the valve is used in a booster scanning circuit.



IIDI2

LOW-MU DOUBLE TRIODE

Indirectly heated

TENTATIVE

| INTER-ELECTRODE | CAPACITANCES | (pF)*—Each | Section |
|-----------------|--------------|------------|---------|
|-----------------|--------------|------------|---------|

| Anode/Grid | ca-g | 7-3 |
|--------------------------|--------|------|
| Heater/Cathode | ch-k | 9.6 |
| Anode 2/Anode 1 | ca"-a' | 2.7 |
| Grid 2/Grid 1 | cg"-g' | 0.25 |
| Grid 1 or Grid 2/Earth | cin | 6.9 |
| Anode 1 or Anode 2/Earth | Cout | 2.5 |

^{*} Measured in fully shielded socket without can.

DIMENSIONS

| Maximum Overall Length | 103 mm |
|------------------------|---------|
| Maximum Base Diameter | 43.5 mm |
| Maximum Seated Height | 88.5 mm |

MOUNTING POSITION—Unrestricted

CHARACTERISTICS*—Each Section

| Anode Supply Voltage | $V_{a(b)}$ | 135 | ٧ |
|---------------------------------|------------|-----|------|
| Anode Current | la | 125 | mA |
| Cathode Bias Resistance | Rk | 250 | Ω |
| Mutual Conductance | gm | 7.0 | mA/V |
| Amplification Factor | μ | 2.0 | |
| Valve Anode Resistance (approx) | ra | 280 | Ω |

^{*} Values quoted correspond to operation at the absolute limit of anode current and dissipation.

December, 1961

ADVANCE DATA, Page 2

Electronic Components Division
Tel.: GERRARD 9797



IIDI2

LOW-MU DOUBLE TRIODE Indirectly heated

TENTATIVE

BASE-108



Viewed from free end of pins

CONNECTIONS

| Pin 1 | Grid 1 | g' |
|-------|-----------|----|
| Pin 2 | Anode 1 | a' |
| Pin 3 | Cathode 1 | k′ |
| Pin 4 | Grid 2 | g" |
| Pin 5 | Anode 2 | a" |
| Pin 6 | Cathode 2 | k" |
| Pin 7 | Heater | h |
| Pin 8 | Heater | h |

Electronic Components Division
Tel: GERRARD 9797



HO.

DOME, INCO SERVICE

Section 1

and the second second



IIE3

BEAM POWER AMPLIFIER Indirectly heated—for Pulse Amplification

| RATING | | |
|--|--|--------------------------------|
| Heater Voltage (volts) Heater Current (amps) Maximum Anode Voltage as Series | Vh Ih | 4.2 2.5 |
| Modulator (volts DC) | Va(max) | 3,500 |
| Maximum Peak Anode Voltage as Break Modulator (volts) Maximum Screen Voltage (volts) Maximum Control Grid Negative | Va(pk)max Vg2(max) | 12,500 700 |
| Bias (volts-ve) Maximum Peak Cathode Current (amps) Inner µ Maximum Anode Dissipation (watts) Maximum Screen Dissipation as | Vgl(max) Ik(pk)max Ugl-g2 Wa(max) | -700 † 3.5 ‡ 9.0 10.0 |
| Series Modulator (watts) Maximum Screen Dissipation as | Wg2(max)Series | 0.9 |
| Break Modulator (watts) Maximum Potential Heater/Cathode | Wg2(max)Break | 2.0 |
| (volts DC) | Vh-k(max) | 150 |
| † Taken under Pulse Conditions of 10 micro-seconds duration and off-on ratio. | | |
| * Taken at $V_a = 200$; $V_{g2} = 200$; | $I_a = 40 \text{ mA}$ | |
| INTER-ELECTRODE CAPACITANCES | | |
| Anode/Earth (puF) Anode/Control Grid (puF) Control Grid/Earth (puF) | Cout Ca-gl Cin | 7.5 0.26 20 |
| "Earth" denotes the remaining electrodes and heater joined t | earthy potential co cathode. | |
| DIMENSIONS | | |
| Meximum Overall Length (mm) Meximum Diameter (mm) Meximum Seated Height (mm) Approximate Nett Weight (ozs) Approximate Packed Weight (ozs) | | 140 54 125 2½ 7 |
| MOUNTING POSITION Vertical | | |
| NOTE | | |
| This valve is intended for use as a builth a short duration pulse input sign may be subjected to reduced atmospher voltage between the control grid and sexceed 1,200 volts. | nal. When the eq | uipme nt peak |





IIE3

BEAM POWER AMPLIFIER
Indirectly heated—for Pulse Amplification

| TYPICAL OPERATION | | Series Modulator | Break Modulator |
|---|--------------|---------------------|--------------------|
| Quiescent Anode Voltage (volts) Screen Voltage (volts) Signal Voltage Positive | Va(o) Vg2 | 3,500 500 | 500 500 |
| (volts) Peak Anode Current (amps) Approximate Knee Voltage | Ia(pk) | 50 2 | 25 1 |
| (volts) Peak Anode Output Voltage (volts) Approximate Peak Grid | | 3,300 | 10,000 |
| Current (amps) | Igl(pk) | 0.12 | 0.05 |

CAP BVA Standard

BULB Clear

BASE British 7 Pin.



Viewed from free end of pins.

CONNEXIONS


| Pin 1 | Blank | |
|---------|--------------|----|
| Pin 2 | Control Grid | gl |
| Pin 3 | Blank | - |
| Pin 4 | Heater | h |
| Pin 5 | Heater | h |
| Pin 6 | Cathode | k |
| Pin 7 | Screen Grid | g2 |
| Top Cap | Anode | a |
| | | |

Electronic Components Division Tel.: GERRARD 9797



BEAM POWER AMPLIFIER
Indirectly heated—for Pulse Amplification

AVERAGE CHARACTERISTIC CURVES



ANODE VOLTS




IIE3

BEAM POWER AMPLIFIER Indirectly heated—for Pulse Amplification

AVERAGE CHARACTERISTIC CURVES






ANODE VOLTS



I I E 3 BEAM POWER AMPLIFIER Indirectly heated—for Pulse Amplification

AVERAGE CHARACTERISTIC CURVES




December, 1961

IIE3

BEAM POWER AMPLIFIER Indirectly heated—for Pulse Amplification

AVERAGE CHARACTERISTIC CURVES



ANODE VOLTS

Electronic Components Division Tel.: GERRARD 9797



H.F. DOUBLE TETRODE

Indirectly heated

TENTATIVE

GENERAL

The 11E13 is an indirectly heated, miniature based, h.f. double tetrode. It is internally neutralised and is intended for use as a push-pull amplifier at frequencies up to 225 Mc/s.

RATING§

| 3 | | | | |
|---|--------|------|------|------|
| Heater Voltage | V_h | 6.3 | 12.6 | ٧ |
| Heater Current | Ih | 0.83 | 0.4 | 2 A |
| Maximum Operating Frequency | f(max) | | 225 | Mc/s |
| Maximum Permissible Temperature of hottest part of bulb | | | 225 | °C |
| Maximum Permissible Temperature of the base pins | | | 120 | °C |

[§] All limiting values are Absolute, not Design Centres.

RATING-Absolute values

Class "C" r.f. amplifier for c.w. telegraphy or f.m. telephony.

| Maximum Anode Voltage | V _{a(max)} | 300 V |
|---|---------------------|---------|
| Maximum Screen Grid Voltage | Vg2(max) | 200 V |
| Maximum Negative Control Grid Voltage | Vg1(max) | -150 V |
| Maximum Heater/Cathode Voltage | | 100 V |
| Maximum Anode Dissipation | Pa(max) | 5.0* W |
| Maximum Screen Grid Dissipation | Pg2(max) | 1-0* W |
| Maximum Control Grid Dissipation | Pg1(max) | 0.2* W |
| Maximum Peak Cathode Current | ik(pk)max | 225* mA |
| Maximum Mean Cathode Current | | 50* mA |
| Maximum Mean Control Grid Current | lg1(av)max | 3-0*mA |
| Maximum Mean Cathode Current Maximum Mean Control Grid | lk(av)max | 50* n |

^{*} Each section.

February, 1962



H.F. DOUBLE TETRODE

Indirectly heated

TENTATIVE

RATING—Absolute values

Class "C" r.f. amplifier with anode and screen grid modulation (carrier condition for use with modulation factor 1).

| Maximum Anode Voltage | V _{a(max)} | 250 | ٧ |
|---------------------------------------|---------------------|------|------|
| Maximum Screen Grid Voltage | Vg2(max) | 200 | V |
| Maximum Negative Control Grid Voltage | Vg1(max) | -150 | ٧ |
| Maximum Heater/Cathode Voltage | Vh-k(max) | 100 | ٧ |
| Maximum Anode Dissipation | Pa(max) | 3.3 | * W |
| Maximum Screen Grid Dissipation | Pg2(max) | 0.6. | 5*W |
| Maximum Control Grid Dissipation | | 0.2 | * W |
| Maximum Peak Cathode Current | ik(pk)max | 180* | mA |
| Maximum Mean Cathode Current | lk(av)max | 40* | mA |
| Maximum Mean Control Grid Current | lg1(av)max | 3-0 | * mA |

^{*} Each section.

RATING—Absolute values

Frequency Trebler.

| Maximum Anode Voltage | V _{a(max)} | 300 V |
|---------------------------------------|---------------------|---------|
| Maximum Screen Grid Voltage | Vg2(max) | 200 V |
| Maximum Negative Control Grid Voltage | Vg1(max) | -150 V |
| Maximum Heater/Cathode Voltage | Vh-k(max) | 100 V |
| Maximum Anode Dissipation | Pa(max) | 5.0* W |
| Maximum Screen Grid Dissipation | Pg2(max) | 1.0* W |
| Maximum Control Grid Dissipation | Pg1(max) | 0·2* W |
| Maximum Peak Cathode Current | ik(pk)max | 225* mA |
| Maximum Mean Cathode Current | lk(av)max | 35* mA |
| Maximum Mean Control Grid | | |
| Current | lg1(av)max | 2.0* mA |

^{*} Each section.



H.F. DOUBLE TETRODE

Indirectly heated

TENTATIVE

INTER-ELECTRODE CAPACITANCES

| Anode/Grid 1 (each section)* | ca-g1 | <0.1 pF |
|--|---------|---------|
| Grid 1/All other electrodes (each section) | cg1-all | 6-2 pF |
| Anode/All other electrodes (each section) | ca-all | 2.6 pF |
| Input Capacitance ‡ | cin | 5.0 pF |
| Output Capacitance ‡ | Cout | 1.5 pF |

^{*} Internally neutralised for push-pull operation.

CHARACTERISTICS †‡

| Mutual Conductance | gm | 3.3 mA/V |
|----------------------------|-------------|----------|
| Inner Amplification Factor | μ g1-g2 | 7.5 |

[†] Each section.

DIMENSIONS

| Maximum O | verall Length | 78.5 | mm |
|------------|---------------|------|----|
| Maximum Di | iameter | 22.2 | mm |
| Maximum Se | ated Height | 71.5 | mm |

MOUNTING POSITION—Unrestricted, but when mounted horizontally pins 2 and 7 must be in the same vertical plane.

BASE-Noval (B9A)



Viewed from free end of pins

February, 1962

[†] Two sections in push-pull.

 $[\]ddagger$ At $I_a = 30$ mA.



H.F. DOUBLE TETRODE

Indirectly heated

TENTATIVE

CONNECTIONS

| Pin 1 | Control Grid, Section 1 | g1' |
|-------|-------------------------|----------|
| Pin 2 | Cathode, Shield | k,s |
| Pin 3 | Control Grid, Section 2 | g1" |
| Pin 4 | Heater | h |
| Pin 5 | Heater | h |
| Pin 6 | Anode, Section 1 | a' |
| Pin 7 | Screen Grid | g2', g2" |
| Pin 8 | Anode, Section 2 | a" |
| Pin 9 | Heater Centre Tap | hct |



H.F. DOUBLE TETRODE Indirectly heated

TENTATIVE

GENERAL

The 11E15 is an internally neutralised h.f. double tetrode. It is intended for use as a push-pull amplifier or frequency trebler at frequencies up to 500 Mc/s.

RATINGS

| Heater Voltage | Vh | 12.6 | | 6.3 V |
|--|----------------|------|-----|-------|
| Heater Current | 1 _h | 0.9 | | 1.8 A |
| Maximum Operating Frequency | f(max | () | 500 | Mc/s |
| Maximum Permissible Temperatur of hottest part of bulb | | 7 | 200 | °C |
| Maximum Permissible Temperatur of the base pins | е | | 180 | °C |

As Class "C" r.f. push-pull power amplifier for c.w.

§All limiting values are Absolute, not Design Centres.

RATING-Absolute values

(fixed bias)

| $V_{a(max)}$ | 600* | ٧ |
|--------------|--|---|
| Vg2(max) | 300 | ٧ |
| Vg1(max) | -100 | ٧ |
| Vh-k(max) | 100 | ٧ |
| Pa(max) | 20† | W |
| Pg2(max) | 3.5† | W |
| | 1-0+ | W |
| | 700± | mA |
| ·K(pk)max | | |
| k(av)max | 120† | mA |
| , , | | |
| | Vg1(max) Vh-k(max) Pa(max) Pg2(max) Pg1(max) ik(pk)max | Vg2(max) 300 Vg1(max) -100 Vh-k(max) 100 Pa(max) 20† Pg2(max) 3·5† Pg1(max) 1·0† ik(pk)max 700† |

February, 1962

ADVANCE DATA, Page 1

50† kΩ

Continued

Rg1-k(max)

H.F. DOUBLE TETRODE Indirectly heated

TENTATIVE

| Maximum Control Grid/ Cathode Resistance | |
|---|------------|
| (automatic bias) | Rg1-k(max) |

Maximum Mean Control Grid Current

Ig1(av)max 5.0†mA

100† kΩ

* For natural cooling Va(max)=600V up to 150 Mc/s but [is limited to 280V at 500 Mc/s. For forced air cooling Va(max)=600V up to 280 Mc/s but is limited to 500V at 500 Mc/s.

† Each section.

RATING-Absolute values

Class "B" a.f. power amplifier or modulator.

| Maximum Anode Voltage | $V_{a(max)}$ | 600 | ٧ |
|---|--------------|------|----|
| Maximum Screen Grid Voltage | Vg2(max) | 300 | ٧ |
| Maximum Negative Control Grid Voltage | Vg1(max) | -100 | ٧ |
| Maximum Heater/Cathode Voltage | Vh-k(max) | 100 | V |
| Maximum Anode Dissipation | Pa(max) | 20† | W |
| Maximum Screen Grid Dissipation | Pg2(max) | 3.5† | W |
| Maximum Control Grid Dissipation | Pg1(max) | 1.0† | ·w |
| Maximum Peak Cathode Current | ik(pk)max | 450† | mA |
| Maximum Mean Cathode Current | lk(av)max | 140† | mA |
| Maximum Control Grid/ Cathode Resistance (fixed bias) | Rg1-k(max) | 50† | kΩ |
| Maximum Control Grid/ Cathode Resistance | el entre le | | |
| (automatic bias) | Rg1-k(max) | 100† | kΩ |
| | | | |

† Each section.

February, 1962



11E15

H.F. DOUBLE TETRODE

Indirectly heated

TENTATIVE

RATING---Absolute values

As Class " C" r.f. power amplifier with anode and screen modulation (carrier condition for use with modulation factor 1).

| factor 1). | | | |
|---|-----------------------|------|----|
| Maximum Anode Voltage | $V_{a(max)}$ | 600* | V |
| Maximum Screen Grid Voltage | Vg2(max) | 300 | V |
| Maximum Negative Control Grid Voltage | Vg1(max) | -175 | ٧ |
| Maximum Heater/Cathode Voltage | V _{h-k(max)} | 100 | ٧ |
| Maximum Anode Dissipation | Pa(max) | 14+ | W |
| Maximum Screen Grid Dissipation | Pg2(max) | 2.3† | W |
| Maximum Control Grid Dissipation | Pg1(max) | 1.0† | W |
| Maximum Peak Cathode Current | ik(pk)max | 1.0† | A |
| Maximum Mean Cathode Current | lk(av)max | 120† | mΑ |
| Maximum Control Grid/ Cathode Resistance (fixed bias) | Rg1-k(max) | 50† | kΩ |
| Maximum Control Grid/ Cathode Resistance | | | |
| (automatic bias) | $R_{g1-k(max)}$ | 100† | kΩ |
| Maximum Mean Control Grid Current | g1(av)max | 5.0 | mA |
| | | | |

^{*} For natural cooling $V_a(max)=600V$ up to [150 Mc/s but is limited to 280V at 500 Mc/s. For forced air cooling $V_a(max)=600V$ up to 250 Mc/s but is limited to 480V at 500 Mc/s.

[†] Each section.



H.F. DOUBLE TETRODE

Indirectly heated

TENTATIVE

RATING—Absolute values

Frequency Trebler.

| Maximum Screen Grid Voltage Maximum Negative Control Grid Voltage Maximum Heater/Cathode Voltage Maximum Anode Dissipation Maximum Screen Grid Dissipation Maximum Control Grid Dissipation Maximum Peak Cathode Current Maximum Mean Cathode Current Maximum Mean Cathode Current Maximum Control Grid/ Cathode Resistance (fixed bias) Maximum Control Grid/ Cathode Resistance (automatic bias) Maximum Mean Control Maximum Mean Control Rg1-k(max) Maximum Mean Control Rg1-k(max) Maximum Mean Control | 3 | Frequency Trebler. | | | |
|--|---|-----------------------|------------|------|----|
| Maximum Screen Grid Voltage Maximum Negative Control Grid Voltage Maximum Heater/Cathode Voltage Maximum Anode Dissipation Maximum Screen Grid Dissipation Maximum Control Grid Dissipation Maximum Peak Cathode Current Maximum Mean Cathode Current Maximum Mean Cathode Current Maximum Control Grid/ Cathode Resistance (fixed bias) Maximum Control Grid/ Cathode Resistance (automatic bias) Maximum Mean Control Maximum Mean Control Rg1-k(max) 300 Vg1(max) Poh-k(max) Poh-k(max) No† Maximum Mean No† Maximum Mean No† Maximum Control Grid/ Cathode Resistance (automatic bias) Maximum Mean Control Rg1-k(max) No† Maximum Mean Control | ĺ | Maximum Anode Voltage | Va(max) | 750 | V |
| Grid Voltage Maximum Heater/Cathode Voltage Maximum Anode Dissipation Maximum Screen Grid Dissipation Maximum Control Grid Dissipation Maximum Peak Cathode Current Maximum Mean Cathode Current Maximum Control Grid/Cathode Resistance (fixed bias) Maximum Control Grid/Cathode Resistance (automatic bias) Maximum Mean Control Maximum Mean Control Maximum Mean Control Maximum Control Grid/Cathode Resistance (automatic bias) Maximum Mean Control Maximum Mean Control | | | | 300 | ٧ |
| Voltage Maximum Anode Dissipation Maximum Screen Grid Dissipation Maximum Control Grid Dissipation Maximum Peak Cathode Current Maximum Mean Cathode Current Maximum Control Grid Cathode Resistance (fixed bias) Maximum Control Grid Cathode Resistance (automatic bias) Maximum Mean Control Maximum Mean Control Maximum Mean Control Maximum Control Grid Cathode Resistance (automatic bias) Maximum Mean Control Maximum Mean Control | | Grid Voltage | Vg1(max) | -175 | ٧ |
| Maximum Screen Grid Dissipation Maximum Control Grid Dissipation Maximum Peak Cathode Current Maximum Mean Cathode Current Maximum Control Grid Cathode Resistance (fixed bias) Maximum Control Grid Cathode Resistance (automatic bias) Maximum Mean Control Rg1-k(max) Rg1-k(max) Maximum Mean Control Rg1-k(max) Maximum Mean Control | | Voltage | Vh-k(max) | | ٧ |
| Dissipation Maximum Control Grid Dissipation Maximum Peak Cathode Current Maximum Mean Cathode Current Maximum Control Grid Cathode Resistance (fixed bias) Maximum Control Grid Cathode Resistance (automatic bias) Maximum Mean Control Maximum Mean Control Rg1-k(max) Rg1-k(max) Maximum Mean Control Rg1-k(max) Maximum Mean Control | | | Pa(max) | 20† | W |
| Dissipation Pg1(max) 1.0† V Maximum Peak Cathode Current ik(pk)max 700† m/ Maximum Mean Cathode Current Ik(av)max 100† m/ Maximum Control Grid/ Cathode Resistance (fixed bias) Rg1-k(max) 50† kG Maximum Control Grid/ Cathode Resistance (automatic bias) Rg1-k(max) 100† kG Maximum Mean Control | | Dissipation | Pg2(max) | 3·5† | W |
| Current ik(pk)max 700† m/ Maximum Mean Cathode Current Ik(av)max 100† m/ Maximum Control Grid/ Cathode Resistance (fixed bias) Rg1-k(max) 50† kG Maximum Control Grid/ Cathode Resistance (automatic bias) Rg1-k(max) 100† kG Maximum Mean Control | | Dissipation | Pg1(max) | 1.0† | W |
| Current Ik(av)max 100† m/A Maximum Control Grid/ Cathode Resistance (fixed bias) Rg1-k(max) 50† kG Maximum Control Grid/ Cathode Resistance (automatic bias) Rg1-k(max) 100† kG Maximum Mean Control | | | ik(pk)max | 700† | mA |
| Cathode Resistance (fixed bias) Maximum Control Grid/ Cathode Resistance (automatic bias) Maximum Mean Control Rg1-k(max) Rg1-k(max) Rg1-k(max) | | | lk(av)max | 100† | mA |
| Maximum Control Grid/ Cathode Resistance (automatic bias) Rg1-k(max) 100† ks2 Maximum Mean Control | | Cathode Resistance | | | |
| (automatic bias) Rg1-k(max) 100† kΩ Maximum Mean Control | | Maximum Control Grid/ | Rg1-k(max) | 50† | kΩ |
| 6:16 | | (automatic bias) | Rg1-k(max) | 100† | kΩ |
| | | | lg1(av)max | 5·0† | mA |
| | | | - ' ' | | |

[†] Each section

INTER-ELECTRODE CAPACITANCES

| Anode/Grid 1*† | ca-g1 | 0.06 | pF |
|------------------------------|---------|------|----|
| Grid 1/All other electrodes† | cg1-all | 10.5 | pF |
| Anode/All other electrodes† | ca-all | 3.2 | pF |
| Input Capacitance‡ | cin | 6.7 | pF |
| Output Capacitance: | Cout | 2.1 | pF |

^{*} Internally neutralised for push pull operation.

February, 1962

[†] Each section.

^{‡ 2} sections in push pull.



H.F. DOUBLE TETRODE

Indirectly heated

TENTATIVE

CHARACTERISTICS

| Mutual Conductance | gm | 4·5†‡ | mA/V |
|---|---------|-------|------|
| Inner Amplification Factor | µg1-g2 | 8·0†‡ | |
| † Each section. ‡At V _a =300V, V _{g2} =250V, I | a=30mA. | | |

DIMENSIONS

| Maximum Overall Length | 103 mm |
|------------------------|---------|
| Maximum Diameter | 47 mm |
| Maximum Seated Height | 91 mm |
| Approximate Net Weight | 2·3 ozs |

MOUNTING POSITION—Unrestricted, but when mounted horizontally anode pins should be in a horizontal plane.

CAPS-Wire 2 mm dia.

BASE-B7A



Viewed from free end of pins

CONNECTIONS

| Pin 1 | Heater | h |
|-----------|------------------------------|--------|
| Pin 2 | Control Grid, Section 1 | 21' |
| Pin 3 | Screen Grid | g2'g2" |
| Pin 4 | Cathode, Beam Plates, Shield | k,bp,s |
| Pin 5 | Heater Centre Tap | hct |
| Pin 6 | Control Grid, Section 2 | g1" |
| Pin 7 | Heater | h |
| Cap No. 1 | Anode, Section 1 | a' |
| Cap No. 2 | Anode, Section 2 | a" |

February, 1962



H.F. DOUBLE TETRODE Indirectly heated

TENTATIVE

GENERAL

The 11E16 is an internally neutralised h.f. double tetrode. It has a centre tapped heater and is intended for use as a push-pull amplifier or frequency trebler at frequencies up to 600 Mc/s.

RATING§

| Heater Voltage | Vh | 12.6 | 6. | 3 V |
|---|--------|------|-------|------|
| Heater Current | lh | 0.65 | 1.3 | 3 A |
| Maximum Operating Frequency | f(max) | | 600 N | 1c/s |
| Maximum Permissible Temperature of hottest part of bulb | , | | 200 | °C |
| Maximum Permissible Temperature of the base pins | | | 180 | °C |

[§] All limiting values are Absolute, not Design Centres.

RATING-Absolute values.

Class "C" r.f. push-pull power amplifier for c.w. telegraphy or f.m. telephony.

| Maximum Anode Voltage | V _{a(max)} | 600* | V |
|--|---------------------|------|----|
| Maximum Screen Grid Voltage | Vg2(max) | 300 | V |
| Maximum Negative Control Grid Voltage | Vg1(max) | -75 | ٧ |
| Maximum Heater/Cathode Voltage | Vh-k(max) | 100 | ٧ |
| Maximum Anode Dissipation | Pa(max) | 10† | W |
| Maximum Screen Grid Dissipation | Pg2(max) | 1.5† | W |
| Maximum Control Grid Dissipation | Pg1(max) | 0.5 | W |
| Maximum Peak Cathode Current | ik(pk)max | 260† | mA |

Continued

February, 1962

IIEI6

H.F. DOUBLE TETRODE

Indirectly heated

TENTATIVE

| Maximum Mean Cathode Current | lk(av)max | 557 | mA |
|---|------------|---------|-----|
| Maximum Control Grid/Cathode | | 4 4 5 7 | |
| Resistance (fixed bias) Maximum Control Grid/Cathode | Rg1-k(max) | 50† | kΩ |
| Resistance (automatic bias) Maximum Mean Control Grid | Rg1-k(max) | 100† | kΩ |
| Current | lg1(av)max | 2.5 | †mA |

^{*} For natural cooling $V_{a(max)}$ =600V up to 150 Mc/s but is limited to 250V at 600 Mc/s. For forced air cooling $V_{a(max)}$ =600V up to 300Mc/s but is limited to 400V at 600 Mc/s.

RATING—Absolute values.

Class "C" r.f. power amplifier with anode and screen modulation (carrier condition for use with modulation factor 1).

| Maximum Anode Voltage | Va(max) | 600* | V |
|--|----------------------|-------------|----|
| Maximum Screen Grid Voltage | Va(max) Vg2(max) | 300 | V |
| Maximum Negative Control Grid Voltage Maximum Heater/Cathode | Vg1(max) | -100 | ٧ |
| Voltage Maximum Anode Dissipation | Vh-k(max) Pa(max) | 100 6·7† | V |
| Maximum Screen Grid Dissipation | Pg2(max) | 1.2† | W |
| Maximum Control Grid Dissipation | Pg1(max) | 0.5† | W |
| Maximum Peak Cathode Current | ik(pk)max | 400† | mA |
| Maximum Mean Cathode Current | lk(av)max | 50† | mΑ |
| Maximum Mean Control Grid Current | lg1(av)max | 2.5† | mA |

^{*} For natural cooling $V_a(max)$ =600V up to 150 Mc/s but is limited to 250V at 600 Mc/s. For forced air cooling $V_a(max)$ =600V up to 250 Mc/s but is limited to 440V at 600 Mc/s.

[†] Each section.

[†] Each section.



H.F. DOUBLE TETRODE Indirectly heated

TENTATIVE

| PA A TOL | NG- | A L | | |
|----------|-----|------|---------|-------|
| KAII | NU | ADSO | iute va | lues. |

Frequency Trebler.

| Maximum Anode Voltage Maximum Screen Grid Voltage | V _{a(max)} V _{g2(max)} | 600 300 | V |
|--|---|-------------|----|
| Maximum Negative Control Grid Voltage Maximum Heater/Cathode | Vg1(max) | -200 | ٧ |
| Voltage Maximum Anode Dissipation | Vh-k(max) Pa(max) | 100 10† | V |
| Maximum Screen Grid Dissipation | Pg2(max | 1.5† | W |
| Maximum Control Grid Dissipation Maximum Peak Cathode | Pg1(max) | 0.5+ | W |
| Current Maximum Mean Cathode | ik(pk)max | 275† | mA |
| Current Maximum Control Grid/Cathode | lk(av)max | 50† | mA |
| Resistance (fixed bias) Maximum Control Grid/Cathode | Rg1-k(max) | 5 0† | kΩ |
| Resistance (automatic bias) Maximum Mean Control Grid | Rg1-k(max) | 100† | kΩ |
| Current + Fach section | lg1(av)max | 2.5† | mA |

† Each section.

RATING-Absolute values

Class "B" a.f. power amplifier or modulator.

| Maximum Anode Voltage Maximum Screen Grid Voltage Maximum Negative Control | V _{a(max)} V _{g2(max)} | 600 V 300 V |
|--|---|----------------|
| Grid Voltage | Vg1(max) | -7 5 V |
| Maximum Heater/Cathode Voltage Maximum Anode Dissipation Maximum Screen Grid | Vh-k(max) Pa(max) | 100 V 10† W |
| Dissipation | Pg2(max) | 1.5† W |

Continued

February, 1962

ADVANCE DATA, Page 3



IIEI6 H.F. DOUBLE TETRODE Indirectly heated

TENTATIVE

| Maximum Control Grid Dissipation | Pg1(max) | 0.5 | t W |
|---|------------|------|-----|
| Maximum Peak Cathode Current | ik(pk)max | 120† | mA |
| Maximum Mean Cathode Current | lk(av)max | 55† | mA |
| Maximum Control Grid/Cathode Resistance (fixed bias) | Rg1-k(max) | 50† | kΩ |
| Maximum Control Grid/Cathode Resistance (automatic bias) | Rg1-k(max) | 100† | kΩ |

† Each section

INTER-ELECTRODE CAPACITANCES

| Anode/Grid 1 *† | ca-g1 | 0.04 pF |
|------------------------------|---------|---------|
| Grid 1/All other electrodes† | cg1-all | 7.5 pF |
| Anode All other electrodes† | ca-all | 2.6 pF |
| Input Capacitance‡ | cin | 4.4 pF |
| Output Capacitance‡ | Cout | 1.6 pF |

^{*} Internally neutralised for push-pull operation.

CHARACTERISTICS†‡

| Mutual Conductance | gm | 3·0 mA/V |
|----------------------------|--------|----------|
| Inner Amplification Factor | μg1-g2 | 8·0 |
| + Fach section. | | |

DIMENSIONS

| Maximum Overall Length | 85 | mm |
|------------------------|----|----|
| Maximum Diameter | 47 | mm |
| Maximum Seated Height | 73 | mm |
| Approximate Net Weight | 2 | OZ |

February, 1962

ADVANCE DATA, Page 4

[†] Each section.

^{± 2} sections in push-pull.

 $[\]pm$ At $V_a = 300V$, $V_g = 250V$, $I_a = 20mA$.



H.F. DOUBLE TETRODE

Indirectly heated

TENTATIVE

MOUNTING POSITION—Mobile operation; vertical, base up or down. Fixed station operation; vertical, base up or down. Horizontal; anode pins in horizontal plane.

CAPS-Wire 2mm dia.

BASE-B7A



Viewed from free end of pins

CONNECTIONS

| Pin 1 | Heater | h |
|-----------|------------------------------|---------|
| Pin 2 | Control Grid, Section 1 | g1 ' |
| Pin 3 | Screen Grid | 82' 82" |
| Pin 4 | Cathode, Beam Plates, Shield | k,bp,s |
| Pin 5 | Heater Centre Tap | hct |
| Pin 6 | Control Grid, Section 2 | g1" |
| Pin 7 | Heater | h |
| Cap No. 1 | Anode, Section 1 | a' |
| Cap No. 2 | Anode, Section 2 | a" |

ACCOUNT ALBERT AS

Annual production in the MO BERGE BRIDE OF THE PROPERTY OF THE

of the other was

A STATE OF THE PARTY.



I2EI

BEAM TETRODE

Indirectly heated-for parallel operation

GENERAL

The I2EI is intended for use as a series or shunt control valve in stabilised power packs.

RATING

| Heater Voltage (volts) | Vh | 6.3 |
|---|------------------------|-------|
| Heater Current (amps) | lh. | 1.6 |
| Maximum Anode Voltage (volts) | V _{a(max)} | 800 |
| Maximum Screen Voltage (volts) | Vg2(max) | 300 |
| Maximum Control Grid Voltage (volts) Maximum Voltage between | Vg1(max) | -100 |
| g ₁ and g ₂ (volts) | $\forall g_1-g_2(max)$ | 400 |
| Mutual Conductance (mA/V) | gm gr(ax) | 14* |
| Inner µ | μg1,g2 | 5.3 * |
| Maximum Anode Dissipation (watts) | Pa(max) | 35 |
| Maximum Screen Dissipation (watts) | Pg2(max) | 5.0 |
| Maximum Cathode Current (mA) Maximum Potential Heater/Cathode | lk(max) | 300 |
| (volts D.C.) | V _{h-k(max)} | 300† |
| * Taken at $V_a = V_{g_2} = 150V$ | a := 200mA. | |

[†] Provided the cathode is positive.

All maximum ratings are Absolute values not Design Centres.

INTER-ELECTRODE CAPACITANCES (pF)

| Grid/Earth | c _{in} | 23.0 |
|-------------|-----------------|------|
| Anode/Earth | cout | 8.0 |
| Anode/Grid | ca.gı | 0.85 |

"Earth" denotes the remaining earthy potential electrodes and heater joined to cathode.

December, 1961



BEAM TETRODE

Indirectly heated-for parallel operation

DIMENSIONS

| Maximum Overall Length (mm) | 146 |
|---------------------------------|-------|
| Maximum Diameter (mm) | 54 |
| Maximum Seated Height (mm) | 133 |
| Approximate Nett Weight (ozs) | 2 1/2 |
| Approximate Packed Weight (ozs) | 7 |


MOUNTING POSITION—Vertical

If run horizontally then the axis AB must be on a horizontal plane.

BULB—Clear

TOP CAP-American miniature (CT 1)

BASE—International Octal (108)



CONNECTIONS


| Pin 1 | No connection | NC |
|---------|---------------|----------------|
| Pin 2 | Heater | h |
| Pin 3 | No connection | NC |
| Pin 4 | Screen Grid | g ₂ |
| Pin 5 | Control Grid | gı |
| Pin 6 | No connection | NC |
| Pin 7 | Heater | h |
| Pin 8 | Cathode | k |
| Top Cap | Anode | a |

Indicates a change

issue 1, Page 2



BEAM TETRODE Indirectly heated—for parallel operation






BEAM TETRODE Indirectly heated—for parallel operation

AVERAGE CHARACTERISTIC CURVES

These curves were taken with a short ducation pulse of 12 y sec. Pulse ratio 400:1. Vg2=150




December, 1961



12E1

BEAM TETRODE Indirectly heated—for parallel operation




December, 1961



12E1

BEAM TETRODE Indirectly heated—for parallel operation



December, 1961



TENTATIVE

GENERAL

The 12E12 is a Pulse Modulator Tetrode, having a maximum anode dissipation of 60 watts, and a maximum peak anode current of 15 amps. It has an indirectly heated cathode, and is intended for use in Radar equipment.

| RATING | | | |
|---|---------|----------------|--------|
| Heater Voltage | (volts) | ٧h | 26 |
| Heater Current | (amps) | l _h | 1.6 |
| Maximum Anode Voltage | (kV) | $V_{a(max)}$ | 11.0 |
| Maximum Screen Grid Operating Voltage | (kV) | Vg2(max) | 1.25 |
| Maximum Screen Grid Voltage $(I_a = 0)$ | (kV) | Vg2(max) | 1.35 |
| Maximum Control Grid Voltage (Negative) | (volts) | −Vg1(max) | _1,000 |
| Maximum Control Grid Voltage (Positive Peak) | (volts) | +Vg1(pk)max. | 300 |
| Maximum Anode Dissipation | (watts) | Pa(max) | 60 |
| Maximum Screen Dissipation | (watts) | Pg2(max) | 8 |
| Maximum Grid 1 Dissipation | (watts) | Pg1(max) | 3 |
| Maximum Peak Anode Current | (amps) | la(pk)max. | 15† |
| Maximum Grid 1 Series Resistance | (kΩ) | Rg1 | 100 |
| Minimum Screen Grid Series Resistance | (kΩ) | Re2 | 20* |

^{*} The Screen Grid should be decoupled to earth with a condenser.

Rating (Continued Overleaf)

[†] For a duty cycle not greater than 0.001. With peak currents in excess of 5 amps the product of peak current in amps and pulse duration in microseconds should not exceed 30.

TENTATIVE

The current-time product limit still applies for currents less than 5 amps, the maximum duty cycle then being limited by the anode dissipation.

The valve should not operate for longer than 5 μ s in any

100 μs period.

A minimum cathode heating time of three minutes should elapse before any cathode current is drawn.

All Maximum Ratings are Absolute values not Design

Centres.

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid 1 (max) | ca-g1 | 2.0 |
|--------------------|-------|-----|
| Cathode/Grid 1 | cg-k | 37 |
| Anode/Cathode | ca-k | 7.5 |

DIMENSIONS

| Maximum Overall Length | (mm) | 150 |
|--------------------------|--------|-----|
| Maximum Diameter | (mm) | 65 |
| Maximum Seated Height | (mm) | 142 |
| Approximate Nett Weight | (ozs) | 53 |
| Approximate Packed Weigh | t(ozs) | 24 |

MOUNTING POSITION—Vertical preferred, but if horizontal the grid plane should be vertical.

TYPICAL OPERATION-As Series Modulator.

| Anode Voltage Supply | | (kV) | $V_{a(b)}$ | 9.5 |
|----------------------------|----|----------|------------|-------|
| Screen Voltage | | (kV) | Vg2 | 1.2 |
| Grid No. 1 Bias | | (volts) | -Vg1 | -800 |
| Grid No. 1 Pulse | 50 | (volts) | +Vg1 | 1,020 |
| Anode Current Pulse | | (amps) | la(pk) | 10 |
| Anode Load | | (ohms) | Ra | 800 |
| Peak Pulse Power Input | | (kW) | Pin(pk) | 100 |
| Peak Pulse Power Output | | (kW) | Pout(pk) | 80 |
| Output Voltage | | (kV) | Vout | 8 |
| Pulse Duration | , | (μ secs) | tp | 2 |
| Pulse Repetition Frequency | | (p/s) | P.R.F. | 500 |

Decembers 1961



TENTATIVE

TOP CAP-CT3

BASE-B4A




Viewed from free end of pins

CONNECTIONS

| Pin 1 | Heater | h |
|---------|-----------------|-----|
| Pin 2 | Screen Grid | 82 |
| Pin 3 | Control Grid | g1 |
| Pin 4 | Heater, Cathode | h,k |
| Тор Сар | Anode | 2 |

TENTATIVE



All Dimensions in mm.

- * Eccentricity with respect to centre line of base.
- † Straight side of top cap.



BEAM TETRODE

Indirectly heated

GENERAL

The 12E13 is a beam tetrode which has a maximum anode dissipation of 35 watts and a maximum cathode current of 175 mA. It is intended for use as a series or parallel regulator valve in stabilised power supply units.

It is also suitable for use as the output stage of an AF amplifier for which two valves will provide up to 100 watts output. Under intermittent conditions, an output of 150 watts is obtainable under Class B conditions.

RATING

| Heater Voltage | Vh | 6.3 | ٧ |
|---|---------------------|-------|----|
| Heater Current | lh . | 1.6 | A |
| Maximum Anode Voltage | V _{a(max)} | 600 | ٧ |
| Maximum Screen Voltage Maximum Anode+Screen | Vg2(max) | 600 | ٧ |
| Voltage | $V_a + g2(max)$ | 600* | ٧ |
| Maximum Anode Dissipation | Pa(max) | 35 | W |
| Maximum Screen Dissipation | Pg2(max) | 6 | W |
| Maximum Anode+Screen Dissipation | Pa+g2(max) | 40* | w |
| Maximum Cathode Current | lk(max) | 175 | mA |
| Maximum Heater/Cathode Voltage | Vh-k(max) | 150 | ٧ |
| Maximum Grid/Cathode Resistance (cathode bias) | () | 220** | kΩ |
| Maximum Grid/Cathode Resistance (fixed bias) | | 100** | kΩ |
| | | | |

^{*} Triode connection

^{**} Resistance tolerance ± 20%



BEAM TETRODE

Indirectly heated

INTER-ELECTRODE CAPACITANCES

| Grid 1/Earth | cin | 16 pF |
|--------------|-------|--------|
| Anode/Earth | cout | 12 pF |
| Anode/Grid 1 | ca-g1 | 1·2 pF |
| | | |

DIMENSIONS

| Maximum Overall Length | 125 | mm |
|------------------------|-----|----|
| Maximum Seated Height | 110 | mm |
| Maximum Diameter | 52 | mm |

MOUNTING POSITION—Unrestricted.

If mounted horizontally, pins 4 and 8 should be in a vertical plane with an inter valve spacing of not less than 4 inches. With two or more valves, vertically mounted, pins 4 and 8 should preferably be in line. Free air circulation should be available and the hottest part of the bulb should not exceed 250°C.

CHARACTERISTICS—Pentode Connection

| Anode Voltage | Va | 250 V |
|--------------------|--------|--------|
| Screen Voltage | Vg2 | 250 V |
| Anode Current | la - | 140 mA |
| Mutual Conductance | gm | 11mA/V |
| Anode Impedance | ra | 12 kΩ |
| Inner Mu | μg1-g2 | 8 |

CHARACTERISTICS—Triode Connection

| Anode, Screen Voltage | Va,g2 | 250 V |
|-----------------------|-------|--------|
| Anode Current | la"° | 160 mA |
| Mutual Conductance | gm | 12mA/V |
| Anode Impedance | ra | 670 Ω |
| Amplification Factor | μ | 8 |

December, 1961



BEAM TETRODE

Indirectly heated

| Supply Voltage | $V_{a(b)}$ | 500 | V |
|---|-----------------|------------------|------------|
| Anode Voltage | Va | 425 | ٧ |
| Screen Voltage | Vg2 | 425 | V |
| Anode+Screen Current (maximum signal) | la+g2(max sig) | 2×100 | mA |
| Anode+Screen Current (quiescent) | $I_a+g2(o)$ | 2×87 | mA |
| Anode+Screen Dissipation (quiescent) | Pa+g2(o) | 2×40 | W |
| Anode+Screen Dissipation (maximum signal) | Pa+g2(max sig) | 2×18 | W |
| Grid Bias Applied (approx.) | V _{g1} | -50 | V |
| Cathode Bias Resistance | Rk | $2\times525\pm5$ | $%*\Omega$ |
| Input Voltage (grid-grid) | $V_{in(g-g)}$ | 90 | V |
| Anode Load (anode-anode) | RL(a-a) | 6 | kΩ |
| Output Impedance | Zout | 4.5 | kΩ |
| Power Output | Pout | 50 | W |
| Distortion | D | 1† | % |
| Intermodulation | | 5† | % |

^{*} Separate bias resistors are essential.

[†] Average pair.

| TYPICAL | OPERATION | Push-Pull Illtra | Linear, Fixed Bias |
|---------|-----------|------------------|--------------------|
| | | | |

| Supply Voltage | $V_{a(b)}$ | 560 | ٧ |
|--|-----------------------|---------|----|
| Anode Voltage | Va | 550 | ٧ |
| Screen Voltage | Vg2 | 550 | ٧ |
| Anode + Screen Current (quiescent) | l _a +g2(o) | 2×50 r | πA |
| Anode+Screen Current (maximum signal) | la+g2(max sig) | 2×150 r | nΑ |

December, 1961

BEAM TETRODE

Indirectly heated

| Anode+Screen Dissipation (quiescent) | Pa+g2(o) | 2×30 | W |
|--------------------------------------|-----------------|---------------|----|
| Anode+Screen Dissipation | | 0 22 | w |
| (maximum signal) | Pa+g2(max) | 2×33 | VV |
| Grid Bias Applied (approx) | V _{g1} | -80* | V |
| Input Voltage (grid-grid) | Vin(g-g) | 120 | ٧ |
| Anode Load (anode-anode) | RL(a-a) | 4.5 | kΩ |
| Output Impedance | zout | 6.5 | kΩ |
| Power Output | Pout | 100 | W |
| Distortion | D | 3 to 6† | % |
| Intermodulation | | 12 | % |

TYPICAL OPERATION—Push-Pull Triode Connection Cathode Bias

| | Cacilo | de Dias | | |
|---------------------------|-------------|---------------|---------------|-----|
| Supply Voltage | $V_{a(b)}$ | 400 | 485 | V |
| Anode Voltage | Va | 350 | 425 | V |
| Screen Voltage | Vg2 | 350 | 425 | V |
| Anode+Screen Current | | | | |
| (quiescent) | $l_a+g2(o)$ | 2×67 | 2×85 | mA |
| Anode+Screen Current | | | | |
| (maximum signal) | la+g2(ma | 2×72 | 2×90 | mA |
| Anode+Screen Dissipat | ion | | | |
| (quiescent) | Pa+g2(o) | 2×24 | 2×40 | W |
| Grid Bias Applied | 0 () | | | |
| (approx) | Vg1 | -38 | -48 | ٧ |
| Cathode Bias Resistance | Rk 2× | 525±5%* | 2×525±59 | %*Ω |
| Input Voltage (grid-grid) | Vin(g-g) | 60 | 70 | V |
| Anode Load (anode- | (8 8) | | | |
| anode) | RL(a-a) | 4 | 4 | kΩ |
| Output Impedance | Zout | 2.5 | 2.5 | kΩ |
| Power Output | Pout | 15 | 27 | W |
| Distortion | D | 1 to 3† | 1 to 3† | % |
| Intermodulation | | 6 | 6 | % |
| | | | | |

^{*} Separate bias resistors are essential.

^{*} A negative bias range of $70\pm25\%$ is recommended. † The distortion will vary according to the degree of matching.

[†] The distortion will vary according to the degree of matching



BEAM TETRODE

Indirectly heated

BASE-International Octal (108)



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | Shield | s |
|-------|----------------------|------------|
| Pin 2 | Heater | h |
| Pin 3 | Anode | a |
| Pin 4 | Screen Grid | g 2 |
| Pin 5 | Control Grid | g1 |
| Pin 6 | No Pin | NP |
| Pin 7 | Heater | h |
| Pin 8 | Cathode, Beam Plates | k,bp |

December, 1961




EDISWAN

12E13

BEAM TETRODE

Indirectly heated

CHARACTERISTIC CURVES: $I_a,I_{g2}/V_a$ ($V_{g1} = OV$)




December, 1961



12E13

Indirectly heated

CHARACTERISTIC CURVES: $I_a,I_{g2}/V_a$ ($V_{g2}=100V$)




December, 1961



12E13

Indirectly heated

CHARACTERISTIC CURVES: $I_a,I_{g2}/V_a$ ($V_{g2}=200V$)






12E13

Indirectly heated

CHARACTERISTIC CURVES: I_a/V_a

Triode Connection






12E13

Indirectly heated


CHARACTERISTIC CURVES: $I_a,I_{g2}/V_a$ (V_{g2} =300V)





BEAM TETRODE

Indirectly heated



* Position of the screen grid taps on the output transformer.

December, 1961 Issue 1, Page 11



BEAM TETRODE Indirectly heated

TENTATIVE

GENERAL

The 12E14 is an indirectly heated Beam Tetrode with a maximum anode dissipation of 35W. It is suitable for use in stabilised power supply units.

RATING-Absolute Values

| Heater Voltage | Vh | 6.3 | ٧ |
|---|--------------|------|----|
| Heater Current | Ih | 1.6 | Α |
| Maximum Anode Voltage | $V_{a(max)}$ | 800 | ٧ |
| Maximum Screen Voltage | Vg2(max) | 300 | ٧ |
| Maximum Control Grid Voltage | Vg1(max) | -100 | ٧ |
| Maximum Control Grid/Screen Voltage | Vg1-g2(max) | 400 | ٧ |
| Maximum Anode Dissipation | Pa(max) | 35 | W |
| Maximum Screen Dissipation | Pg2(max) | 5 | W |
| Maximum Cathode Current | lk(max) | 300 | mΑ |
| Maximum Heater/Cathode Voltage d.c. (heater negative) | Vh-k(max) | 300 | ٧ |

DIMENSIONS

| Maximum Overall Length | 106 | mm |
|------------------------|-----|----|
| Maximum Diameter | 44 | mm |
| Maximum Seated Height | 93 | mm |


MOUNTING POSITION—Vertical. If run horizontally then axis AB must be on a horizontal plane.



BEAM TETRODE Indirectly heated

TENTATIVE

BASE-108



Viewed from free end of pins

CONNECTIONS

| Pin 1 | Internal Connection | IC |
|--------|---------------------|----|
| Pin 2 | Heater | h |
| Pin 3 | Anode | a |
| Pin 4 | Grid 2 | g2 |
| Pin 5 | Grid 1 | g1 |
| Pin 6* | Beam Plates | bp |
| Pin 7 | Heater | h |
| Pin 8 | Cathode | k |

^{*} Should be connected to Cathode.



13EI

BEAM TETRODE

Indirectly heated-for D.C. Control Applications

GENERAL

This Low Impedance Beam Tetrode is intended for general D.C. Control applications and has a centre tapped heater. It is suitable for Triode connection and has a maximum anode dissipation of 90 watts.

RATING

| Heater Voltage | (volts) | Vh | 26.0 | 13.0 | |
|--|--------------------------------------|------------|------|---------|---|
| Heater Current | (amps) | lh . | 1.3 | 2.6 | |
| | e Voltage (volts) | Va(max) | 800 | 1500† | 4 |
| Maximum Scree | n Voltage (voits) | Vg2(max) | 300 | | |
| | rol Grid Voltage | Vg1(max) | -10 | 00 | |
| Maximum Anod | e Dissipation | g (max) | 28 | Total S | |
| (watts) | | Pa(max) | 90 | | |
| Maximum Scree | n Dissipation | . =(=) | | | |
| (watts) | • | Pg2(max) | 10 | | |
| sipation (Trio | e plus Screen Dis- de Connection) | | | 5-, 7 | |
| (watts) | | Pa+g2(max) | 95 | | 4 |
| Maximum Contr (watts) | ol Grid Dissipation | Pg1(max) | 1 | | _ |
| Maximum Catho | de Current (mA) | lk(max) | 800 | 5000† | - |
| Maximum Heate | r/Cathode Voltage | e K(IIIax) | • | | |
| (volts D.C.) (I | Heater-ve) | Vh-k(max) | 300 | | |
| Mutual Conduct | | n n(max) | | | |
| Connection) (| mA/V) | gm | 35* | | |
| Amplification Fa | ctor (Triode | | | | |
| Connection) | | μ t | 4.5* | | |
| Anode Resistance | $e(\delta v_a/\delta i_a)$ (Triode | | 90 | | |
| Connection) ($*V_a = 150 \text{ vol}$ | | ra(t) | 130* | | |
| Va=130 VOI | $I_a = 500 \text{m}$ | Α. | | | |
| | | | | | |

All maximum ratings are absolute values not design centres.

† Series pulse rating. For peak currents greater than 2 amps, the product of the peak current and pulse duration in amp-microseconds should not exceed 10. The valve should not operate for longer than 5 µs in any 100 µs period.

> Indicates a change ← Issue 1, Page 1



13EI

BEAM TETRODE

Indirectly heated-for D.C. Control Applications

| INTER-ELECTRODE | CAPACITANCES | (pF) | i |
|-----------------|--------------|------|---|
|-----------------|--------------|------|---|

| Control Grid/Earth | cin | 56 |
|--------------------|-------|------|
| Anode/Earth | Cout | 20-4 |
| Anode/Control grid | ca-g1 | 1.3 |

DIMENSIONS


| Maximum Overall Length | (mm) | 166.0 |
|---------------------------|-------|-------|
| Maximum Diameter | (mm) | 65.0 |
| Maximum Seated Height | (mm) | 157.0 |
| Approximate Nett Weight | (ozs) | 6.0 |
| Approximate Packed Weight | (ozs) | 30.0 |

MOUNTING POSITION—Vertical

BULB-Clear

BASE-B7A

Viewed from free end of pins.



VALVEHOLDER-Ediswan Clix Cat. No. VH117/701

CONNECTIONS

| Pin 1 | Heater |
|-------|-------------------------|
| Pin 2 | Heater Centre Tap h tap |
| Pin 3 | Control Grid g1 |
| Pin 4 | Cathode |
| Pin 5 | Screen Grid g2 |
| Pin 6 | Anode |
| Pin 7 | Heater h |

December, 1961

Indicates a change Lissue 1, Page 2


Associated Electrical Industries Limited



13EI

BEAM TETRODE Indirectly heated—for D.C. Control Applications

AVERAGE CHARACTERISTIC CURVES : I_a/V_{g1} V_a =600V Curves taken with short duration pulse






BEAM TETRODE

Indirectly heated-for D.C. Control Applications

AVERAGE CHARACTERISTIC CURVES: Ig2/Vg1 Va=600V


Curves taken with short duration pulse





BEAM TETRODE Indirectly heated—for D.C. Control Applications


AVERAGE CHARACTERISTIC CURVES: I_a/V_{g1}
TRIODE CONNECTED
Curves taken with short duration pulse





BEAM TETRODE Indirectly heated—for D.C. Control Applications


AVERAGE CHARACTERISTIC CURVES: I_a/V_a $V_g = 100V$ Curves taken with short duration pulse





I3EI BEAM TETRODE Indirectly heated—for D.C. Control Applications

AVERAGE CHARACTERISTIC CURVES: Ig2/Va
Vg2=100V
Curves taken with short duration pulse



. 1451 BUCATIT MABE Leftersky hearts - for D.C. C. corol Applications

*ART : ELANOS ALEBEAC PERENCIONAL ESPACA



13E12

BEAM TETRODE

TENTATIVE

GENERAL

The 13E12 is an indirectly heated Beam Tetrode having a centre tapped heater. It is suitable for use in stabilised power supply units, servo-mechanisms, etc.

RATING—Absolute Values

| Heater Voltage | V_h | 26-0 | 13-0 V |
|---|-----------------------|------|--------|
| Heater Current | lh | 1.3 | 2.6 A |
| Maximum Anode Voltage | V _{a(max)} | 800 | ٧ |
| Maximum Screen Voltage | Vg2(max) | 300 | ٧ |
| Maximum Control Grid Voltage | Vg1(max) | -100 | ٧ |
| Maximum Anode Dissipation | Pa(max) | 90 | W |
| Maximum Screen Dissipation | Pg2(max) | 10 | W |
| Maximum Anode + Screen Dissipation (Triode Connected) Maximum Control | Pa+g2(max) | 95 | w |
| Grid Dissipation Maximum Cathode | Pg1(max) | 1 | W |
| Current | lk(max) | 800 | mA |
| Maximum Heater/ Cathode Voltage D.C. (Cathode Positive) | V _{h-k(max)} | 300 | V |

INTER-ELECTRODE CAPACITANCES (pF)

| Control Grid/Earth | cin | 62.0 |
|--------------------|-------|------|
| Anode/Earth | Cout | 17.0 |
| Anode/Control Grid | Ca-91 | 1.0 |

December, 1961

ADVANCE DATA, Page 1





I3EI2 BEAM TETRODE TENTATIVE

DIMENSIONS

| Maximum Overall Length | | 140 mm |
|---------------------------|--|--------|
| Maximum Diameter | | 65 mm |
| Maximum Seated Height | | 128 mm |
| Approximate Nett Weight | | 5 ozs |
| Approximate Packed Weight | | 29 ozs |

MOUNTING POSITION—Vertical

CHARACTERISTICS—Triode Connected

| Anode Voltage | Va | 150 V |
|------------------------|----|----------------|
| Anode Current | la | 500 mA |
| Mutual Conductance | gm | 25 mA/V |
| Amplification Factor | μ | 2.8 |
| Valve Anode Resistance | | 1570 1 1 1 1 1 |
| (approx.) | ra | 110 Ω |

BASE-B7A



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | | Heater | h |
|-------|---|-------------------|-----|
| Pin 2 | | Heater Centre Tap | hct |
| Pin 3 | 1 | Control Grid | g1 |
| Pin 4 | | Cathode | k |
| Pin 5 | | Screen Grid | g2 |
| Pin 6 | | Anode | a |
| Pin 7 | | Heater | h |

December, 1961

ADVANCE DATA, Page 2

Electronic Components Division Tel.: GERrard 9797



ES85 RADIATION COOLED TRIODE

GENERAL

The ES85 is a directly heated Thoriated tungsten filament triode, designed to operate as a Class B amplifier or modulator and as a Class C amplifier or oscillator.

RATING

| Filament Voltage (volts) | Vf | 10 |
|---|----------------|-------|
| Filament Current (amps) | l _f | 3.25 |
| Maximum Anode Voltage (kV) | Va(max) | 1.25 |
| Maximum Anode Dissipation (watts) | Pa | 85 |
| Mutual Conductance (mA/V) | 8m | 3.7 |
| Amplification Factor* | μ | 12.7 |
| Anode Impedance (ohms) | ra | 3,450 |
| Maximum Operating Frequency | _ | |
| at Full Rating (Mc/s) | | 6 |
| Maximum Audio Output 2 Valves | | |
| (watts) (Class B Push-Pull) | Pout | 310 |
| Distortion at Maximum Output | Dtot | 3% |
| * Taken at $V_a = I kV$; $V_g = -55 v$. | | |

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid | cga | 13 |
|----------------|------|-----|
| Anode/Filament | Cout | 4 |
| Grid/Filament | cin | 6.5 |

DIMENSIONS

| Maximum Overall Length (mm) | 204 |
|-----------------------------|-----|
| Maximum Diameter (mm) | 57 |

BASE-Jumbo


NOTE: This valve should be mounted so that its filament is in vertical plane.

December, 1961



EDISWAN


ES85
RADIATION COOLED TRIODE






ES85 RADIATION COOLED TRIODE

GRID CURRENT - ANODE VOLTAGE CHARACTERISTIC
VALVETYPE ES 85





ES85
RADIATION COOLED TRIODE



December, 1961



ESTION RADIATION COOLED TRIODE

TENTATIVE

GENERAL

The ES1101 is an indirectly heated power triode intended for use under zero bias conditions in Class B Push Pull Audio Amplifiers. It has a maximum anode dissipation of 40 watts and a maximum power output per pair of valves of 200 watts.

RATING

| Heater Voltage (volts) | ٧h | 7.5 |
|-------------------------------------|-----------|------|
| Heater Current (amps) | lh | 1.2 |
| Maximum Anode Voltage (volts) | Va(max) | 1250 |
| Maximum (Mean) Cathode Current (mA) | lk(av)max | 200 |
| Maximum Anode Dissipation (watts) | Pa(max) | 40 |
| Mutual Conductance (mA/V) | gm | 3.0* |
| Amplification Factor | μ | 72* |
| Anode Impedance (kilohms) | ra | 24* |

^{*} Measured at Va=1000V; Ia=40mA

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid | ca-g | 4.0 |
|---------------|------------------|-----|
| Anode/Cathode | c _{a-k} | 1.0 |
| Grid/Cathode | cg-k | 5.2 |

DIMENSIONS

| Maximum Overall Length | (mm) | 156 |
|---------------------------|-------|-----|
| Maximum Seated Height | (mm) | 141 |
| Maximum Diameter | (mm) | 52 |
| Approximate Nett Weight | (ozs) | 2 |
| Approximate Packed Weight | (ozs) | 4 |

December ,1961

ESII0I RADIATION COOLED TRIODE

TENTATIVE

MOUNTING POSITION-Vertical, base downwards

| TYPICAL OPERATION—Push Pu | | udio C es per | |
|---|----------------------|------------------|------|
| Anode Voltage (volts) | Va | 1000 | 1250 |
| Anode Current (no signal) (mA) | Ia(0) | 25 | 20 |
| Anode Current (maximum signal) (mA) | Ia(max sig) | 137 | 120 |
| Grid Bias (volts) | Vg | 0 | -4.0 |
| Grid Current (Mean) (mA) | lg(av) | 25 | 20 |
| Grid Current (Peak) (mA) | lg(pk) | 50 | 42 |
| Input Voltage (grid to grid) (peak) (volts) | V _{in(g-g)} | 200 | 200 |
| Drive Power (watts) | Pdr | 2.5 | 2.2 |
| Anode Dissipation (no signal) (watts) | Pa(0) | 12.5 | 12.5 |
| Anode Dissipation (max signal) (watts) | Pa(max sig) | 25 | 25 |
| Anode Load (anode to anode) (kilohms) | R _{a-a} | 10 | 13 |
| Power output (total) (watts) | Pout | 175 | 200 |
| Distortion (%) | D | 6 | 6 |
| Input Impedance (grid to grid) (kilohms) | Zin(g-g) | 4 | 4.5 |
| Output Impedance (kilohms) | Zout | 15 | 15 |

The above conditions apply to speech and music only. For continuous sine wave modulation the anode load should be increased by not less than 20% to avoid excessive dissipation.

ESI101

RADIATION COOLED TRIODE

TENTATIVE

BASE-UX4



Viewed from free end of pins.

TOP CAP-CT2

CONNECTIONS

| Heater | h |
|---------|---------------------------|
| Cathode | k |
| Grid | g |
| Heater | h |
| Anode | 2 |
| | Cathode Grid Heater |



Indian supposed in the contract of the contrac

1





ESI 102 RADIATION COOLED TRIODE TENTATIVE

GENERAL

The ES1102 is a directly heated power triode intended for use in Class AB₁ or AB₂ Push Pull Amplifiers having a maximum power output of 300 watts per pair of valves. It has a maximum anode dissipation of 100 watts.

RATING

| Filament Voltage (volts) | Vf | 6.0 |
|-----------------------------------|---------------------|-------|
| Filament Current (amps) | lf | 2.7 |
| Maximum Anode Voltage (volts) | V _{a(max)} | 1250 |
| Maximum Mean Cathode Current (mA) | lk(av)max | 250 |
| Maximum Anode Dissipation (watts) | Pa(max) | 100 |
| Mutual Conductance (mA/V) | gm | 3.9* |
| Amplification Factor | μ | 5.5* |
| Anode Impedance (kilohms) | ra | 1-41* |

^{*} Measured at Va=1kV; la=100mA.

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid | c _{a-g} | 15.7 |
|----------------|------------------|------|
| Anode/Filament | ca-f | 10-8 |
| Grid/Filament | cg.f | 15.8 |

DIMENSIONS

| Maximum Overall Length | (mm) | 192 |
|---------------------------|-------|-----|
| Maximum Seated Height | (mm) | 182 |
| Maximum Diameter | (mm) | 65 |
| Approximate Nett Weight | (lbs) | 1 |
| Approximate Packed Weight | (lbs) | 2 |

ESI 102 RADIATION COOLED TRIODE TENTATIVE

MOUNTING POSITION—Vertical, base downwards.

TYPICAL OPERATION-Push-Pull. Values per valve.


| | | Class | s AB ₁ | Clas | s AB ₂ |
|---|-------------------------|-------|-------------------|------|-------------------|
| Anode Voltage (maximum signal) (kV) | V _{a(max sig)} | 1.0 | 1.25 | 1.0 | 1.25 |
| Anode Current (no signal) (mA) | la(o) | 50 | 50 | 50 | 50 |
| Anode Current (maximum Signal) (mA) | la(max sig) | 165 | 150 | 150 | 182 |
| Anode Dissipation (no signal) (watts) | Pa(o) | 55 | 70 | 55 | 55 |
| Anode Dissipation (maximum signal) (watts) | Pa(max sig) | 53 | 100 | 50 | 80 |
| Grid Bias (volts) | Vg - | -200 | -225 | -200 | -225 |
| Input Voltage (grid to grid) (peak) (volts) | | 400 | 450 | 500 | 560 |
| | Vin(g-g)pk | - | - | | |
| Grid Current (mA) | lg | 0 | 0 | 7-5 | 10 |
| Anode Load (Anode to Anode) (kilohms) | R _{a-a} | 4 | 8 | 8 | 8 |
| Power Output (total)(watts) | Pout | 125 | 175 | 200 | 300 |
| Distortion (%) | | 4 | 5 | 6 | 6 |
| | | | | | |

The power supply should have an impedance not greater than 400 ohms.


Under Class AB2 conditions the anode dissipation rises to a maximum at approximately one half of full output.



ESTI02 RADIATION COOLED TRIODE TENTATIVE




BASE-L4



All dimensions in mm.

ESTI02 RADIATION COOLED TRIODE TENTATIVE

CHARACTERISTIC CURVES: Ia/Va



December, 1961

Rectifiers and Thyratrons



SELECTION CHART HIGH VOLTAGE RECTIFIERS

| | HALF-WAV | HALF-WAVE MERCURY VAPOUR | APOUR | |
|----------------|----------|--|---------|--------|
| | PEAK CAT | PEAK CATHODE CURRENT (Amps) | (Amps) | |
| P.I.V. (kV) | 1.25 | 0.9 | 0-9 | 7.0 |
| 10 | ESU76 | ESU150 | ESU872 | |
| | ESU886 | | ESU8008 | |
| | ESU101 | E de la constante de la consta | Ŝ | |
| 15 | | | ESU200 | ESU575 |
| | | | | ESU673 |

December, 1961



SELECTION CHART HIGH VOLTAGE RECTIFIERS

| PEAK CATHODE CURRENT (Amps) 0.18 0.375 0.6 19G6 19G3 19H4 | | 1.0 | | | | 19H5 | | ESU74 |
|--|------------|-------|------|------|------|------|------|-------|
| 0.18 0.375 19G6 19G3 | | 9.0 | | | 19H1 | | | |
| 1944 | CATHODE CU | 0.375 | | 19G3 | | | | |
| | PEAK | 0.18 | 19G6 | | | | 19H4 | |

December, 1961



Condensed Data on Obsolete Types

| | | | | | | I dX. | Cathode | l'lax. | |
|-----------|------------------|---------|---------------------|--------|--------|-------------------------------------|---------|--------|-----------|
| Туре | Class | \ \ | Vh Ih Ik(pk) P.I.V. | 1k(pk) | P.I.V. | Mean | Heating | Anode | Notes |
| | | (volts) | (amps) | (amps) | (kV) | (volts) (amps) (amps) (kV) la(amps) | Time | Dissi- | |
| | | | | | | - | (secs) | pation | |
| EHT16 | Rectifier H.W. M | 4.0 | 15.0 | 15.0 | 20 | 3.0 | 09 | | 3. |
| ESU75 | Rectifier H.W. M | 2.0 | 10.0 | 6.0 | 7 | 0.2 | 15 | | |
| ESU 206 | Rectifier H.W. V | 11.5 | 2.0 | | 10 | 0.1 | | | |
| ESU208 | Rectifier H.W. V | 14.0 | 0.9 | | 14 | 0.3 | | | |
| ESU303 | Rectifier H.W. M | 4.0 | 12.5 | 3.0 | 10 | 0.75 | 09 | | |
| ESU400 | Rectifier H.W. M | 2.0 | 12.5 | 6.0 | 10 | 1.5 | 09 | | |
| ESU450 | Rectifier H.W. V | 17.0 | 9.9 | 7.0 | 20 | | | | |
| ESU751 | Rectifier H.W. M | 2.0 | 10.0 | 6.0 | 5 | | 15 | | |
| ESU1500 | Rectifier H.W. V | 15.5 | 28.0 | | 30 | 9.0 | | | |
| ESU1500AX | Rectifier H.W. V | 16.5 | 15.2 | | 9 | 9.0 | | | |
| MR15 | Rectifier H.W. | | | | | | | | Control |
| | Thyratron | 4.0 | 15.0 | 15.0 | 20 | 3.0 | 09 | | Ratio 300 |
| MR304 | Rectifier H.W. | | | | | | | | Control |
| | Thyratron | 4.0 | 12.5 | 3.0 | 14 | 8.0 | 09 | | Ratio 400 |
| MU25 | Rectifier H.W. M | 4.0 | 28.0 | 100 | 0.5 | 25 | 300 | | |

August, 1962

Page 1, Issue 2

Condensed Data on Replacement Types

LOW VOLTAGE RECTIFIERS

| Type Number | Description | V _f (V) | I _f (A) | V _{out} (V) | I _{out} | Base |
|----------------|---|-----------------------|--------------------|-------------------------|------------------|---------|
| 68504 | Full-wave, tungar Half-wave, tungar Half-wave, tungar Half-wave, tungar Full-wave, gas discharge Full-wave, gas discharge | 2·3 | 18 | 30 | 5·0 | G.E.S. |
| 68506 | | 2·3 | 18 | 75 | 6·0 | G.E.S. |
| 68508 | | 2·5 | 25 | 60 | 15 | G.E.S. |
| 68510 | | 2·0 | 12 | 75 | 1·5 | E.S. |
| 68530 | | 2·0 | 8·0 | 30 | 6·0 | Special |
| 68532 | | 2·0 | 3·5 | 20 | 2·0 | Special |

HALF-WAVE HIGH VACUUM RECTIFIERS

| Type Number | V_f or V_h (V) | If or Ih | i _{k(pk)max} (A) | P.I.V. _(max) (kV) | $I_{k(max)}$ (mA) | Pa(max) (W) | Base |
|----------------|----------------------|-------------|---------------------------|------------------------------|---------------------|----------------|------------------|
| 19E2 19G3 | 4·0 4·0 | 2·1 1·4 | 12 0·375 | 4·0 6·3 | 50 | 5.0 | 108 108 |
| 19HI | 4.0 | 2.0 | 0.6 | 15 | 75 | _ | B4 |
| I9H5 ESUISI | 4·0 4·0 | 4·0 12·0 | 1·0 1·0 | 18 75 | 200 | 32 100 | G.E.S. G.E.S. |
| V1901 | 16.5 | 15.2 | _ | 60 | 400 | _ | E.S. |

HALF-WAVE MERCURY VAPOUR RECTIFIERS

| Type Number | V _f (V) | I _f (A) | i _{k(pk)} (A) | P.I.V. _(max) (kV) | I _{k(max)} (A) | V _{out} * (kV) | l _{out} * (A) | Base |
|----------------|-----------------------|--------------------|------------------------|---------------------------------|-------------------------|----------------------------|---------------------------|--------|
| ESU76 | 2·0 | 7·5 | 1·25 | 10 | 0·25 | 3·2 | 0·5 | G.E.S. |
| ESUI50 | 4·0 | 7·5 | 5·0 | 15 | 1·0 | 4·75 | 2·0 | G.E.S. |

^{*} Maximum output in biphase half-wave using two valves.

XENON RECTIFIERS

| Type Number | V _f (V) | l _f (A) | i _{k(pk)} (A) | P.I.V. _(max) (kV) | I _{k(max)} (A) | V _{out} (kV) | I _{out} (A) | Base |
|----------------|-----------------------|--------------------|------------------------|------------------------------|-------------------------|--------------------------|-------------------------|--------|
| ESUI04 | 4.0 | 2.8 | {1.0 2.0 | 10 5·0 | 0·25 0·5 | 3·2 1·5 | 0·5 1·0} | B4 |
| ESUI05 | 2.0 | 7.5 | {1·0 2·0 | 10 5·0 | 0·25 0·5 | 3·2 1·5 | 0·5 1·0 | G.E.S. |

High Vacuum Rectifiers

DATING



I9G6 HIGH VACUUM HALF WAVE RECTIFIER Indirectly heated—for High Voltage Power Supplies

| RATING | | | |
|--|------------------------|---------|-----|
| Heater Voltage | V_h | 4.0 | V |
| Heater Current | l _h | 0.5 | A |
| Maximum Peak Inverse Anode Voltage (Wkg) | P.I.Vmax(w) | 6.0 | kV |
| Maximum Peak Inverse Anode Voltage (no-load) | P.I.V(max) | 7.0 | kV |
| Maximum Anode Voltage (r.m.s.) | V _{a(rms)max} | 2.5 | kV |
| Maximum Mean Anode Current | la(av)max | 30-0 | mΑ |
| Maximum Peak Anode Current | la(pk)max | 180-0 | mΑ |
| Minimum Surge Limiting Resistance | / | 5,400 | * Ω |
| Maximum Reservoir Capacitance | Cmax | 1.0 | μF |
| * This resistance can be obtained in the of the transformer winding. | ne distributed | resista | nce |
| PO NO | | | |
| INTER-ELECTRODE CAPACITANC | ES (pF) | | |
| Anode to all other electrodes | Ca-all | | 2.8 |
| | | | |
| DIMENSIONS | | | |
| Maximum Overall Length | | 60 r | nm |
| Maximum Diameter | | 19 r | nm |
| Approximate Nett Weight | | 14 | oz |
| Approximate Packed Weight | | 1 2 | oz |
| | | | |

MOUNTING POSITION—Unrestricted

19**G**6

HIGH VACUUM HALF WAVE RECTIFIER

Indirectly heated—for High Voltage Power Supplies

CAP-CT1

BASE-Miniature Button 7-Pin (B7G.)



Viewed from free end of pins.

BASE CONNECTIONS

| Pin 1 | IC to Pin 2 | IC |
|-------|-------------|-------------------|
| Pin 2 | Cathode | property of the k |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h h |
| Pin 5 | IC to Pin 2 | IC |
| Pin 6 | IC to Pin 2 | IC |
| Pin 7 | IC to Pin 2 | IC |
| Сар | Anode | ZI URUTE IIA |

NOTES

Cathode and Heater should normally be tied externally. If left free, the heater to cathode voltage must never exceed 10 volts Peak.

The heater must be switched on for 20 seconds before the anode voltage is applied.


All Maximum Ratings are absolute values not design centres.

December, 1961



I9G6 HIGH VACUUM HALF WAVE RECTIFIER Indirectly heated—for High Voltage Power Supplies


AVERAGE CHARACTERISTIC CURVES: Ia,Ra/Va





1964 PhGH VACUUM HALF WAVE RECTIFIES SHOW PRINCE det high Vetros Power Stand to

AND ALTO SEVEN STREET BARRIES DANS A





19H4

HIGH VACUUM DIODE

Indirectly heated—for High Voltage Power Rectification ←

| RATIN3 q | | | |
|--|--------------------------|-----------------|---|
| Heater Voltage (volts) | v _h | 2.5 | |
| Heater Current (amps) | I _h | 1.7 | + |
| Maximum Mean Anode Current (mA) | Ia(av)max. | . 30.0 | + |
| Maximum Peak Anode Current (mA) | Ia(pk)max. | • 180 | + |
| Maximum Peak Inverse Voltage - No Load (KV) | P.I.V. o. (max) | • 23.0 | |
| Maximum Peak Inverse Voltage - On Load (KV) Maximum Mean Anode Current (mA) | P.I.V. w. (max) | • 20.0 † 5.0 | |
| Maximum Peak Inverse Voltage - No Load or On Load (KV) | | † 18.0 | |
| Minimum Surge Limiting Resistance (ohms) | ~ | 18,000 | + |
| Maximum Reservoir Condenser (µF) | (50 c/s (1,600 c/s | 0.5 0.01 | * |
| Delayed Switching. The He switched on for 10 seconds Anode Voltage is applied. | eater must be before the | | |
| † Simultaneous Switching. | | | 4 |
| ¶ All Maximum Ratings are ab | solute values, | | |
| not design centres. | | | |
| DIMENSIONS | | | |
| Maximum Overall Length (mm) | | 129 | |
| Maximum Diameter (mm) | | 40 | |
| Maximum Seated Height (mm) | | 116 | |
| Approximate Nett Weight (ozs) | | 21 | |
| Approximate Packed Weight (ozs) | | 31 | |
| MOUNTING POSITION - Unrestricted | | | |
| | | | |

Indicates a change -



19H4

HIGH VACUUM DIODE

Indirectly heated—for High Voltage Power Rectification

~

CAP American Miniature Type

BULB Clear

BASE International Octal (IO8)



Viewed from free end of pins.

CONNEXIONS.

| Pin 1 | | |
|---------|----------------|-----|
| Pin 2 | Heater | h |
| Pin 3 | | _ |
| Pin 4 | - | - |
| Pin 5 | - | - |
| Pin 6 | · _ | - |
| Pin 7 | Heater/Cathode | h/k |
| Pin 8 | - | - |
| Top Cap | Anode | a |

NOTE

All pins with the exception of No. 2 should be connected to pin No. 7 on the holder, and pin No. 7 connected to the reservoir condenser.


Indicates a change
Issue 1, Page 2



19H4

HIGH VACUUM DIODE Indirectly heated—for High Voltage Power Rectification

AVERAGE CHARACTERISTIC CURVE





GENERAL

The 19H12 is an Inverse Damping Diode intended for use in radar transmitters to prevent voltage overswings.

RATING

| Filament Voltage (volts) | Vh | 4.0 |
|---|-----------------|----------|
| Filament Current (amps) | l _h | 12.0 |
| Maximum Anode Dissipation (watts) | Pa(max) | 50 |
| Maximum Peak Inverse Voltage (kV) | PIV(max) | 25 |
| Maximum Peak Pulse Current (Normal) (amps) Maximum Peak Pulse Current | ik(pk)max | 30* |
| (Fault) (amps) | ik(fault)max | 50† |
| Approximate Pulse Impedance at 30 amps (ohms) | D.C. Resistance | 23 |
| * Maximum pulse length 10μ s. For | mean and r.m.s. | currents |

see rating chart.

The filament must be switched on for 30 seconds before the anode voltage is applied.

All maximum ratings are Absolute values not Design Centres.

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Filament | ca-f | 27.8 |
|---------------------------|------|------|
| DIMENSIONS | | |
| Maximum Overall Length | (mm) | 240 |
| Maximum Diameter | (mm) | 120 |
| Approximate Nett Weight | (Ib) | 13 |
| Approximate Packed Weight | (lb) | 61/2 |

MOUNTING POSITION—Unrestricted.

TOP CAPS—CT3


December, 1961

[†] For 1 second maximum. For further details see fault rating



EDISWAN

I9HI2 HIGH VACUUM DIODE Directly heated TENTATIVE




All dimensions in mm.

Electronic Components Division
Tel.: GERrard 9797




RATING CHART: Ia(pk)/Duty Ratio
Normal Conditions
The Chart gives Absolute Maximum values, not Design Centres



December, 1961




RATING CHART: $I_a(pk)/I_a(av)$ Fault Conditions. Maximum Fault Duration =1 sec. The Chart gives Absolute Maximum values, not Design Centres






RATING CHART
Normal conditions
The Chart gives Absolute Maximum values, not Design Centres



December, 1961



 $\begin{array}{c} \text{RATING CHART: } I_a(\text{pk})/I_a(\text{av}) \\ \text{Normal Conditions} \\ \text{The Chart gives Absolute Maximum values, not Design Centres} \end{array}$



December, 1961




ESU74 HIGH VACUUM HALF WAVE RECTIFIER

| RATING | | |
|---|-----------------|--------|
| Filament Voltage (volts) | V _f | 4.0 |
| Filament Current (amps) | If | 11.5 |
| Maximum Peak Inverse Voltage (volts) | P.I.V. (max) | 40,000 |
| Maximum Mean Anode Current (mA) | la(av)max | 80 |
| Average Maximum Filament Emission (amps) | l _{em} | 1.1 |
| Maximum Anode Dissipation (watts) | Pa | 50 |
| | | |
| DIMENSIONS | | |
| Maximum Overall Length | (mm) | 250 |
| Maximum Diameter | (mm) | 60 |
| Approximate Nett Weight | (ozs) | 7.0 |
| Approximate Packed Weight | (lbs) | 2.0 |
| Approximate Packed Export Weight | (lbs) | 2.0 |

MOUNTING POSITION-Vertical.

December, 1961


ESU74
HIGH VACUUM HALF WAVE RECTIFIER





HIGH VACUUM HALF WAVE RECTIFIER

TYPICAL CHARACTERISTIC CURVES: Ia/Va



ESULTA

HAW YOU

14.1

MERCANDER STANDARD REPORT OF A PROPERTY OF A




ESU77 HALF-WAVE HIGH VACUUM RECTIFIER

| GENERAL | | |
|---|---------------------|-----------------------|
| The ESU.77 is a directly heated filament high voltage half-wave a tantalum anode. | Thoriated rectifier | Tungsten employing |
| RATING | | |
| Filament Voltage (volts) | Vf | 4 |
| Filament Current (amps) | If | 12 |
| Maximum Peak Inverse Voltage (kV) | P.I.V. | Max. 40 |
| Maximum Peak Anode Current for Rectifier and Diode charging conditions (amps) | Ia(pk)n | max. 1.1 |
| Maximum Anode Dissipation (watts) | Pa | 130 |
| Nominal Internal Resistance at 300 mA (ohms) | | 600 |
| DIMENSIONS | | |
| Maximum Overall Length (mm) | | 270 |
| Maximum Diameter (mm) | | 61 |
| BASE - G.E.S. | | |
| MOUNTING POSITION - Vertical | | |
| | | |



ESU77
HALF-WAVE HIGH VACUUM RECTIFIER



HARD GLASS BULB

All dimensions in mm. unless stated otherwise.

December, 1961

Gas-filled Rectifiers



ESUI0I HALF-WAVE MERCURY VAPOUR RECTIFIER TENTATIVE

GENERAL

The ESU101 is a directly heated high voltage half-wave mercury vapour rectifier, which has been designed for use in radio relay amplifiers.

RATING

| Filament Voltage (volts) | Vf | | 4.0 |
|-----------------------------------|-------------|-------|------|
| Filament Current (amps) | lf | | 2.7 |
| Maximum Peak Inverse Voltage (kV) | P.I.V.(max) | | 10.0 |
| Maximum Peak Anode Current (amps) | | | 1.25 |
| Maximum Mean Anode Current(amps) | la(av)max | | 0.25 |
| Voltage Drop (approx) (volts) | Vdrop | | 16 |
| Condensed Mercury Temperature | | | |
| Range (°C) | | 20 to | 60 |
| Heating Time (seconds) | | | 60 |

DIMENSIONS

| Maximum Overall Length | (mm) | 139 |
|---------------------------|-------|------|
| Maximum Diameter | (mm) | 48 |
| Approximate Nett Weight | (ozs) | 2 |
| Approximate Packed Weight | (ozs) | 31/4 |

MOUNTING POSITION Vertical, base downwards,

TYPICAL OPERATION

A Biphase Half Wave Rectifier using two valves can give an output of 500 mA at 3.2 kV.

NOTES

The H.T. supply to the anode should not be switch on until the specified filament heating time has elapsed. When newly installed or after a period of disuse the filament should be run at normal temperature for 15 minutes before the application of the H.T. voltage.

December, 1961

Issue 1, Page 1

Electronic Components Division Tel.: GERrard 9797



ESUI0I HALF-WAVE MERCURY VAPOUR RECTIFIER TENTATIVE

BULB Clear.

BASE British 4 Pin (B4).



Viewed from free end of pins.

CAP 11/16 ins. diameter.

VALVEHOLDER EDISWAN CLIX VH300/4, VH42/4.

TOP CAP CONNECTOR EDISWAN CLIX TC434


CONNECTIONS

| Pin 1 | No Connection | NC |
|---------|---------------|----|
| Pin 2 | No Connection | NC |
| Pin 3 | Filament | f |
| Pin 4 | Filament | f |
| Top Cap | Anode | a |

Electronic Components Division Tel.: GERrard 9797



ESUI0I HALF-WAVE MERCURY VAPOUR RECTIFIER TENTATIVE



All Dimensions in mm unless stated otherwise.

December, 1961

THE PROPERTY AND A PR





HALF-WAVE XENON RECTIFIER

TENTATIVE

GENERAL

The ESU103 is a directly heated half-wave Xenon Rectifier requiring a heating delay time of 10 seconds. Two rectifiers in a Full-wave circuit will give an output of 0.5 amps at 3.2kV or 1.0 amp at 1.6kV. This rectifier may be operated in the ambient temperature range -50°C to $+75^{\circ}\text{C}$.

RATING

| Filament Voltage (volts) | V_f | | 2.5 |
|--------------------------------------|-----------|------------|------------|
| Filament Current (amps) | If | Course and | 5.0 |
| Maximum Peak Inverse Voltage (kV) | PIV (max) | 5.0 | 10.0 |
| Maximum Peak Anode Current (amps) | ia(pk)max | 2.0 | 1.0 |
| Maximum Mean Anode Current (amps) | la(av)max | 0.5 | 0.25 |
| Maximum Voltage Drop | (volts) | | 12.0 |
| Minimum Heating Time (| (secs) | | 10 |
| Ambient Temperature Range (°C) | | | -55 to +75 |
| DIMENSIONS | | | |
| Maximum Overall Lengt | h | (mm) | 160 |
| Maximum Seated Height | annual i | (mm) | 144 |
| Maximum Diameter | | (mm) | 52 |
| Approximate Nett Weig | ght | (ozs) | 4 |
| Approximate Packed We | eight | (ozs) | 8 |
| | | | |

MOUNTING POSITION—Unrestricted

December, 1961



ESUI03 HALF-WAVE XENON RECTIFIER

TENTATIVE

| TYPICAL OPERATION-Full-way | e (2 Valves) | n Ellit | 2- 11 |
|----------------------------------|--------------|---------|-------|
| Peak Inverse Voltage Rating (kV) | PIV(max) | 5 | 10 |
| Output Voltage (kV) | Vout | 1.6 | 3.2 |
| Output Current (amps) | lout | 1.0 | 0.5 |

TOP CAP-CT3

BASE-UX4 with Bayonet



Viewed from free end of pins.

VALVE HOLDER—Ediswan Clix VH262/4

TOP CAP CONNECTOR-Ediswan Clix TC433

CONNECTIONS

| Pin 1 | Filament | | · · · f |
|---------|------------------|-----------|---------|
| Pin 2 | No Connection | | NC |
| Pin 3 | No Connection | Bart * al | NC |
| Pin 4 | Filament, Shield | | f,s |
| Top Cap | Anode | | 2 |

December, 1961



HALF-WAVE MERCURY VAPOUR RECTIFIER

TENTATIVE

GENERAL

THE ESU106 is an indirectly heated half-wave Mercury Vapour Rectifier having a normal cathode heating delay time of five minutes. Two rectifiers in a full wave circuit will give an output of 6 amps at 6.3kV. This rectifier may be operated with condensed mercury temperatures in the range $+25^{\circ}\text{C}$ to $+70^{\circ}\text{C}$.

RATING

| Heater Voltage (volts) | Vh | 4.0 |
|---|-------------|--------------|
| Heater Current (amps) | lh | 14.0 to 16.0 |
| Maximum Peak Inverse Voltage (kV) | PIV(max) | 20.0† |
| Maximum Peak Anode Current (amps) | ia(pk)max | 15.0† |
| Maximum Mean Anode Current (amps) | la(av)max | 3.0† |
| Maximum Voltage Drop (volts) | u(u.)ux | 15.0 |
| Minimum Cathode Heating Time (at 15°C) (minutes) | | 5.0* |
| Condensed Mercury Temperature Range (°C) | | +25 to +70 |
| Maximum Surge Cathode Current (0.1 sec max) (amps) | lk(surge)ma | ax 150 |
| * A. f | | |

^{*} At free air ambient temperature 10°C heating time is 10 minutes, at 5°C heating time is 20 minutes.

DIMENSIONS

| Maximum Overall Length | (mm) | 310 |
|---------------------------|-------|-----|
| Maximum Diameter | (mm) | 78 |
| Approximate Nett Weight | (lbs) | 1 |
| Approximate Packed Weight | (lbs) | 8 |

December, 1961

[†] See "Typical Operation" for temperature derating.

HALF-WAVE MERCURY VAPOUR RECTIFIER

TENTATIVE

MOUNTING POSITION-Vertical, base downwards

TYPICAL OPERATION

A Full Wave Rectifier using 2 valves can deliver an output of 6 amps at 6.3kV.

| Condensed Mercury Temperature (°C) | | 70 | 65 | 60 | 55—25 |
|-------------------------------------|-----------|----|----|----|-------|
| Maximum Peak Inverse Voltage (kV) | PIV(max) | 5 | 10 | 15 | 20 |
| Maximum Peak Cathode Current (amps) | ik(pk)max | 30 | 20 | 18 | 15 |
| Maximum Mean Cathode Current (amps) | | | | | 3 |


NOTE

The cathode of this rectifier should be allowed an adequate heating time, preferably longer than the specified absolute minimum but in any circumstances no shorter, before the application of anode voltage.

The condensed mercury temperature, which may be measured with a thermocouple attached to the coolest part of the bulb, should never pass outside the specified limits during operation.

After transportation, or a period of storage, or when first placed in service, an initial cathode heating time of 30 minutes should be allowed to ensure the correct distribution of the mercury within the valve.





VALVE HOLDER—AEI 4857

TOP CAP CONNECTOR-AEI TC433

CONNECTIONS

Base Centre Base Shell Top Cap Heater, Cathode Heater

Anode


h,k h

August, 1962

Page 3, Issue 2



CHARACTERISTIC CURVES: THg/t





HALF-WAVE MERCURY VAPOUR RECTIFIER

GENERAL

The ESU107 is an indirectly heated half-wave mercury vapour rectifier having a minimum cathode heating delay time of three minutes. Two rectifiers in a full wave circuit will give an output of 6·0A at 6·3kV. This rectifier may be operated with condensed mercury temperatures in the range $+25^{\circ}$ to $+70^{\circ}\text{C}$.

RATING

| Heater voltage | ٧h | | | | 5.0 | V |
|--|--------------|-------|-------|-------|-------|-----|
| Heater current | lh | | | | 12 | A |
| Maximum peak inverse voltage | P.I.V.(max) | | | | 20 | kV |
| Maximum operating frequency | fmax | | | | 150 | c/s |
| Minimum pre-heat time | | | | | 3 | min |
| Maximum output voltage in biphase half- wave using two valves | V(out)max | | | | 6.3 | kV |
| Maximum output current in biphase half- wave using two valves | I(out)max | | | | 6-0 | Α |
| Maximum voltage drop across valve | • | | | | 15 | V |
| Maximum surge cathode current (0·1 sec max) | lk(surge)max | | | | 150 | Α |
| Maximum peak inverse voltage | P.I.V.(max) | 20 | 15 | 10 | 5.0 | kV |
| Condensed mercury temperature limits | | 25-55 | 25-60 | 25-65 | 25-70 | °C |
| Peak cathode current | ik(pk) | 15 | 18 | 20 | 25 | A |
| Maximum average cathode current (maximum average time 10 sec) | lk(av)max | 3.0 | 4.0 | 5.0 | 6.0 | Α |

DIMENSIONS

| Maximum overall length | 305 | mm |
|---------------------------|-----|----|
| Maximum diameter | 78 | mm |
| Maximum seated height | 285 | mm |
| Approximate net weight | 1 | lb |
| Approximate packed weight | 8 | lb |

February, 1962

HALF-WAVE MERCURY VAPOUR RECTIFIER

MOUNTING POSITION-Vertical, base downwards.

NOTES


The cathode of this rectifier should be allowed an adequate heating time, preferably longer than the specified absolute minimum, but in any circumstances no shorter, before the application of anode voltage.

The condensed mercury temperature, which may be measured with a thermocouple attached to the coolest part of the bulb, should never pass outside the specified limits during operation.

After transportation, or a period of storage, or when first placed in service, an initial cathode heating time of 30 minutes should be allowed to ensure the correct distribution of the mercury within the valve.

TOP CAP-CT3

BASE-B4D



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | No Connection | NC |
|---------|-----------------|-----|
| Pin 2 | Heater, Cathode | h,k |
| Pin 3 | Heater | h |
| Pin 4 | No Connection | NC |
| Тор Сар | Anode | a |
| | | |


February, 1962

Issue 1, Page 2

Associated Electrical Industries Limited

Electronic Components Department
Tel: GERrard 9797






VIEW OF FREE END.

All dimensions in mm.



CHARACTERISTIC CURVES: THg/t





ESUIII

HALF WAVE MERCURY VAPOUR RECTIFIER

GENERAL

The ESU111 is an indirectly heated half wave Mercury Vapour Rectifier having a cathode heating delay time of 3 minutes. Two rectifiers in a full wave circuit will give an output of 6 amps at 6.3kV. This rectifier may be operated with condensed mercury temperatures in the range $+25^{\circ}\mathrm{C}$ to $+70^{\circ}\mathrm{C}$.

RATING

| Heater Voltage (volts) | V_h | 5-0 |
|-------------------------------------|--------------|----------|
| Heater Current (amps) | lh | 12.0 |
| Maximum Peak Inverse Voltage (kV) | PIVmax | 20-0* |
| Maximum Peak Anode Current (amps | la(pk)max | 15.0* |
| Maximum Mean Anode Current (amps | i) ia(av)max | 3-0* |
| Maximum Voltage Drop (volts) | | 15-0 |
| Minimum Heating Time (mins) | | 3 ← |
| Condensed Mercury Temperature Range | +25 | to +70°C |

^{*} See "Typical Operation" for temperature derating.

DIMENSIONS

| Maximum Overall Length | (mm) | 337 ← |
|---------------------------|-------|-------|
| Maximum Seated Height | (mm) | 310 ← |
| Maximum Diameter | (mm) | 78 |
| Approximate Nett Weight | (lbs) | 1 |
| Approximate Packed Weight | (lbs) | 81 |

Indicates a change 🗲

ESUIII

HALF WAVE MERCURY VAPOUR RECTIFIER

MOUNTING POSITION-Vertical, base downwards

TYPICAL OPERATION

A full wave Rectifier using 2 valves can deliver an output of 6.0. amps at 6.3kV.

| Condensed Mercury Temperature (°C) | | 70 | 65 | 60 | 55 |
|--|-----------|----|----|----|------------|
| 14 87 | | 25 | 25 | 25 | to 25 ← |
| Maximum Peak Inverse Voltage (kV) | PIV(max) | 5 | 10 | 15 | 20 |
| Maximum Peak Cathode Current (amps) | ik(pk)max | 25 | 20 | 18 | 15 ← |
| Maximum Mean Cathode Current (amps) | lk(av)max | 6 | 5 | 4 | 3 🖛 |

NOTES.-

The cathode of this rectifier should be allowed an adequate heating time, preferably longer than the specified absolute minimum but in any circumstances no shorter, before the application of anode voltage.


The condensed mercury temperature, which may be measured with a thermocouple attached to the coolest part of the bulb, should never pass outside the specified limits during operation.

After transportation, or a period of storage, or when first placed in service, an initial cathode heating time of 30 minutes should be allowed to ensure the correct distribution of the mercury within the valve.

Indicates a change
Issue 1, Page 2



ESUIII HALF-WAVE MERCURY VAPOUR RECTIFIER




All dimensions in mm.

BASE-RMA A3-20

TOP CAP CONNECTOR-AEI TC433

February, 1962





HALF-WAVE MERCURY VAPOUR RECTIFIER

GENERAL

The ESU115 is a directly heated high voltage half-wave mercury vapour rectifier, which has been designed for use in radio relay amplifiers.

RATING

| Filament Voltage (volts) | Vf | 4.0 |
|---|-------------|----------|
| Filament Current (amps) | lf | 2.7 |
| Maximum Peak Inverse Voltage (kV) | P.I.V.(max) | 6.5 |
| Maximum Peak Anode Current (amps) | la(pk)max | 1.25 |
| Maximum Mean Anode Current(amps) | a(av)max | 0-25 |
| Voltage Drop (approx) (volts) | Vdrop | 16 |
| Condensed Mercury Temperature Range (°C) | | 20 to 60 |
| Heating Time (seconds) | | 60 |

DIMENSIONS

| Maximum Overall Length | (mm) | 139 |
|---------------------------|-------|-----|
| Maximum Diameter | (mm) | 48 |
| Approximate Nett Weight | (ozs) | 3 |
| Approximate Packed Weight | (ozs) | 31 |

MOUNTING POSITION-Vertical, base downwards.

TYPICAL OPERATION

A Biphase Half Wave Rectifier using two valves can give an output of 500 mA at $2.0\,$ kV.

NOTES

The H.T. supply to the anode should not be switched on until the specified filament heating time has elapsed. When newly installed or after a period of disuse the filament should be run at normal temperature for 15 minutes before the application of the H.T. voltage.

December, 1961



HALF-WAVE MERCURY VAPOUR RECTIFIER

BULB-Clear.

BASE-British 4 Pin (B4).



Viewed from free end of pins.

CAP-CT2.

VALVEHOLDER-EDISWAN CLIX VH300/4, VH42/4.

TOP CAP CONNECTOR-EDISWAN CLIX TC430.

CONNECTIONS

| Pin 1 | No Connection | NO |
|---------|---------------|----|
| Pin 2 | No Connection | NO |
| Pin 3 | Filament | f |
| Pin 4 | Filament | f |
| Top Cap | Anode | a |



HALF WAVE MERCURY VAPOUR RECTIFIER

GENERAL

_ . _

The ESU200 is a directly heated oxide coated filament High Voltage Half Wave Mercury Vapour Rectifier. When first placed into operation it is essential that the filament is run at its rated value for 15 minutes without any anode voltage being applied.

| RATING | | |
|--|-------------|-----------|
| Filament Voltage (volts) | Vf | 4.0 |
| Filament Current (amps) | lf | 11-0 |
| Maximum Peak Inverse Anode Voltage (kV) | PIV (max) | **15 |
| Maximum Peak Anode Current (amps) | la(pk)(max) | **5.0 |
| Maximum Average Anode Current (amps) | la(av)(max) | 1.25 |
| Voltage Drop (volts) approx. | , ,, , | 12 |
| Ambient Temperature Range | | 20°-60° C |
| Cathode Heating Delay Time (secs) | t | 60 |
| DIMENSIONS | | |
| Maximum Overall Length | (mm) | 270 |
| Maximum Diameter | (mm) | 57 |
| Approximate Nett Weight | (ozs) | 8 |
| | 5 | |

MOUNTING POSITION-Vertical

Approximate Packed Export Weight (lbs)

TOP CAP-Anode (C.T.9)

Approximate Packed weight

BASE G.E.S .- Filament


**Note:—Maximum ratings cannot necessarily be used simultaneously. Normally if either the maximum P.I.V. or maximum mean current are to be used, the other factor has to be reduced appreciably.

(lbs)

December, 1961



ESU200
HALF WAVE MERCURY VAPOUR RECTIFIER



All dimensions in m.m.



HALF WAVE MERCURY VAPOUR RECTIFIER Directly heated

RATING

| Filament Voltage (volts) | Vf | 5.0 |
|--------------------------------------|--------------|--------|
| Filament Current (amps) | lf | 10∙0 ← |
| Maximum Peak Anode Current (amps |) la(pk)max. | 7.0 ← |
| Maximum Mean Anode Current (amp | . , | 1.75 ← |
| Maximum Peak Inverse Voltage (volts) | ` ' | 15,000 |
| Approximate Voltage Drop (volts) | Vir | 10-0 |
| Filament Heating Time (secs) | | 60 |
| Condensed Mercury Temp. (°C) | | 20-60 |
| | | |
| DIMENSIONS | | |
| Maximum Overall Length (mm) | | 275 🖝 |
| Maximum Diameter (mm) | | 78 |
| Approximate Nett Weight | (ozs) | 10½ |
| Approximate Packed Weight | (lbs) | 4 |
| Approximate Packed Export Weight | (lbs) | 41/2 |
| | | - |

MOUNTING POSITION—Vertical.

BASE-Jumbo.


SPECIAL NOTE.

When the rectifier is first placed into service, the filament should be operated at Normal Voltage for 15 minutes without the anode voltage. This will enable the mercury to be correctly distributed.

> Indicates a change Issue 1, Page 1

ESU575

HALF WAVE MERCURY VAPOUR RECTIFIER
Directly heated



UNDERSIDE VIEW OF BASE

ALL DIMENSIONS IN M.M. UNLESS OTHERWISE STATED

December, 1961



HALF WAVE MERCURY VAPOUR RECTIFIER

Directly heated

RATING

| Filament Voltage (volts) | Vf | 5.0 |
|------------------------------------|-------------|-------|
| Filament Current (amps) | lf | 10.0 |
| Maximum Peak Anode Current (amps) | la(pk)max. | 7.0 |
| Maximum Mean Anode Current (amps) | la(av)max. | 1.75 |
| Maximum Peak Inverse Voltage (kV) | P.I.V.(max) | 15 |
| Approximate Voltage Drop (volts) | Vir | 10.0 |
| Cathode Heating Time (secs) | | 60 |
| Condensed Mercury Temperature (°C) | | 20-60 |

DIMENSIONS

| Maximum Overall Length | (mm) | 282 |
|-------------------------------------|-------|------|
| Maximum Diameter | (mm) | 78 |
| Approximate Nett Weight | (ozs) | 10½ |
| Approximate Packed Weight | (lbs) | 4 |
| Approximate Packed Export Weight | (lbs) | 41/2 |

MOUNTING POSITION—Vertical.

BASE-Super Jumbo-Filament.

TOP CAP-Anode.

SPECIAL NOTE

When the rectifier is first placed into service, the filament should be operated at Normal Voltage for 15 minutes without the anode voltage. This will enable the mercury to be correctly distributed.


December, 1961



EDISWAN

ESU673

HALF WAVE MERCURY VAPOUR RECTIFIER Directly heated



UNDERSIDE VIEW OF BASE

ALL DIMENSIONS IN M.M. UNLESS OTHERWISE STATED

December, 1961



ESU866 HALF WAVE MERCURY VAPOUR RECTIFIER


| RATING | | |
|--|--------------------------------|--------|
| Filament Voltage (volts) | Vf | 2.5 |
| Filament Current (amps) | If | 5.0 |
| Maximum Peak Anode Current (amps) | Ia(pk) | 1.0 |
| Maximum Peak Inverse Voltage (volts) | P.I.V (max) | 10,000 |
| Maximum Mean Anode Current (amps) | Ia(av)max | 0.28 |
| Approximate Voltage Drop (volts) | Vir | 18 |
| Cathode Delay Time (secs) | t | 60 |
| Ambient Temperature (C°) | | 20-60 |
| DIMENSIONS | | |
| Maximum Overall Length (mm) | | 170 |
| Maximum Diameter (mm) | | 66 |
| Approximate Nett weight (ozs) | | 3 |
| Approximate Packed Weight (1bs) | | 11 |
| Approximate Packed Export Weight | | 2 |
| MOUNTING POSITION Vertical | | |
| BASE | | |
| U.X. 4 pin. This valve can also be s with an E.S. base, in which case it i ESU.866/ES. | upplied fitte s known as th | d |
| TOP CAP Anode | | |
| SPECIAL NOTE | | |
| When first placed into operation it i | | |
| that the filament is run at the rated | | |
| 15 minutes without any anode voltage applied. | being | |
| | | |



ESU866 HALF WAVE MERCURY VAPOUR RECTIFIER

230V 50~ DLS10 DLS


BRIDGE RECTIFIER CIRCUIT TO SUPPLY 2.7 K.V. AT 300 m.A.




December, 1961



ESU866
HALF WAVE MERCURY VAPOUR RECTIFIER





UNDERSIDE VIEW OF BASE

ALL DIMENSIONS IN M.M. UNLESS OTHERWISE STATED

1172

Millian control stable policy in

416

Qui Ca-

DURANT WAY THERESE

A STREET THE STREET STREET



ESU872

HALF WAVE MERCURY VAPOUR RECTIFIER

GENERAL

This directly heated rectifier is designed to withstand high peak inverse voltages and to conduct at relatively low applied voltages.

RATING

| Filament Voltages (volts) | Vr | 5.0 |
|---|----------|-------|
| Filament Current (amps) | Ir | 7.5 |
| Maximum Peak Inverse Anode Voltage (KV) | P.I.V. | 10 |
| Peak Anode Current (amps) | Ia(pk) | 5 |
| Maximum Mean Anode Current (amps) | Ia(mean) | 1.25 |
| Condensed Mercury Temperature (°C) | a(modil) | 20-60 |
| Cathode Heating Delay Time (secs) | | 60 |
| Voltage Drop (volta) | | 15 |
| | | |

DIMENSIONS

Maximum Overall Length (inches)
Maximum Diameter (inches)
8½
2.5/16

BASE Jumbo - filament

TOP CAP - Anode

APPLICATION


When a mercury vapour rectifier is first placed in service, its filament should be operated at normal voltage for approximately 15 minutes without anode voltage in order to distribute the mercury properly. This procedure need not be repeated unless, during subsequent handling, the mercury is spattered on to the filament and anode.

Nount the rectifier vertically in a well-ventilated position as the bulb becomes hot during continuous operation. To avoid the possibility of flash-back on reverse voltage, the temperature of the rectifier bulb at the point where the mercury vepour condenses should not be allowed to exceed 60°C. Where there is a possibflity of the air temperature rising considerably, an air draught cooling should be used.

Unless the valve is operated on very light loads, the filament must be allowed to attain its full operating temperature before the anode voltage is applied, and the Cathode Delay Time should elapse before the anode supply is switched on. A delay switch is recommended for full load operation (see DLS range of swich The filament supply should not be switched off before the H.T. supply.

December, 1961

ESU872
HALF WAVE MERCURY VAPOUR RECTIFIER



ALL DIMENSIONS IN M.M. UNLESS OTHERWISE STATED

December, 1961



ESU8008

HALF WAVE MERCURY VAPOUR RECTIFIER

GENERAL

This directly heated rectifier is designed to withstand high peak inverse voltages and to conduct at relatively low applied voltages.

| RATING | | |
|--|----------|--------|
| Filament Voltages (volts) | Vf | 5.0 |
| Filament Current (amps) | If | 7.5 |
| Maximum Peak Inverse Anode Voltage (KV) | P.I.V. | 10 |
| Maximum Peak Anode Current (amps) | Ia(pk) | 5 |
| Maximum Wean Anode Current (amps) | Ia(mean) | 1.25 |
| Condensed Mercury Temperature (°C) | | 20-60 |
| Cathode Heating Time (secs) | | 60 |
| Approximate Voltage Drop (volts) | | 10 |
| DIMENSIONS | | |
| Maximum Overall Length (inches) Maximum Diameter (inches) | | 2.5/16 |
| BASE Super Jumbo ~ filament | | |

TOP CAP - Anode

APPLICATION


When a mercury vapour rectifier is first placed in service, its filament should be operated at normal voltage for approximately 15 minutes without anode voltage in order to distribute the mercury properly. This procedure need not be repeated unless, during subsequent handling, the mercury is spattered on to the filament and anode.

Mount the rectifier vertically in a well-ventilated position as the bulb becomes but during continuous operation. To avoid the possibility of flash-back on reverse voltage, the temperature of the rectifier bulb at the point where the mercury vapour condenses should not be allowed to exceed 60°C. Where there is a possibility of the air temperature rising considerably, an air draught cooling should be used.

Unless the valve is operated on very light loads, the filament must be allowed to attain its full operating temperature before the anode voltage is applied, and the Cathode Delay Time should elapse before the anode supply is switched on. A delay switch is recommended for full load operation (see DLS range of switches). The filament supply should not be switched off before the H.T. supply.

December, 1961

ESU8008
HALF WAVE MERCURY VAPOUR RECTIFIER



ALL DIMENSIONS IN M.M. UNLESS OTHERWISE STATED

December, 1961 Issue 1, Page 2





GAS FILLED TETRODE

Indirectly heated—for use as a Grid Controlled Rectifier

RATING

| Heater Voltage (volts) | V _{li} | 6.3 |
|-----------------------------------|------------------------|----------|
| Heater Current (amps) | Ih | 1.0 |
| Approximate Voltage drop (volts) | ** | 9.0 |
| Max. Peak Forward Anode Voltage | Va(max) | 600 |
| Max. Peak Inverse Anode Voltage | Va(max) P.I.V.(max) | 1300 |
| Max. Shield Grid Voltage (volts) | V _{g2} (max) | -100 |
| Max. Control Grid Voltage (volts) | Vgl(max) | -100 |
| Max. Peak Cathode Current (mA) | Ik(pk)max | 1250 |
| Max, Mean Cathode Current (mA) | Ik(av)max | 250 |
| Control Grid Series Resistance | refer / most | |
| (megohms) | .0 | 1 to 1.0 |

NOTE

Cathode and heater should normally be tied externally. If left free, the heater to cathode voltage must never exceed 25 volts peak. The heater must be switched on for 15 seconds before anode voltage is applied.

All maximum ratings are absolute values, not design centres.

DIMENSIONS

| Maximum Overall Length (mm) | 110 |
|---------------------------------|-----|
| Maximum Diameter (mm) | 40 |
| Maximum Seated Height (mm) | 97 |
| Approximate Nett Weight (ozs) | 12 |
| Approximate Packed Weight (ozs) | 2 |

MOUNTING POSITION - Unrestricted.

Indicates a change
Issue 1, Page 1

GAS FILLED TETRODE Indirectly heated—for use as a Grid Controlled Rectifier

BULB Clear

BASE International Octal (IO8)



Viewed from free end of pins.


CONNEXIONS

| Pin 1 | No connection | NC |
|-------|---------------|----|
| Pin 2 | Heater | h |
| Pin 3 | Anode | a |
| Pin 4 | No connection | NC |
| Pin 5 | Control Grid | gl |
| Fin 6 | Shield Grid | 82 |
| Fin 7 | Heater | h |
| Pin 8 | Cathode | k |
| | | |



GAS FILLED TETRODE Indirectly heated-for use as a Grid Controlled Rectifier

AVERAGE CHARACTERISTIC CURVES



to contact the industrial beautiful to the contact of the contact



THYRATRON GAS TETRODE Indirectly heated—for use as Gas Relay

| RATING | | |
|--|------------------------|-----------|
| Heater Voltage (volts) | v_h | 6.3 |
| Heater Current (amps) | Ih | 0.6 |
| Arc Voltage Drop (volts) | Maj - D | 8 |
| Maximum Forward Anode Volts | Va | 650 |
| Maximum Peak Inverse Anode Voltage (volts | s) P.I.V.(max) | 1300 |
| Maximum Shield Grid Voltage (volts) | Vg2(max) | -100 |
| Maximum Control Grid Volts | Vgl(max) | -100 |
| Maximum Peak Cathode Current (mA) | I _k (pk)max | 500 |
| Maximum Average Cathode Current (mA) | I _k (av)max | 100 |
| Control Grid Circuit Res. (Megohms) | Rgl | 0.01-10. |
| Control Ratio Gl | | 250 |
| Control Ratio G2 | | 1000 |
| | | |
| \bullet $V_{g2} = 0$ $R_{g1} = 0$ | 0 | |
| $t V_{gl} = 0 R_{gl} = 0$ | $0 	 R_{g2} = 0$ | |
| IMPORTANT | | |
| Heater to cathode voltage must never | exceed 25 vo | olts peak |
| The heater must be switched on for l anode voltage is applied. | 10.sec min be | efore |
| 111) All maximum ratings are absolute val centres. | lues, not desi | ign |
| DIMENSIONS | | |
| Overall Length Maximum (mm) | 0.0 | 54 |
| Maximum Diameter (mm) | | 19 |
| Maximum Seated Height (mm) | | 47.5 |
| Approximate Nett Weight (ozs) | | à |
| Approximate Packed Weight (ozs) | | 늁 |
| MOUNTING POSITION - Unrestricted. | | 1 |

December, 1961



THYRATRON GAS TETRODE Indirectly heated—for use as Gas Relay

BASE - Miniature Button 7, pin B7G.



Viewed from free end of pins.


CONNEXIONS

| Pin | 1 | Grid 1 | gl |
|-----|---|---------|----|
| Pin | 2 | Cathode | k |
| Pin | 3 | Heater | h |
| Pin | 4 | Heater | h |
| Pin | 5 | Grid 2 | g2 |
| Pin | 6 | Anode | a |
| Pin | 7 | Grid 2 | g2 |

December, 1961



20A3
THYRATRON GAS TETRODE
Indirectly heated—for use as Gas Relay



December, 1961





2IAI

GAS FILLED TETRODE

Indirectly heated—for use as a Grid Controlled
Rectifier

GENERAL

The 21A1 is a Gas Filled Tetrode intended for use as a Half Wave Grid Controlled Rectifier at altitudes up to 55,000 feet.

RATING

| Heater Voltage (volts) | Vh | 6-3 |
|--|-----------------------|--------------------|
| Heater Current (amps) | lh | 0.95 |
| Arc Voltage Drop (volts) | | 9.0 |
| Maximum Peak Forward Anode Voltage (volts) | V _{a (max)} | 600* |
| Maximum Peak Inverse Anode Voltage (volts) | PIV (max) | 1,300*‡ |
| Maximum Shield Grid Voltage (Before Anode Conduction) (volts) | Vg2 (max) | —100 |
| Maximum Control Grid Voltage (Before Anode Conduction) (volts) | Vg1 (max) | —100 |
| Maximum Peak Cathode Current (mA) | lk(pk) max | 1,250 |
| Maximum Mean Cathode Current (mA) | Ik(av) max | 250† |
| Maximum Mean Positive Control Grid Current (mA) | Ig1(av) max | 5†§ |
| Control Grid Series Resistance (megohms) | R _{g1} | 0.01 to 10 |
| Maximum Peak Heater to Cathode Voltage (Heater Positive) (volts) | V _{h-k(max)} | 25 |
| Maximum Peak Heater to Cathode Voltage (Heater Negative) (volts) | | 100 |
| Ambient Temperature Range (C°) | | —50 to +90 |
| | | |

NOTES—See overleaf

December, 1961

GAS FILLED TETRODE

Indirectly heated—for use as a Grid Controlled
Rectifier

NOTES

The heater must be switched on for 15 seconds minimum before the application of anode voltage.

- * Maximum ratings are Absolute Values not Design Centres and apply at air pressure corresponding to an altitude of 55,000 feet and up to a maximum supply frequency of 1.6kc/s.
- † Under transient switching conditions and note (*) the Maximum Surge Peak Inverse Voltage is 2000V.
- | Maximum Negative Voltage during Conduction is 10V.
- † Maximum averaging time, 15 seconds.
- \S Currents of this order may not be drawn when the anode is more negative than —10 volts.

DIMENSIONS

| Maximum Overall Length | (mm) | 85 |
|---------------------------|-------|------|
| Maximum Diameter | (mm) | 33 |
| Maximum Seated Height | (mm) | 71 |
| Approximate Nett Weight | (ozs) | 11/4 |
| Approximate Packed Weight | (ozs) | 2 |

MOUNTING POSITION—Unrestricted

December, 1961



2IAI

GAS FILLED TETRODE

Indirectly heated—for use as a Grid Controlled Rectifier

BASE-International Octal (6 Pin)



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | Heate r | h |
|-------|----------------|----|
| Pin 2 | No Pin | NP |
| Pin 3 | Anode | a |
| Pin 4 | No Pin | NP |
| Pin 5 | Control Grid | 81 |
| Pin 6 | Shield Grid | 82 |
| Pin 7 | Heater | h |
| Pin 8 | Cathode | k |




EDISWAN

21A1

GAS FILLED TETRODE

Indirectly heated—for use as a Grid Controlled
Rectifier

AVERAGE CHARACTERISTIC CURVES: Ig1/Vg1



December, 1961




2IAI

GAS FILLED TETRODE

Indirectly heated—for use as a Grid Controlled
Rectifier

AVERAGE CHARACTERISTIC CURVES : $V_{a(ign)}/V_{g1}$ $R_{g1} = 0\Omega$ $R_{g2} = 0\Omega$




December, 1961



CAS FILED TETRODE

in untertain he hand who as a so Cold Concretted Receiver

A STATE OF THE STATE OF THE STATE OF



GENERAL

The 21B12 is an inert gas filled thyratron suitable for welding or motor control. It has a directly heated oxide coated cathode.

RATINGS

August, 1962

| Filament voltage Filament current | V_{f} | 2·5 9·0 | ٧ |
|--|-----------------------|--------------|---------|
| Maximum peak forward anode voltage | lf | 1.0 | kV |
| Maximum peak inverse anode voltage | P.I.V.max | | 5 kV |
| Maximum mean cathode current | I _{k(av)max} | | A |
| Maximum peak cathode current | ik(pk)max | 30 | Α |
| Maximum surge cathode current (max duration 0.1 sec) | | 300* | Α |
| Maximum negative grid voltage before conduction | $V_{g(max)}$ | -300 | V |
| Maximum negative grid voltage after conduction | $V_{g(max)}$ | -10 | V |
| Control ratio | 0, , | 200:1 | |
| Maximum striking voltage for conduction | | 70 | V |
| Voltage drop | | 12 | V |
| Maximum grid resistance range | | 10-100+ | kΩ |
| Ionisation time | ti | 10 | μ s |
| Deionisation time | td | 1000 | μS |
| Commutation factor $(V/\mu s \times A/\mu s)$ | | 0.7 | |
| Ambient temperature range | | -55 to $+75$ | °C |

^{*} Recommended anode fuse = 6A. Maximum anode fuse = 10A.


INTER-ELECTRODE CAPACITANCES


| Anode/grid | c _{a-g} | 3.8 pF |
|----------------|------------------|---------|
| Anode/filament | C _{a-f} | 0.15 pF |
| Grid/filament | C _{g-f} | 2.5 pF |

MOUNTING POSITION—Unrestricted

Page 1, Issue 1


[†] Recommended value = $33k\Omega$.





All dimensions in millimetres


CHARACTERISTIC CURVES: Va/Vg



August, 1962 Page 3, Issue 1



CHARACTERISTIC CURVES: Ig/Vg





21B13 INERT GAS FILLED THYRATRON TENTATIVE

GENERAL

The 21B13 is a xenon filled thyratron suitable for welding, motor control and other power applications. It has an indirectly heated oxide-coated cathode.

RATING

| Heater voltage | Vh | 5.0 | V |
|---|-------------|----------|------|
| Heater current | 1h | 21 | A |
| Maximum peak forward anode voltage | | 1-2 | kV |
| Maximum peak inverse anode voltage | P.I.V.(max) | 1-2 | kV |
| Maximum mean cathode current | | | |
| (max averaging time 15 sec) | lk(av)max | 10* | A |
| Maximum peak cathode current | ik(pk)max | 100 | A |
| Maximum surge cathode current | | | |
| (max duration 0·1 sec) | | 2000 | A |
| Maximum anode voltage drop | | 18 | V |
| Maximum anode voltage for conduction | | 70 | V |
| Maximum negative grid voltage before conduction | | -200 | V |
| Maximum negative grid voltage after conduction | | -10 | V |
| Maximum grid resistance | Rg(max) | 50 | kΩ |
| Recommended minimum grid resistance | Rg(min) | 10 | kΩ |
| Minimum pre-heat time | 8(*****) | 120 | s |
| Ambient temperature range | | -55 to + | 75°C |

^{*} The anode structure must be left free, to ensure adequate cooling by free convection.

INTER-ELECTRODE CAPACITANCES

| Anode/grid Anode/cathode Grid/cathode | ca-g ca-k | 8·8 0·15 13·4 | pF pF |
|---|--------------|---------------------|----------|
| Grid/Catilode | cg-k | 10-4 | þí |

CHARACTERISTICS

| 10 | us |
|-------|-----------------------------|
| 50 | μS |
| 500 | μs |
| <20 | μΑ |
| 200:1 | |
| | 50 500 < 20 |

December, 1961

ADVANCE DATA, Page 1



21B13

INERT GAS FILLED THYRATRON

TENTATIVE

MOUNTING POSITION—Vertical, base down

DIMENSIONS

| Maximum overall length | 230 | mm |
|----------------------------------|-----|----|
| Maximum diameter over bulb | 70 | mm |
| Maximum diameter over connectors | 115 | mm |

CAP-18" diameter

BASE—Special

CONNECTIONS

Anode—Cap
Grid—Flexible lead from body of valve
Heater—Copper strip on base with 2BA slot
Heater and Cathode—Copper strip on base with 0BA clearing hole

GENERAL

The 21N12 is a convection cooled mercury vapour thyratron. It has an indirectly heated oxide coated cathode and is intended for use in power supplies and welding equipment, etc.

RATINGS—Absolute values

| Heater voltage | V_h | 5·0± | 5% V |
|---|--------------|----------|------|
| †Heater current (nominal) | Ih | 5.0 | A |
| Maximum peak forward anode voltage | | 10 | kV |
| Maximum peak inverse anode voltage | P.I.V.max | 10 | kV |
| Maximum surge peak inverse voltage | | 20 | kV |
| Maximum anode voltage drop | | 18 | V |
| Maximum mean cathode current (max averaging 15 sec) | Ik(av)max | 3.0 | Α |
| Maximum peak cathode current | ik(pk)max | 25 | Α |
| Maximum surge cathode current (0.1 sec) | | 250 | Α |
| Maximum grid resistance | $R_{g(max)}$ | 100 | kΩ |
| Maximum supply frequency | | 150 | c/s |
| Condensed mercury temperature limits | T_{Hg} | 35 to 70 | °C |

[†] The heater must be switched on for a minimum of three minutes before the anode voltage is applied.


MOUNTING POSITION—Vertical, base down.

CHARACTERISTICS

| Critical grid current (at $V_a = 6kV$) | | <10 | μA |
|---|----------------|-------|---------|
| Control ratio (nominal) | | 200:1 | |
| Ionisation time (approx) | ti | 10 | μs |
| De-ionisation time (approx) | t _d | 1,000 | μs |

August, 1962








VIEW OF FREE END.


All dimensions in millimetres.

CHARACTERISTIC CURVES: Ig/Vg





CHARACTERISTIC CURVES: THg/t



GENERAL

The 21N13 is a mercury vapour thyratron suitable for welding and motor control. It has an indirectly heated oxide coated cathode.

RATINGS

| Heater voltage | Vh | 5.0 | V |
|--|----------------|---------|---------|
| Heater current | l _h | 5.0 | A |
| Maximum peak forward anode voltage | | 1.5 | kV |
| Maximum peak inverse anode voltage | P.I.V.max | 1.25 | kV |
| Maximum negative grid voltage before conduction | $V_{g(max)}$ | -500 | V |
| Maximum negative grid voltage during conduction | $V_{g(max)}$ | -10 | V |
| Maximum mean cathode current (max averaging time 15 sec) | Ik(av)max | 3.0 | A |
| Maximum peak cathode current (25c/s and above) | ik(pk)max | 20 | A |
| Maximum surge cathode current | | | |
| (fault protection max duration 0.1 sec) | | 200 | A |
| Critical grid current (at V _a =1.0kV) | | <10 | μA |
| Maximum power supply frequency | | 150 | c/s |
| Condensed mercury temperature limits | T_{Hg} | 40 to 7 | 70°C |
| Control ratio | | 150:1 | |
| De-ionisation time (approx) | t _d | 1000 | μ s |
| lonisation time (approx) | t _i | 10 | μ s |
| Anode voltage drop | | 16 | V |
| Maximum grid resistance | $R_{g(max)}$ | 100 | kΩ |
| Recommended minimum grid resistance | $R_{g(min)}$ | 10 | kΩ |
| | | | |

MOUNTING POSITION—Vertical, base down

BASE-UX4 (E.I.A. No. A4-10)




Viewed from free end of pins.

CONNECTIONS

| Pin 1 | Heater | h |
|-------|-----------------|-----|
| Pin 2 | Heater, Cathode | h,k |
| Pin 3 | Grid | g |
| Pin 4 | Heater, Cathode | h,k |
| Сар | Anode | a |

August, 1962


Page 1, Issue 2



All dimensions in mm.



CHARACTERISTIC CURVES: Va/Vg




August, 1962


Page 3, Issue 1



CHARACTERISTIC CURVES: Ig/Vg




RATING CURVE: Forward Voltage, P.I.V./T_{Hg} (Fault Conditions).



August, 1962

Page 5, Issue 1



Mercury Vapour Thyratron

GENERAL

The 21N14 is a mercury vapour thyratron suitable for welding and motor control. It has an indirectly heated oxide-coated cathode.

RATINGS

| Heater voltage | V_h | 5.0 | V |
|---|-----------------------|---------|---------|
| Heater current | I _h | 5.0 | A |
| Maximum peak forward anode voltage | | 1.5 | kV |
| Maximum peak inverse anode voltage | P.I.V. max | 1.25 | kV |
| Maximum negative grid voltage before conduction | $V_{g(max)}$ | -500 | V |
| Maximum negative grid voltage during conduction | V _{g(max)} | -10 | V |
| Maximum mean cathode current (max averaging 15 sec) | I _{k(av)max} | 3.0 | Α |
| Maximum peak cathode current (25c/s and above) | i _{k(pk)max} | 20 | Α |
| Maximum surge cathode current | K(PK) | | |
| (Fault protection max duration 0.1 sec) | | 200 | Α |
| Maximum critical grid current (at $V_a = 1.0kV$) | | <10 | μA |
| Maximum power supply frequency | | 150 | c/s |
| Condensed mercury temperature limits | T_{Hg} | 40 to 7 | , |
| Control ratio | | 150:1 | |
| De-ionisation time (approx) | t _d | 1,000 | μS |
| Ionisation time (approx) | ti | 10 | μS |
| Anode voltage drop | | 16 | V |
| Maximum grid resistance | $R_{g(max)}$ | 100 | kΩ |
| Recommended minimum grid resistance | R _{g(min)} | 10 | kΩ |
| | 5,, | | |

MOUNTING POSITION—Vertical, Base down

BASE-B4



Viewed from free end of pins.


CONNECTIONS

| Pin 1 | Heater, Cathode | h,k |
|-------|-----------------|-----|
| Pin 2 | Grid | g |
| Pin 3 | Heater, Cathode | h,k |
| Pin 4 | Heater | h |
| Cap | Anode | a |

August, 1962


Page 1, Issue 1






Page 2

CHARACTERISTIC CURVES : V_a/V_g






CHARACTERISTIC CURVES: Ig/Vg






RATING CURVE: Forward Voltage, P.I.V./THg (Fault Conditions)



August, 1962

Page 5, Issue 1





21N15

MERCURY VAPOUR THYRATRON Indirectly heated

GENERAL

The 21N15 is a Mercury Vapour Thyratron suitable for welding and motor control. It has an indirectly heated oxide coated cathode.

| RATING | | | |
|---|----------------|----------|-----|
| Heater Voltage | Vh | 5.0 | ٧ |
| Heater Current | 1 _b | 5.0 | A |
| Maximum Peak Forward Anode Voltage | | 1.5 | kV |
| Maximum Peak Inverse Anode Voltage | P.I.V.(max) | 1.25 | kV |
| Maximum Negative Grid Voltage (before Conduction) | | 500 | ٧ |
| Maximum Negative Grid Voltage (during Conduction) | | 10 | ٧ |
| Maximum Mean Cathode Current (maximum averaging 15 seconds) | lk(av)max | 3.0 | Α |
| Maximum Peak Cathode Current (25c/s and above) | lk(pk)max | 20 | |
| Maximum Surge Cathode Current (Fault protection maximum duration 0·1 seconds) | | 200 | A |
| Maximum Critical Grid Current (at $V_a = 1.0kV$) | | <10 | μА |
| Maximum Power Supply Frequency Condensed Mercury Temperature | | 150 | c/s |
| Limits | THg | 40 to 75 | oC |
| Control Ratio | 6 | 150:1 | |
| De-ionisation Time (approx) | | 1,000 | μs |
| Ionisation Time (approx) | | 10 | μS |
| Anode Voltage Drop | | 16 | V |
| Maximum Grid Resistance Recommended Minimum Grid | $R_{g(max)}$ | 100 | kΩ |
| Resistance | Rg(min) | 10 | kΩ |



EDISWAN

21N15

MERCURY VAPOUR THYRATRON Indirectly heated

DIMENSIONS

Maximum Overall Length 199 mm
Maximum Diameter 57 mm
Maximum Seated Height 184 mm

MOUNTING POSITION—Vertical, Base down

CAP-CT3

BASE-UX4 (E.I.A. No. A4-10)




Viewed from free end of pins.

CONNECTIONS

| Pin 1 | Heater | h |
|-------|-----------------|------|
| Pin 2 | Heater, Cathode | h, k |
| Pin 3 | Grid | g |
| Pin 4 | Heater, Cathode | h, k |
| Сар | Anode | a |






All dimensions in mm.




CHARACTERISTIC CURVES: Va/Vg





CHARACTERISTIC CURVES: Ig/Vg



Electronic Components Division Tel.: GERRARD 9797




21N15 MERCURY VAPOUR THYRATRON

Indirectly heated


RATING CURVE: Forward Voltage, P.I.V./THg







CHARACTERISTIC CURVES: THg/t







MOLTAGORY MADE LA CHARACTER Local Mod Sel

Her apply a seri



SPECIAL QUALITY BEAM TETRODE Directly heated—for battery operation

GENERAL

The S2P20 can withstand continuous vibration at an acceleration of 2.5g. and a short duration shock of 500g. Further interesting design features are as follows:

Miniature construction for Portable equipment. For use as an R.F. Power Amplifier up to ... 100Mc/s R.F. Power, Single ended > 2.4W R.F. Power, Parallel or Push Pull ... > 4.8W Designed to operate with a low H.T. Voltage of 150V. Centre tapped Filament for Series or Parallel operation.

| RATING-Absolute Valu | es. | Series | Parallel |
|---|---------------------|-------------|-----------------|
| Filament Voltage Filament Current | V _f | 5·0 0·23 | 2·5 V 0·46 A |
| Maximum Anode Dissipation Maximum Screen | Pa(max) | 5 | W |
| Dissipation Maximum Anode | Pg2(max) | 2 | W |
| Voltage | V _{a(max)} | 150 | V |
| Maximum Screen Voltage | Vg2(max) | 150 | V |
| Maximum Operating Frequency Maximum Shock | f(max) | 100 | Mc/s |
| (short duration) Maximum Acceleration | (g) | 500 | |
| (continuous operation) | (g) | 2. | 5 |

INTER-ELECTRODE CAPACITANCES (pF)+

| Anode/Grid 1 | ca-g1 | < 0.17 |
|--------------|-------|--------|
| Grid 1/Earth | cin | 8-5 |
| Anode/Earth | Cout | 6.6 |

† Measured with fully shielded socket, without can and skirt.

DIMENSIONS

| Maximum Overall Length | 67·5mm |
|------------------------|--------|
| Maximum Diameter | 22-2mm |
| Maximum Seated Height | 60-5mm |
| | |

MOUNTING POSITION—Unrestricted.

December, 1961



S2P20

SPECIAL QUALITY BEAM TETRODE Directly heated—for battery operation

The test limits are for guidance in equipment design. The quality is controlled statistically to ensure that only a small percentage are outside these limits. The quality control levels are related to the importance of the characteristic hains tested LIMITS OF CHARACTERISTICS

| related to the importance of the characteristic being tested. | naracte | LISCIC | Delu | g rest | Ġ. | | | | |
|--|---------|---------|------------|--|-------------------|---------------------|---------------------|-------------|-------|
| TEST | Vf(do | 3 4° CO | CONDITIONS | CONDITIONS Vf(dc) Va* Vg2* Vg1* Vbp* (V) (V) (V) (V) (V) | Х _{bр} * | LIFE | LIMITS MIN. MAX. | ITS MAX. | STINO |
| Filament Current | 7. | | | ٠ | | Initial | 0.21 | 0.25 | 4 |
| Anode Current | 2 | 150 150 | 150 | -10 | 0 | Initial | 21 | 35 | mA |
| Screen Current | 2 | 150 | 150 | 10 | 0 | Initial | · | 4 | mA |
| Mutual Conductance | 2 | 150 | 150 | -10 | 0 | Initial | 3.2 | 5.4 | mA/V |
| Grid No. 1 Cut-off Voltage $(I_a=2mA)$ | 2 | 150 | 150 | | 0 | Initial | Page ith a | -25 | > |
| Peak Anode Current († V2/k)=120V. RI = 320Ω. | | | | | | V a | | 7 E | |
| $V_{\text{sig}} = 20 V_{\text{rms}}$ $R_{\text{Pl}} = 22 K \Omega$ | 2 | , it | 120 | ٠ | 0 | Initial | 110 | | mA |
| | | | | | | 250 hrs. | 100 | 2. | mA |
| Change in Peak Anode Current | 4.5 | | 120 | 1 | 0 | Initial | | 25 | mA |
| Change in Peak Anode Current | 5 | · un | 120 | zipiz | 0 | Initial to 1 hr. | hall hall | 20 | % |
| Reverse Grid Current | Ŋ | 150 | 150 | 5 150 150 -10 | 0 | Initial 250 hrs. | LEU Jeni Jeni | 4 | EAA |



SPECIAL QUALITY BEAM TETRODE Directly heated—for battery operation

| n | LIMITS OF CHARACTERISTICS, cont. | CHA | RACTE | RISTICS | , cont. | | | | |
|---|----------------------------------|------|---------------------------|-------------------|---------|---------------------|-----|------|-------------|
| Interelectrode Leakage Resistance V_{g1} to all = $-100V$ | 0 | | | | | Initial 250 hrs | | 100 | ΣΣ |
| V_{g2} to all $=-300 V$ | 0 | | | | · | Initial 250 hrs. | ٠. | 100 | E E E |
| V_a to all = -300 V | 0 | | ٠ | | ٠ | Initial 250 hrs. | | 100 | GΩ |
| V_{bp} to all $=-300V$ | 0 | | | | | Initial 250 hrs. | | 100 | ω G G |
| Vibration Noise Output Voltage; $V_{a}(b)\!=\!150V,R_{L}\!=\!2K\Omega$ Life Test Conditions | 'n | | 150 | 150 -10 | 0 | Initial | | 200 | mVrms |
| Adjust Grid No. 1 Voltage to give la=33mA | 5 1: (rms) | 150 | 5 150 150 rms) | | 0 | 0.10 | | | |
| Capacitances measured in fully shielded socket, without can | Ele | ctro | Electrodes gl to E a to E | gl to E a to E | | er he | 5.6 | 10.5 | ች 4 |
| and skirt. | | | 8 | a to g1 | | | | 0.17 | P. |

* Voltages measured with respect to filament negative (pin 4).

‡ Preheat for 15 minutes before test at Anode Current test conditions.

I power supplies shall have negligible impedance to operating frequency. Grid signal impedance shall be less than 5 ohms; voltage sinusoidal.

SPECIAL QUALITY BEAM TETRODE Directly heated—for battery operation

SPECIAL TESTS

Glass Envelope Strain Test

A statistical sample is tested to control glass quality. No voltages are applied to the electrodes.

The valves are completely immersed in boiling water at a temperature between 97°C and 100°C for 15 seconds and then immediately plunged into ice cold water for 5 seconds. The valves are then examined for glass cracks.

Base Strain Test

A statistical sample is tested to control base strain. No voltages are applied to the electrodes.

The pins of the valves are forced over a specified cone, valves and cones are then completely submerged in boiling water at a temperature between 97°C and 100°C for 10 seconds. The valves and cones are allowed to cool to room temperature on a wooden support before examining for glass cracks.

Fatigue Test

A statistical sample is tested to control heater failures and other mechanical defects. The heaters are successively run at 5V r.m.s. for one minute and switched off for 3 minutes, no other voltages applied.

The valves are rigidly mounted on a vibrating machine and vibrated for at least 100 hours, for not less than 30 hours in each of three mutually perpendicular planes at a frequency of 170 c/s with a minimum peak acceleration of 5g.

Shock Test

A statistical sample is tested to control mechanical defects likely to be caused by shock. No voltages are applied to the electrodes.

The valves are subjected to five blows of approximately 500g acceleration in each of four directions.

Holding Period-Inoperatives Control

After completing the test specification the valves are held for at least 28 days and are then retested to ensure that there has been no deterioration on storage.

December, 1961



SPECIAL QUALITY BEAM TETRODE Directly heated—for battery operation

| CHARACTERISTICS | | | |
|----------------------|-------|-----|------|
| Filament Voltage | V_f | 5 | V |
| Anode Voltage | V_a | 150 | V |
| Screen Voltage | Vg2 | 150 | V |
| Control Grid Voltage | Vg1 | -10 | ٧ |
| Beam Plates Voltage | Vbp | 0 | ٧ |
| Anode Current | la | 28 | mA |
| Screen Current | lg2 | 2 | mA |
| Mutual Conductance | gm | 4-3 | mA/V |

TYPICAL OPERATION—Class "C" Power Amplifier (at 70 Mc/s)

| (at /0 Mc/s) | | |
|-------------------------|--------|--------|
| Anode Voltage | Va | 150 V |
| Screen Supply Voltage | Vg2(b) | 150 V |
| Screen Feed Resistor | Rg2 | 3.9 kΩ |
| Anode Current | la | 40 mA |
| Control Grid Current | lg1 | 1 mA |
| Control Grid Voltage | Vg1 | -22 V |
| Grid Bias Resistor | Rg1 | 22 kΩ |
| R.F. Power Output (min) | Pout | 2.4 W |

December, 1961



SPECIAL QUALITY BEAM TETRODE Directly heated—for battery operation

BASE-B9A



Viewed from free end of Pins.

CONNECTIONS

| Pin 1 | Anode | 2 |
|-------|---------------------|-----|
| Pin 2 | No Connection | NC |
| Pin 3 | Beam Plates | bp |
| Pin 4 | Filament | f |
| Pin 5 | Filament | f+ |
| Pin 6 | Grid 2 | g2 |
| Pin 7 | Grid 1 | gl |
| Pin 8 | Beam Plates | bp |
| Pin 9 | Filament Centre Tap | fct |

December, 1961



SPECIAL QUALITY BEAM TETRODE Directly heated—for battery operation

TENTATIVE

GENERAL

The S2P21 can withstand continuous vibration at an acceleration of 2-5g and a short duration shock of 500g. Further interesting design features are as follows:

Miniature construction for portable equipment.

| For use as an r.f. power amplifier up to | | | | 200 Mc/s |
|---|--------|-----|---------|--------------|
| R.F. power, single ended | | *** | | 2.9 W |
| R.F. power, parallel or push pull | | | *** | 5.8 W |
| Designed to operate with a low h.t. voltage | of 150 | V. | | |

Centre tapped filament for series or parallel operation.

RATING-Absolute values

| Filament voltage | Vf | 2.5 | 5.0 V |
|---|----------|------|--------|
| Filament current | lf . | 0-46 | 0.23 A |
| Maximum anode dissipation | Pa(max) | 5.0 | W |
| Maximum screen dissipation | Pg2(max) | 2-0 | W |
| Maximum anode voltage | Va(max) | 150 | V |
| Maximum screen voltage | Vg2(max) | 150 | V |
| Maximum operating frequency | f max | 200 | Mc/s |
| Maximum shock (short duration) | | 500 | g |
| Maximum acceleration (continuous operation) | | 2.5 | g |

INTER-ELECTRODE CAPACITANCES*

| Anode/Grid 1 | ca-g1 | <0.13 | pF |
|--------------|-------|-------|----|
| Grid 1/Earth | Cin | 9.0 | pF |
| Anode/Earth | Cout | 4.5 | pF |

* Measured in fully-shielded socket, without can and skirt.

CHARACTERISTICS

| Filament voltage | Vf. | 5-0 | V |
|----------------------|-----------------|-----|------|
| Anode voltage | Va | 150 | V |
| Screen voltage | Vg2 | 150 | V |
| Control grid voltage | V _{g1} | -10 | V |
| Beam plates voltage | Vbp | 0 | V |
| Anode current | la · | 28 | mA |
| Screen current | lg2 | 2.0 | mA |
| Mutual conductance | 8m | 4.3 | mA/V |

February, 1962

ADVANCE DATA, Page 1



SPECIAL QUALITY BEAM TETRODE

Directly heated-for battery operation

TENTATIVE

LIMITS OF CHARACTERISTICS

The test limits are for guidance in equipment design. The quality is controlled statistically to ensure that only a small percentage are outside these limits. The quality control levels are related to the importance of the characteristic being tested.

| | | _ C | DNDIT | IONS | | | | | |
|--|-------------|-------|-------|-------|---------------------|---------------------|------------|--------------|----------|
| TEST | Vf(d (V) | | | | * V _{bp} * | PERIOD | | MITS MAX. | UNITS |
| Filament current | 5 | | | | | Initial | 0.21 | 0.25 | Α |
| Anode current | 5 | 150 | 150 | -10 | 0 | Initial | 21 | 35 | mA |
| Screen current | 5 | 150 | 150 | -10 | 0 | Initial | | 4 | mA |
| Mutual conductance Grid No. 1 cut-off voltage | 5 | 150 | 150 | -10 | 0 | Initial | 3.2 | 5-4 | mA/V |
| (l _a =2mA) Peak anode current | 5 | 150 | 150 | • | 0 | Initial | • | -25 | ٧ |
| $(† V_a(b) = 120V, RL = 320\Omega,$ | | | | | | | | | |
| $V_{sig} = 20V_{rms}$, $R_{g1} = 22K\Omega$) | 5 | | 120 | | 0 | Initial | 110 | | mA |
| | | | | | | 250 hrs. | 100 | | mA |
| Change in peak anode current | 4-5 | | 120 | • | 0 | Initial | | 25 | mA |
| Change in peak anode current | 5 | | 120 | • | 0 | Initial to 1 hr. | | 20 | % |
| Reverse grid current | 5 | 150 | 150 | -10 | 0 | Initial 250 hrs. | | 2 4 | μΑ |
| Inter-electrode leakage resistance | _ | | | | | la tetal | | 400 | |
| Vg1 to all = -100V | 0 | • | | | | Initial | | 100 | MΩ |
| V_{g2} to all = -300V | 0 | | | | | 250 hrs. | | 100 | MΩ |
| vg2 to all = -300 v | U | • | | - 1 | | 250 hrs. | HI I | 50 | MΩ |
| Va to all = -300V | 0 | | | | | Initial | | 100 | MΩ |
| Va to all == -000 V | 0 | | | | | 250 hrs. | | 50 | MΩ |
| V _{bp} to all = -300V | 0 | | | | | Initial | | 100 | MΩ |
| vop to an - ooov | | | | | | 250 hrs. | | 50 | MΩ |
| Vibration noise output voltage‡ | 5 | | 150 | -10 | 0 | Initial | ting to | 500 | 1 |
| $V_a(b)=150V$, $RL=2K\Omega$ | 3 | | 130 | -10 | U | iniciai | | 300 | mVrm |
| Life Test Conditions Adjust grid No. 1 voltage to give la=33mA | | 150 | 150 | | 0 | | | 14 19-1 | |
| 0 | (rms | / | | | | | | | 0.00 |
| Capacitances measured in fully shielded socket, without can | Ele | ctrod | a t | to E | | | 6·5 5·6 | 10·5 7·6 | pF pF |
| and skirt | | | a t | to g1 | | | | 0.17 | pF |

^{*} Voltages measured with respect to filament negative (pin 4).

February, 1962

ADVANCE DATA, Page 2

[†] All power supplies shall have negligible impedance to operating frequency. Grid signal impedance shall be less than 5 ohms; voltage sinusoidal.

[‡] Preheat for 15 minutes before test at anode current test conditions.



SPECIAL QUALITY BEAM TETRODE

Directly heated-for battery operation

TENTATIVE

SPECIAL TESTS

Glass Envelope Strain Test

A statistical sample is tested to control glass quality. No voltages are applied to the electrodes.

The valves are completely immersed in boiling water at a temperature between 97°C and 100°C for 15 seconds and then immediately plunged into ice cold water for 5 seconds. The valves are then examined for glass cracks.

Base Strain Test

A statistical sample is tested to control base strain. No voltages are applied to the electrodes.

The pins of the valves are forced over a specified cone, valves and cones are then completely submerged in boiling water at a temperature between 97°C and 100°C for 10 seconds. The valves and cones are allowed to cool to room temperature on a wooden support before examining for glass cracks.

Fatigue Test

A statistical sample is tested to control heater failures and other mechanical defects. The heaters are successively run at 5V r.m.s. for one minute and switched off for 3 minutes, no other voltages applied.

The valves are rigidly mounted on a vibrating machine and vibrated for at least 100 hours, for not less than 30 hours in each of three mutually perpendicular planes at a frequency of 170 c/s with a minimum peak acceleration of 5g.

Shock Test

A statistical sample is tested to control mechanical defects likely to be caused by shock. No voltages are applied to the electrodes.

The valves are subjected to five blows of approximately 500g acceleration in each of four directions.

Holding Period-Inoperatives Control

After completing the test specification the valves are held for at least 28 days and are then retested to ensure that there has been no deterioration on storage.

February, 1962

ADVANCE DATA, Page 3



SPECIAL QUALITY BEAM TETRODE

Directly heated—for battery operation

TENTATIVE

| TYPICAL | OPERATION- | -Class C power | amplifier at 70 Mc/s. |
|---------|------------|----------------|-----------------------|
| | | | |

| TITLE OF MILITIES TO CIAGO C PO | reci dilipililei de l'ellejs. | | |
|---------------------------------|-------------------------------|---------|--|
| Anode voltage | V _a | 150 V | |
| Screen supply voltage | Vg2(b) | 150 V | |
| Screen feed resistor | Rg2 | 5.0 kΩ | |
| Anode current (approx) | la | 40 mA | |
| Control grid current | lg1 | 0.7 mA | |
| Control grid voltage | Vg1 | -15·4 V | |
| Grid bias resistor | Rg1 | 22 kΩ | |
| R.F. power in load (average) | PĽ | 2-9 W | |
| | | | |

TYPICAL OPERATION—Class C power amplifier at 200 Mc/s

| TITIOAL OF LITATION Class C POT | ver amplifier at 200 lite/s | |
|---------------------------------|-----------------------------|--------|
| Anode voltage | Va | 150 V |
| Screen supply voltage | Vg2(b) | 150 V |
| Screen feed resistor | Rg2 | 17 kΩ |
| Anode current (approx) | la a | 40 mA |
| Control grid current | lg1 | 1.0 mA |
| Control grid voltage | V ₀ 1 | -22 V |
| Grid bias resistor | Rg1 | 22 kΩ |
| R.F. power in load (average) | PĽ. | 1-9 W |

DIMENSIONS

| DITIETION | |
|------------------------|---------|
| Maximum overall length | 67∙5 mm |
| Maximum diameter | 22.2 mm |
| Maximum seated height | 60·5 mm |

MOUNTING POSITION—Unrestricted.

BASE—Noval (B9A)



Viewed from free end of pins.

CONNECTIONS

| COMMECTIONS | | |
|-------------|---------------------|-----|
| Pin 1 | Anode | a |
| Pin 2 | Anode | a |
| Pin 3 | Anode | a |
| Pin 4 | Filament | f |
| Pin 5 | | f+ |
| Pin 6 | Grid 2 | 92 |
| Pin 7 | Grid 1 | 91 |
| Pin 8 | Beam Plates | bp |
| Pin 9 | Filament Centre Tap | fct |
| | | |

February, 1962

ADVANCE DATA, Page 4

Associated Electrical Industries Limited



SPECIAL QUALITY H.F. PENTODE

Indirectly heated—for parallel operation TENTATIVE

GENERAL

The S6F12 is a Special Quality H.F. Pentode having characteristics similar to the 6F12, and is intended for use in AC or DC powered equipment having parallel connected heater chains. A special shock resistant construction is employed which gives increased reliability and life expectancy.

Quality tests are performed on electrical characteristics, vibration noise, base strain, glass strain, electrode resonance, vibration fatigue, shock resistance, heater cycling, stability and life.

The characteristic curves of the S6F12 are similar to those of the 6F12.

RATING

| Heater Voltage | (volts) | Vh | 6.3 |
|--|-----------|---------------------|-------|
| Heater Current | (amps) | lh | 0.3 |
| Maximum Anode Voltage | (volts) | V _{a(max)} | 300 |
| Maximum Screen Voltage | (volts) | Vg2(max) | 300 |
| Maximum Anode Dissipation | n (watts) | Pa(max) | 3.0 |
| Maximum Screen Dissipation | (watts) | Pg2(max) | 0.9 |
| Maximum Heater to Cathoo Voltage | | Vh-k(max) | 150 |
| Maximum Grid 1 to Cathod Resistance (cathode bias) | | Rg1-k(max) | 0.5* |
| Mutual Conductance | (mA/V) | gm | 7.5** |
| Inner Mu | | μg1-g2 | 75** |
| Maximum Shock (short duration) | (g) | | 500 |
| Maximum Acceleration (continuous operation) | (g) | | 2.5 |
| Maximum Bulb Temperatur | e (°C) | | 200 |
| | | | |

^{*} Maximum value for fixed bias operation=100k Ω .

December, 1961

^{**} V_a=V_g2=250 v; I_a=10 mA; I_g2=2.5 mA; V_g1=-2v_s
All maximum ratings are Absolute Values not Design Centres.

SPECIAL QUALITY H.F. PENTODE Indirectly heated—for parallel operation

TENTATIVE

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid 1 | ca-g1 | 0.008† |
|--------------|-------|--------|
| Anode-Earth | Cout | 3.25†† |
| Grid 1/Earth | cin | 7.6 †† |

† Total capacity including a Benjamin B7G holder type 75/833 and cylindrical screen can 75/832.

†† Inter-electrode capacity with holder capacity balanced out but with cylindrical screen can.

"Earth" denotes the remaining earthy potential electrodes, heater and shields connected to cathode.

DIMENSIONS

| Maximum Overall Length | (mm) | | 54.5 |
|---------------------------|----------|--|------|
| Maximum Diameter | (mm) | | 19 |
| Maximum Seated Height | (mm) | | 47.5 |
| Approximate Nett Weight | (ozs) | | 14 |
| Approximate Packed Weight | t (ozs.) | | 1 2 |

MOUNTING POSITION-Unrestricted.

TYPICAL OPERATION

| Anode Voltage | (volts) | Va | 250 |
|-------------------|---------|-----|-----|
| Screen Voltage | (volts) | Vg2 | 250 |
| Grid Bias Voltage | (volts) | Vg1 | -2 |
| Anode Current | (mA) | la | 10 |
| Screen Current | (mA) | lg2 | 2.5 |

BULB-Clear.

December, 1961




SPECIAL QUALITY H.F. PENTODE

Indirectly heated-for parallel operation

TENTATIVE

BASE-B7G



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | Control Grid | 81 |
|-------|-----------------|------------|
| Pin 2 | Cathode | k |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |
| Pin 5 | Anode | а |
| Pin 6 | Suppressor Grid | g 3 |
| Pin 7 | Screen Grid | 82 |



DESCRIPTION OF THE PROPERTY OF



make he had been been as a



SPECIAL QUALITY PULSE AND R.F. TETRODE Indirectly heated—for parallel operation

TENTATIVE

GENERAL

The S6F17 is a Special Quality Beam Tetrode intended for pulse and R.F. amplification, and has characteristics similar to the 6F17. It is intended for use in AC or DC powered equipment having parallel connected heater chains. A special shock resistant construction is employed which gives increased reliability and life expectancy.

Quality tests are performed on electrical characteristics, vibration noise, base strain, glass strain, electrode resonance, vibration fatigue, shock resistance, heater cycling, stability and life.

RATING

| KATING | | | |
|-----------------------------------|---------|--------------|------|
| Heater Voltage | (volts) | ٧h | 6.3 |
| Heater Current | (amps) | lh | 0.3 |
| Maximum Anode Voltage | (volts) | $V_{a(max)}$ | 600 |
| Maximum Screen Voltage | (volts) | Vg2(max) | 600 |
| Maximum Anode Dissipation | (watts) | Pa(max) | 3.5 |
| Maximum Screen Dissipation | (watts) | Pg2(max) | 0.7 |
| Maximum Heater-Cathode Voltage | (volts) | Vh-k(max) | 100 |
| Mutual Conductance | (mA/V) | gm | 8.3* |
| Maximum Bulb Temperature | (°C) | | 165‡ |
| Maximum Shock (Impact) | (g) | | 500 |
| Maximum Acceleration (Continuous) | (g) | | 2.5 |

^{*} $V_a = V_g = 250$ v; $I_a = 64$ mA; $V_{g1} = -6.25$ v. Pulse conditions.

All maximum ratings are Absolute Values not Design Centres.

December, 1961

[‡] Reliability will be seriously impaired if the maximum bulb temperature is exceeded.

SPECIAL QUALITY PULSE AND R.F. TETRODE Indirectly heated—for parallel operation

TENTATIVE

NOTE

The life expectancy may be reduced if conditions other than those used for life test are imposed on the valve and will be reduced appreciably if maximum ratings are exceeded. Life test values are: $V_a=250 \text{ v}$; $V_g2=200 \text{ v}$; $V_{h-k}=100 \text{ v}$; $R_g1=500 \text{ kilohms}$; $R_k=1 \text{ kilohm}$. Reliability and performance will be adversely affected if heater voltage ratings are exceeded, life and reliability being directly related to the degree with which the heater voltage is maintained at its centre rated value.

INTER-ELECTRODE CAPACITANCES (pF)

| Grid 1/Earth | cin | 6.2 |
|--------------|-------|------|
| Anode/Earth | cout | 5.2 |
| Grid 1/Anode | ca-g1 | 0.03 |

Capacitances measured with screen can but with holder capacity balanced out.

DIMENSIONS

| Maximum Overall Length | (mm) | 54.5 |
|---------------------------|----------|------|
| Maximum Diameter | (mm) | 19.0 |
| Maximum Seated Height | (mm) | 47.5 |
| Approximate Nett Weight | (ozs) | 14 |
| Approximate Packed Weight | t (ozs.) | 1 2 |

MOUNTING POSITION—Unrestricted

BULB-Clear


[&]quot;Earth" denotes the remaining earthy potential electrodes, heater and shields connected to cathode.



SPECIAL QUALITY PULSE AND R.F. TETRODE Indirectly heated—for parallel operation

TENTATIVE

BASE-B7G.



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | Grid 1 | g1 |
|-------|-------------|-----------|
| Pin 2 | Cathode | k |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |
| Pin 5 | Anode | a |
| Pin 6 | Beam Plates | bp |
| Pin 7 | Grid 2 | 82 |



CONTROL TO REEL TO A THOROUGH DATE OF THE CONTROL O

Burn of the IX

100

THE LIMITION

| and the second | |
|----------------|--|
| | |
| | |



S6F17F

SPECIAL QUALITY PULSE BEAM TETRODE Indirectly heated

GENERAL

The S6F17F is an indirectly heated, special quality, pulse beam tetrode with flying leads, for use in pulse and r.f. amplifiers where dependable performance is required under shock and vibration conditions.

A special shock resistant construction is employed which

gives increased reliability and life expectancy.

Quality tests are performed on electrical characteristics, vibration noise, lead fragility, glass strain, electrode resonance, vibration fatigue, shock resistance, heater cycling, stability and life.

| | TI | | |
|--|----|--|--|
| | | | |
| | | | |

| KATING; | | | |
|---|------------|------|------|
| Heater Voltage | ٧h | 6.3 | V |
| Heater Current | h | 0.3 | A |
| Maximum Anode Voltage | Va(max) | 600 | ٧ |
| Maximum Screen Voltage | Vg2(max) | 600 | ٧ |
| Mutual Conductance | 8m | 8.3* | mA/V |
| Maximum Anode Dissipation | Pa(max) | 3.5 | W |
| Maximum Screen Dissipation | Pg2(max) | 0.7 | W |
| Maximum Heater/Cathode Voltage d.c. | Vh-k(max) | 100 | ٧ |
| Maximum Bulb Temperature | Tbulb(max) | 165 | °C |
| Maximum Shock (short duration) | , , | 500 | g |
| Maximum Acceleration (continuous operation) | | 2.5 | g |
| | | | |

^{*} $V_a = V_g 2 = 250V$, $V_{g1} = -6.25V$. Tested under pulse conditions.

[†] If used in a can at maximum rating, the can must be matt black both internally and externally.

[‡] All limiting values are Absolute Values, not Design Centres.



S6FI7F

SPECIAL QUALITY PULSE BEAM TETRODE Indirectly heated

| Test | 35 | S & Cond | Conditions Va Vg2 (V) (V) | la (mA) | Life | Min. | Limits . Max. | Units |
|-------------------------------|------|----------|---------------------------------|------------|--------------------|------|------------------|------------|
| Heater Current | 6.3 | | | | Initial 500 hrs | 0.27 | 0.33 | 4 4 |
| Negative Grid Voltage | 6.3 | 200 | 200 | 17 | 1,000 hrs. | 8.4 | 15.8 | (∢> |
| | | | | | 500 hrs. | 7.4 | 15.8 | >> |
| Screen Current | 6.3 | 200 | 200 | 17 | Initial | 2.05 | 5.1 | mA |
| Mutual Conductance | 6.3 | 200 | 200 | 17 | Initial | 5.6 | 2.0 | mA/V |
| Pulse Anode Current | 6.3 | 300 | 300 | | Initial | 133 | | mA |
| V91=-100V, Pulse Amp.=+100V | | | | | 500 hrs. | 100 | | mA |
| tp=10-15us, Duty cycle .0025 | | | | | 1,000 hrs. | 06 | | mA |
| Change in Pulse Anode Current | 6.3 | 300 | 300 | | Initial | | | |
| | | | | | to 1 hr. | | 20 | 3 |
| Inner Amplification Factor | 4.3 | 000 | 006 | 47 | oitio. | 7.5 | 19.5 | |
| Anode Current Cut-off | 9 40 | 200 | 200 | | | | 38 | |
| Reverse Grid Current | 6.9 | 200 | 200 | 17 | | | 0.75 | 111 |
| Re1 = 500 k \(\Omega\) (max) |) | | | | | | 1.0 | MA |
| | | | | | 1,000 hrs. | , | 1.5 | 777 |

LIMITS OF CHARACTERISTICS

9



S6FI7F

SPECIAL QUALITY PULSE BEAM TETRODE Indirectly heated

a

| LIMITS | OF | CHA | RACT | ERIST | LIMITS OF CHARACTERISTICS—Cont. | | | |
|---|-------------|---|--|------------|---------------------------------|------------------|--------------------|--------|
| Test | 35 | | Conditions Va Vg2 (V) (V) | la (mA) | Life Period | Limits Min. N | nits Max. | Units |
| Reverse Grid Current Rg1 = $500\mathrm{k}\Omega$, V_{g1} = $-38V$ Heater/Cathode Leakage Current V_{h-k} = $\pm 100V$ | 7.0 | 6.3 | . 500 | | Initial Initial 500 hrs. | 5.0 | 10 10 10 10 | 4444 |
| Inter-electrode Leakage Resistance V_{g1} to all = $-100V$ | 6.3 | ٠ | | | Initial 500 hrs | 100 | | G C |
| V_{g2} to all = -300 V | 6.3 | | | | Initial 500 brs | 865 | | ΣΣ |
| V_a to all = -300 V | 6.3 | | | | Initial 500 hrs. | 500 | | ΣΣ |
| Vibration Noise Output Voltage $V_{a}(b) = 250V$, $V_{g1} = -17V$, $R_{L} = 2k\Omega$ Life Test Conditions | 6.3 | | 250 | 18 | Initial | | 09 | mV(p-p |
| $R_{g1} = 500k \Omega$, $V_{h-k} = 100V$, $R_k = 1k \Omega$ Capacitances measured in fully shielded socket but with holder capacity balanced out. | 6·3 Elec | 6·3 250 200 Electrodes g1 to a to | 6-3 250 200 Electrodes g1 to E a to E a to g1 | | | 5.5 | 7.1 6.1 0.05 | 444 |

December, 1961

S6FI7F

SPECIAL QUALITY PULSE BEAM TETRODE Indirectly heated

INTER-ELECTRODE CAPACITANCES **

| Anode/Grid 1 | ca-g1 | 0.03 pF |
|--------------|-------|---------|
| Grid 1/Earth | cin | 6.2 pF |
| Anode/Earth | Cout | 5·2 pF |

** Measured with cylindrical screen but with holder capacity balanced out.

"Earth" denotes the remaining earthy potential electrodes, heater and shields connected to cathode.

DIMENSIONS

| Minimum Lead Length | 38 | mm |
|-----------------------|------|----|
| Maximum Diameter | 19 | mm |
| Maximum Seated Height | 47.5 | mm |

MOUNTING POSITION—Unrestricted.

BASE-B7G/F



Viewed from free end.

CONNECTIONS

| Pin 1 | Grid 1 | 81 |
|-------|-------------|----|
| Pin 2 | Cathode | k |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |
| Pin 5 | Anode | a |
| Pin 6 | Beam Plates | bp |
| Pin 7 | Grid 2 | g2 |
| | | |

December, 1961



S6FI7F

SPECIAL QUALITY PULSE BEAM TETRODE

SPECIAL TESTS

Glass Envelope Strain Test

A statistical sample is tested to control glass quality. No voltages are applied to the electrodes.

The valves are completely immersed in boiling water at a temperature between 97°C and 100°C for 15 seconds and then immediately plunged into ice cold water for 5 seconds. The valves are then examined for glass cracks.

Base Strain Test

A Lead Fragility Test is carried out in place of the Base Strain Test.

Fatigue Test

A statistical sample is tested to control heater failures and other mechanical defects. The heaters are successively run at 6.9V for one minute and switched off for three minutes, no other voltages applied. The valves are rigidly mounted on a vibrating machine and vibrated for at least 100 hours, for not less than 30 hours in each of three mutually perpendicular planes at a frequency of 170 c/s with a minimum peak acceleration of 5g.

Shock Test

A statistical sample is tested to control mechanical defects likely to be caused by shock. No voltages are applied to the electrodes. The valves are subjected to five blows of approximately 500g acceleration in each of four directions.

Holding Period-Inoperatives Control

After completing the test specification the valves are held for at least 28 days and are then retested to ensure that there has been no deterioration on storage.



STATES MANAGEMENT MUNUC SADORES

TEST DUBBER

Burth with the second section of the

A scattered comment to be successful and properly and scattered as the electron and successful a

Thirty Steel

the first frequency from a large of an elitic of the Barn street.

on Tours St.

A mathematic and provided to concrete toward allumes and other notices are supported by a control of feet to the control of the state of the control of the

ser F. daggill.

Franchical manufacto control magnification defects restly to be caused by shape. No voltarios and applied to our sectodes. The relate are subjected to five blows of controllery 200 conference in one of four subsections.

Holdies Forlad-Indos thirds Cold of

Airer completing the case equalification the valves and held age in pass 15 days and are those respects to contract that there has been no direct ordain on earth go.



SPECIAL QUALITY DUAL CONTROL PENTODE

Indirectly heated

TENTATIVE

GENERAL

The S6F33 is a Special Quality screened H.F. Pentode having a short cut off suppressor grid characteristic and is intended for use where dependable performance is required under conditions of shock and vibration. It is suitable for modulation, gating, and variable reactance applications, where only a small input is available. A diode has been tied to the suppressor grid to prevent blocking when this grid is under positive drive conditions.

RATING-Absolute Values

| Heater Voltage (volts) | ٧h | 6.3 |
|--|---------------------|-----------|
| Heater Current (amps) | l _h | 0.35 |
| Maximum Anode Dissipation (watts) | Pa(max) | 3.0 |
| Maximum Screen Dissipation (watts) | Pg2(max) | 1.5 |
| Maximum Anode Voltage (volts) | V _{a(max)} | 300 |
| Maximum Anode Voltage (la=0) (volts) | Va(b)max | 550 |
| Maximum Screen Voltage (volts) | Vg2(max) | 300 |
| Maximum Screen Voltage (Ig2=0) (volts) | Vg2(b)max | 400 |
| Maximum Heater/Cathode Voltage (volts) | Vh-k(max) | ± 150 |
| Maximum Bulb Temperature (°C) | | 200 |
| Maximum Shock (Short Duration) (g) | | 500 |
| Maximum Acceleration (Continuous | | |
| Operation) (g) | | 2.5 |

INTER-ELECTRODE CAPACITANCES (pF)

(Measured with a close fitting metal shield)

| Control Grid/Earth | cg1-E | 7.55 |
|--------------------|-------|--------|
| Anode/Earth | ca-E | 4.55 |
| Anode/Control Grid | ca-g1 | <0.015 |

December, 1961



SPECIAL QUALITY DUAL CONTROL PENTODE

Indirecty heated

TENTATIVE

DIMENSIONS

| Maximum Overall Length | (mm) | 54-5 |
|---------------------------|-------|------|
| Maximum Diameter | (mm) | 19 |
| Maximum Seated Height | (mm) | 47.5 |
| Approximate Nett Weight | (ozs) | 1/4 |
| Approximate Packed Weight | (ozs) | 1 |

MOUNTING POSITION—Unrestricted

TEST CONDITIONS

| Anode Voltage (volts) | V_a | 200 |
|--------------------------------|-----------------|------|
| Grid 2 Voltage (volts) | V _{g2} | 200 |
| Grid 3 Voltage (volts) | V_{g3} | 0 |
| Cathode Bias Resistance (ohms) | Rk | 287 |
| Anode Current (mA) | la | 7.1 |
| Grid 2 Current (mA) | lg2 | 4.35 |
| Mutual Conductance (mA/V) | gm | 4.05 |
| Anode Impedance (Megohms) | ra | 0.1 |
| Inner Mu | μg1-g2 | 42 |



SPECIAL QUALITY DUAL CONTROL PENTODE Indirectly heated

TENTATIVE

LIMITS OF CHARACTERISTICS

The test limits are for guidance in equipment design. The quality is controlled statistically to ensure that only a small percentage are outside these limits. The quality control levels are related to the importance of the characteristic being tested.

| Test | 3.5 | Cor | Conditions Va-E Vg2-E Vg3* (V) (V) (V) | S /g3* Rk (V) (Ω) | Life | Limits Min. M | Max. | Units |
|---|-----|-----|--|-------------------------|-------------|------------------|------|-------|
| Hoster Current | 6.3 | 3 | 9 | | leitia | 0.32 | 0.38 | ٩ |
| |) | | | | 500 hrs. | 0.32 | 0.38 | < |
| Anode Current | 6.3 | | 200 200 0 287 | 287 | Initial | 2.6 | 8.6 | MA |
| | | | | | 500 hrs. | 5.05 | 9.8 | MA |
| | | | | | 1,000 hrs. | 9.4 | 9.8 | mA |
| Screen Current | 6.3 | | | 287 | Initial | 2.7 | 0.9 | mA |
| Mutual Conductance | 6.3 | 200 | 200 | 287 | Initial | 3-15 | 2.4 | MA/V |
| | | | | | 500 hrs. | 2.7 | 5.4 | MA/V |
| | | | | | 1,000 hrs. | 2.5 | 2.4 | MA/V |
| Change of Mutual Conductance | 6.3 | 200 | 200 | 287 | Initial | | 10 | % |
| (1 hour life) | | | | | to 1 hr. | | | 2 |
| Change of Mutual Conductance | 5.7 | 200 | 200 | 287 | Initial | | 15 | % |
| (c.f. gm at $V_h = 6.3 \text{ V}$. Preheat valves for 5 mins.) | | | | | | | | |
| Average Change of Mutual | 4.3 | 000 | 000 | 207 | 10141 | | 7 2 | 6 |
| Conductance | ? | 200 | 0.3 200 200 0 20/ | /07 | to 500 hrs. | | 2 | % |
| | _ | | | | | | | |



SPECIAL QUALITY DUAL CONTROL PENTODE

Indirectly heated

TENTATIVE

| THE PERSON NAMED IN COLUMN TWO IS NOT THE PERSON NAMED IN COLUMN TWO I | | - | - | STREET, SQUARE, | | - | A STANDARD SANDERS OF TAXABLE PARTY. | - | THE SPECIAL PROPERTY. |
|--|-----|-----|---|-----------------|-----|---------------------|--------------------------------------|------------------|-----------------------|
| Test | 3.5 | Con | Conditions Va-E Vg2-E V ₁ (V) (V) (V | vg3* | ¥ ĝ | Life | Ain. | Limits 1. Max | Units |
| Inner Amplification Factor | 6.3 | | 200 200 0 | | 287 | Initial | 34 | 20 | |
| (Ik = 12mA, 8 vg1 = 1V) Grid No. 1 Cut-off (la = 0·1mA) | 6.3 | 200 | 200 | 0 | | Initial | . " | 12. | >> |
| $V_{g3}=0$ vary V_{g1} to give $V_{g2}=10$ mA then adjust V_{g3} | 9 | | 3 | | | | , | : | |
| for $l_a = 0.1 \text{mA}$) Grid No. 3 Current (Vg1 = -30V) Reverse Grid No. 1 Current | 6.3 | 200 | 200 | 20 | 287 | Initial | - | 0.5 | mA A |
| $(R_{g1} = 0.5 M\Omega \text{ (max)})$ |) | | | | 3 | 500 hrs. | | 000 | HA. |
| Reverse Grid No. 1 Current** | 6-9 | 300 | 300 300 0 | | 260 | Initial | | 00 | HA. |
| Heater/Cathode Leakage Current (Vh.t = 100V, Cathode positive | 6.3 | | | | | Initial 500 hrs. | | 20 40 | EA EA |
| and negative successively) | | | | | 5 | 1,000 hrs. | | 40 | #A |
| Inter-Electrode Leakage Resistance Vg1 to all = -100V | 6.3 | | | | | Initial | 100 | | GM |
| Alternatives wines that a property year | | | | | | 1,000 hrs. | 300 | | ZG Σ |
| V_{g2} to all = $-300V$ | 6-3 | | | | | Initial 500 hrs. | 000 | | SEE |
| | | | | | | 1,000 hrs. | 30 | | 2 |

December, 1961



SPECIAL QUALITY DUAL CONTROL PENTODE

Indirectly heated TENTATIVE

| Test | 35 | 8 45 | Conditions Va-E Vg2-E Vg3* (V) (V) (V) | 3,63 | * (g | Life | Limits Min. M | nits Max. | Units |
|--|-----|------|--|------|------|-----------------------------------|------------------|--|----------------------|
| V_{g3} to all = $-300V$ | 6.3 | | | | | Initial 500 hrs. | 920 | | ΣΣΣ |
| V_a to all = -300V | 6.3 | | | | | 1,000 hrs. Initial 500 hrs. | 858 | | Z G G |
| /ibration Noise Output Voltage † $(V_a(b) = 250V, V_g = -4.5V,$ | 6.3 | | 250 0 | 0 | | 1000 hrs. Initial | ° · | 15. | MΩ mV (r.m.s.) |
| RL = 2KΩ at 50c/s and 2 g min. peak acceleration) Life Test Conditions | 6.3 | 250 | 6-3 250 200 0 150 | 0 | 150 | | | John Committee of the C | elean Los |
| Lapacitances ↑↑ Electrodes \$1 to E a to E a to E a to S↑ | | | | | | | 3.9 | 8.6 5.2 0.015 | 444 |

* A zero indicates that grid 3 and cathode are joined.

Valve mounted so that the direction of vibration is parallel to the minor axis of the electrode ** Preheat valve for 5 minutes under test conditions, after a further 5 minutes the grid 1 current must not be rising or out of limits.

mounting structure.

Test of sufficient duration to obtain a steady reading of noise output.

Inter Electode capacity on 1 Mc/s bridge with valve mounted in a fully shielded socket and cylindrical screening can.

2

LIMITS OF CHARACTERISTICS—Cont.

SPECIAL QUALITY DUAL CONTROL PENTODE Indirectly heated

TENTATIVE

GLASS ENVELOPE STRAIN TEST

A statistical sample is tested to control glass quality. No voltages are applied to the electrodes.

The valves are completely immersed in boiling water at a temperature between 97°C and 100°C for 15 seconds and then immediately plunged into ice cold water for 5 seconds. The valves are then examined for glass cracks.

BASE STRAIN TEST

A statistical sample is tested to control base strain. No voltages are applied to the electrodes.

The pins of the valves are forced over a specified cone, valves and cones are then completely submerged in boiling water at a temperature between 97°C and 100°C for 10 seconds. The valves and cones are allowed to cool to room temperature on a wooden support before examining for glass cracks.

FATIGUE TESTS

A statistical sample is tested to control heater failures and other mechanical defects. The heaters are successively run at 6.9V for 1 minute and switched off for 3 minutes, no other voltages applied.

The valves are rigidly mounted on a vibrating machine and vibrated for at least 100 hours, for not less than 30 hours in in each of 3 mutually perpendicular planes at a frequency of 170 c/s with a minimum peak acceleration of 5g.

SHOCK TEST

A statistical sample is tested to control mechanical defects likely to be caused by shock. No voltages are applied to the electrodes.

The valves are subjected to 5 blows of approximately 500g acceleration in each of 4 directions.

HOLDING PERIOD—Inoperatives Control

After completing the test specification the valves are held for at least 28 days and then retested to ensure that there has been no deterioration on storage.

December, 1961



SPECIAL QUALITY DUAL CONTROL PENTODE

Indirectly heated

TENTATIVE

BASE-B7G



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | Grid 1 | 81 |
|-------|---------------------|-------|
| Pin 2 | Cath ode | k |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |
| Pin 5 | Anode | a |
| Pin 6 | Grid 3, Diode Anode | g3,ad |
| Pin 7 | Grid 2 | g2 |



TOTAL SCOTNEY JOHNNOO JAUG TILLAUD INDOPE Solved tillenies

371 7 10



part to any time and he was



SPECIAL QUALITY BEAM TETRODE

Indirectly heated-for parallel operation

TENTATIVE

GENERAL

The S11E12 is a Special Quality Beam Tetrode intended for use as a series or shunt control valve in stabilised power supply units, and has similar characteristics (within ratings) to the 12E1. It is indirectly heated and should be parallel connected to the supply. A special shock resistant contruction is employed which gives increased reliability and life expectancy.

Quality tests are performed on electrical characteristics, vibration noise, base strain, glass strain, electrode resonance, vibration fatigue, shock resistance, heater cycling, stability and life.

RATING

December, 1961

| Heater Voltage | (volts) | Vh | 6.3 |
|--|---------|--------------|--------|
| Heater Current | (amps) | lh | 1.6 |
| Maximum Anode Voltage | (volts) | $V_{a(max)}$ | 800 |
| Maximum Screen Voltage | (volts) | Vg2(max) | 300 |
| Maximum Control Grid Voltage | (volts) | Vg1(max) | -100 |
| Maximum Voltage between Grids 1 and 2 | (volts) | Vg1-g2(max) | 400 |
| Mutual Conductance | (mA/V) | gm | 13.5* |
| Inner Mu | | μg1-g2 | 5.5* |
| Maximum Anode Dissipation | (watts) | Pa(max) | 28 |
| Maximum Screen Dissipation | (watts) | Pg2(max) | 5 |
| Maximum Cathode Current | (mA) | lk(max) | 300 |
| Maximum Heater to Cathode Voltage (DC heater negative) | (volts) | Vh-k(max) | 350 |
| Maximum Heater to Cathode Voltage (DC heater positive) | (volts) | Vh-k(max) | 150 |
| Maximum Resistance Grid 1 to Cathode—Fixed Bias | (ohms) | Rg1-k(max)1 | 00,000 |
| Maximum Resistance Grid 1 to Cathode—Cathode Follower | (ΜΩ) | Rg1-k(max) | 1 |

SPECIAL QUALITY BEAM TETRODE

Indirectly heated-for parallel operation

TENTATIVE

| Maximum Acceleration (continuous operation) | (g) | | 2 |
|---|----------|-------------|---------|
| Maximum Shock (short duration) | (g) | | 500 |
| Maximum Peak Anode Voltage (Scanning Operation) | (volts) | Va(pk)max | 1,500† |
| * Measured at Va = Vg2=150 v Vg1=-8.5 v. | ; la=200 | 0 mA; lg2= | 12 mA ; |
| † For duty cycle of $1/25$ and n μ seconds. | naximum | pulse durat | ion 200 |
| All maximum ratings are Centres. | Absolute | Values not | Design |

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid 1 | ca-g1 | 1.8 |
|--------------|-------|------|
| Grid 1/Earth | cin | 19.5 |
| Anode/Earth | Cout | 16.5 |

[&]quot;Earth" denotes the remaining earthy potential electrodes, heater and shields connected to cathode.

DIMENSIONS

| Maximum Overall Length | (mm) | 98 |
|---------------------------|-------|------|
| Maximum Diameter | (mm) | 44 |
| Maximum Seated Height | (mm) | 83 |
| Approximate Nett Weight | (ozs) | 21/2 |
| Approximate Packed Weight | (ozs) | 51 |

MOUNTING POSITION—Vertical. If run horizontally then it is recommended that the axis AB be on a horizontal plane.

BULB-Clear.

December, 1961




SPECIAL QUALITY BEAM TETRODE

Indirectly heated-for parallel operation

TENTATIVE

BASE-International Octal.



Viewed from free end of pins

CONNECTIONS

| Pin 1 | Internal Connection | IC |
|-------|---------------------|-----------|
| Pin 2 | Heater | h |
| Pin 3 | Anode | a |
| Pin 4 | Grid 2 | g2 |
| Pin 5 | Grid 1 | g1 |
| Pin 6 | Beam Plates | bp |
| Pin 7 | Heater | h |
| Pin 8 | Cathode | k |

Note.—Pins 6 and 8 should be connected together at the valve holder.




SIIE12

SPECIAL QUALITY BEAM TETRODE

Indirectly heated-for parallel operation

AVERAGE CHARACTERISTIC CURVES: I_a , I_{g2}/V_{g1} Curves taken with short duration pulse Pulse Length = 12μ sec. Pulse Ratio = 400:1Grid Current starts at $V_{g1} = -1.0V$ (approx.)




December, 1961



SPECIAL QUALITY BEAM TETRODE Indirectly heated—for parallel operation

AVERAGE CHARACTERISTIC CURVES : I_a , I_{g2}/V_a $V_{g2} = 150V$

Curves taken with short duration pulse Pulse Length = $12\mu sec.$ Pulse Ratio = 400:1




December, 1961

SPECIAL QUALITY BEAM TETRODE

Indirectly heated-for parallel operation

AVERAGE CHARACTERISTIC CURVES: Ia/Vg TRIODE CONNECTED

Curves taken with short duration pulse
Pulse Length = 12 \(\mu\)sec. Pulse Ratio = 400:1
Grid Current starts at Vg1 = -1.0V (approx.)




December, 1961



SPECIAL QUALITY BEAM TETRODE Indirectly heated—for parallel operation

AVERAGE CHARACTERISTIC CURVES: I_a/V_a TRIODE CONNECTED Curves taken with short duration pulse Pulse Length= 12μ sec. Pulse Ratio=400:1Grid Current starts at $Vg_1 = -1.0$ V(approx)



December, 1961

A SOURCE OF A SECURITION OF THE PROPERTY OF TH

bedieved selvinghed included Sekelment



S19G6F

SPECIAL QUALITY HALF-WAVE RECTIFIER

Indirectly heated

GENERAL

The S19G6F is a special quality, indirectly heated, high vacuum half-wave rectifier with flying leads. It is intended for use in high voltage power supplies. A special shock resistant construction is employed which gives increased reliability and life expectancy. Quality tests are performed on electrical characteristics, vibration noise, lead fragility, glass strain, electrode resonance, vibration fatigue, shock resistance, heater cycling, stability, and life.

RATING

| Heater Voltage | Vh | 4.0 | 0 V |
|--|--------------------|-------|-----|
| Heater Current | lh. | 0.5 | 5 A |
| Maximum r.m.s. Anode Voltage | Va(r.m.s.)ma | x 2.0 | kV |
| Maximum Working Peak Inverse Voltage | | | kV |
| Maximum No Load Peak Inverse Voltage | | 6.0 | kV |
| Maximum Mean Anode Current | la(av)max | 30 | mA |
| Maximum Peak Heater/Cathode Voltage | Vh-k(pk)max | 10* | ٧ |
| Maximum Peak Anode Current | ia(pk)max | 180 | mA |
| Maximum Reservoir Capacitor (50 c/s) | C _(max) | 1.1 | μF |
| Minimum Surge Limiting Resistance | | ,500† | Ω |
| Minimum H.T. Switching Delay for Full Rating | tsd(min) | 20 | s |
| Maximum Shock (short duration) | () | 500 | g |
| Maximum Acceleration (continuous operation) | | 2. | |

^{*} Cathode and heater should normally be tied, externally.

December, 1961

[†] This resistance can be obtained in the distributed resistance of the transformer winding.

[‡] All limiting values are Absolute Values, not Design Centres.



SI9G6F

SPECIAL QUALITY HALF-WAVE RECTIFIER

Indirectly heated

LIMITS OF CHARACTERISTICS

The test limits are for guidance in equipment design. The quality is controlled statistically to ensure that only a small percentage are outside these limits. The quality control levels are related to the importance of the characteristic being tested.

| Test | 35 | S Zad | Conditions Va Vh-k (V) (V) | O (F) | Life Period | Min. | Limits n. Max. | Units |
|---|------------------------------------|------------|----------------------------------|------------------------|-------------------|---------------------|--|----------|
| Heater Current | 4 | | | | Initial | 0.45 | 0.55 | < |
| Anode Current | 4 | 55 | | | Initial | 20.47 | · · | Y E E |
| Change in Anode Current | 4 | 25 | • | 5 | Initial | 9 | ç | 6 |
| Heater/Cathode Leakage Current Voltage Breakdown, tested in | 4 | | 10 | 11.5 | Initial | igua Igua | 55 | · 4 |
| half-wave rectifier circuit. $R_{IIm}=4.5k\Omega$, $R_{L}=68k\Omega$, $I_{a}=30mA$ approximately. | 4 | 2kV rms | | - | Initial | Merani e Singres | Tata - I | |
| Load conditions maintained for 10 seconds then supply voltage switched on and off three times at five second intervals. There must be no persistent sparking, blue glow or other abnormal manifestations. | secor times sistent ions. | at f | ive se king, | upply scond blue | 50,41 5-1-17-4 | | Section in girl to sing second section | Jan 1916 |
| Life Test Conditions Tested in half-wave rectifier circuit. Rlim = $4.5 k\Omega$, RL = $66 k\Omega$, l_a = $30 mA$ approx. | 4 | 2kV rms | | - | 12.30 | | 766 | 47.5 |



S19G6F

SPECIAL QUALITY HALF-WAVE RECTIFIER

Indirectly heated

DIMENSIONS

| Maximum Seated Height | 54 mm |
|-----------------------|-------|
| Maximum Diameter | 19 mm |
| Minimum Lead Length | 38 mm |

MOUNTING POSITION—Unrestricted

CAP—CT1 and flying lead.

BASE-B7G/F



Viewed from free end.

CONNECTIONS

| Pin 1 | Internal Connection | IC |
|---------|---------------------|----|
| Pin 2 | Cathode | k |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |
| Pin 5 | Internal Connection | IC |
| Pin 6 | Internal Connection | IC |
| Pin 7 | Internal Connection | IC |
| Тор Сар | Anode | a |

December, 1961

SI9G6F

SPECIAL QUALITY HALF-WAVE RECTIFIER

Indirectly heated

Glass Envelope Strain Test

A statistical sample is tested to control glass quality. No voltages are applied to the electrodes.

The valves are completely immersed in boiling water at a temperature between 97°C and 100°C for 15 seconds and then immediately plunged into ice cold water for 5 seconds. The valves are then examined for glass cracks.

Base Strain Test

A Lead Fragility Test is carried out in place of the Base Strain Test.

Fatigue Test

A statistical sample is tested to control heater failures and other mechanical defects. The heaters are successively run at 4.0V for one minute and switched off for three minutes, no other voltages applied. The valves are rigidly mounted on a vibrating machine and vibrated for at least 100 hours, for not less than 30 hours in each of three mutually perpendicular planes at a frequency of 170 c/s with a minimum peak acceleration of 5g.

Shock Test

A statistical sample is tested to control mechanical defects likely to be caused by shock. No voltages are applied to the electrodes. The valves are subjected to five blows of approximately 500g acceleration in each of four directions.

Holding Period-Inoperatives Control

After completing the test specification the valves are held for at least 28 days and then retested to ensure that there has been no deterioration on storage.

Photo-Cells



GENERAL

The 27A12 is a vacuum Photo-Cell with a caesium antimony cathode surface, having maximum sensitivity in the blue region of the spectrum. It has a high sensitivity to daylight, but negligible infra-red response. It may be used for sound reproduction, counting applications, etc.

RATINGS—Absolute values

| Maximum working voltage | | 100 | V |
|------------------------------|-----------------------|-----|---------|
| Maximum mean cathode current | | | |
| (max averaging time 30 sec) | I _{k(av)max} | 5.0 | μA |
| Maximum ambient temperature | $T_{amb(max)}$ | 70 | °C |

INTER-ELECTRODE CAPACITANCE

| Anode/cathode | c _{a-k} | 0.7 | pF |
|---------------|------------------|-----|----|
|---------------|------------------|-----|----|

CHARACTERISTICS

| Average overall sensitivity (approx) | | 45* | $\mu A/L$ |
|--|------------|--------|-----------|
| Maximum dark current | Idark(max) | 0.005 | μΑ |
| Minimum insulation resistance between electrodes | | 20.000 | MO |

^{*} Measured at 0.04 lumens with a lamp colour temperature of 2700°K and a cell series resistance of $1.0M\Omega$. Anode voltage = 100V.


DIMENSIONS

| Maximum overall length | 54·5 mm |
|----------------------------|---------|
| Maximum seated height | 47∙5 mm |
| Light centre from seat | 23 mm |
| Maximum diameter | 19 mm |
| Approximate cathode width | 18 mm |
| Approximate cathode length | 32 mm |

MOUNTING POSITION—Unrestricted

August, 1962 Page 1, Issue 1

[†] Measured at 100V and $1.0M\Omega$ series resistance, zero illumination.



DIRECTION OF LIGHT


VIEW OF FREE END.


All dimensions in mm.

The cathode connection should be made to pins 1, 2, 6 and 7 connected together and the anode connection to pins 3, 4 and 5 connected together.



SPECTRAL RESPONSE OF ANTIMONY CAESIUM PHOTO-CATHODE







27C12

PHOTO-CELL

TENTATIVE

GENERAL

The 27C12 is a vacuum Photo-Cell with a caesium-oxygen-silver cathode surface, having maximum sensitivity in the near infra-red region of the spectrum. It is highly sensitive to incandescent light sources and may be used for machine control, counting applications, etc.

RATING-Absolute values

| Maximum working voltage | | 250 | V |
|------------------------------|-----------|-----|---------|
| Maximum mean cathode current | | | |
| (max averaging time 30 sec) | k(av)max | 10 | μA |
| Maximum ambient temperature | Tamb(max) | 100 | °C |

INTER-ELECTRODE CAPACITANCE

| Anode/Cathode | ca-k | 1-1 pF |
|---------------|------|--------|
|---------------|------|--------|

CHARACTERISTICS

| Average overall sensitivity (approx) | | 20* | $\mu A/L$ |
|--|-----------|------|-----------|
| Maximum dark current | dark(max) | 0.03 | 5† μA |
| Minimum insulation resistance between electrodes | , , | 2000 | MΩ |
| Recommended working voltage | | 50 | V |

^{*} Measured at 0·1 lumens with a lamp colour temperature of 2700°K and a cell series resistance of 1·0M Ω . Anode voltage=50V.

DIMENSIONS

| Maximum overall length | 54-5 mm |
|--------------------------------|-----------|
| Maximum seated height | 47.5 mm |
| Light centre from seat | 19-5 mm |
| Maximum diameter | 19 mm |
| Minimum cathode width | 11-5 mm |
| Minimum cathode length | 22 |
| Minimum projected cathode area | 2·6 sq.cm |

December, 1961

ADVANCE DATA, Page 1

[†] Measured at 100V and 1.0M Ω series resistance, zero illumination.



27C12

PHOTO-CELL

TENTATIVE

MOUNTING POSITION—Unrestricted

BASE-B7G

Direction of light



Viewed from free end of pins

CONNECTIONS ±

| Pin 1 | Cathode | k |
|-------|---------|---|
| Pin 2 | Cathode | k |
| Pin 3 | Anode | a |
| Pin 4 | Anode | a |
| Pin 5 | Anode | a |
| Pin 6 | Cathode | k |
| Pin 7 | Cathode | k |

† The cathode connection should be made to pins 1, 2, 6 and 7 connected together and the anode connection to pins 3, 4 and 5 connected together.


December, 1961

ADVANCE DATA, Page 2




27C12 PHOTO-CELL


TENTATIVE



All dimensions in mm.



VIEW OF FREE END.





27]12

PHOTO-CELL

TENTATIVE

GENERAL

The 27J12 is a gas-filled Photo-Cell with a caesium-oxygen-silver cathode surface, having maximum sensitivity in the red region of the spectrum. It may be used for actuating electro-mechanical devices.

RATING-Absolute values

| Maximum working voltage | | 90 | V |
|--|-----------|-----|--------------|
| Maximum mean cathode current (max averaging time 30 sec) | lk(av)max | 2.5 | μΑ |
| Maximum peak cathode current | ik(pk)max | 8.0 | μΑ |
| Maximum peak cathode current density | | 15 | $\mu A/cm^2$ |

INTER-ELECTRODE CAPACITANCE

| Anode/cathode | ca-k | 1.1 | pF |
|---------------|------|-----|----|

CHARACTERISTICS

| Average overall sensitivity (appr | ox) | | 125* | $\mu A/L$ |
|-----------------------------------|-------------------|------------|------|-----------|
| Average primary sensitivity (app | rox) | | 20† | $\mu A/L$ |
| Maximum gas amplification factor | r | Ag(max) | 10** | |
| Maximum dark current | | Idark(max) | 0.1‡ | μΑ |
| Minimum insulation resistance be | etween electrodes | , , | 2000 | $M\Omega$ |

- * Measured at 0.02 lumens with a lamp colour temperature of 2700°K and a cell series resistance of 1.0M Ω . Anode voltage=90V.
- ** Gas amplification factor is a ratio of current at 90V to current at 25V under the conditions of note*.
- † The primary sensitivity is measured at an anode voltage of 25V, at which ionization has not taken place.
- \pm Measured at 90V and 1.0M Ω series resistance, zero illumination.

December, 1961

ADVANCE DATA, Page 1



27112

PHOTO-CELL

TENTATIVE

DIMENSIONS

| Maximum overall length | 54.5 | mm |
|--------------------------------|------|-------|
| Maximum seated height | 47.5 | mm |
| Light centre from seat | 19-5 | mm |
| Maximum diameter | 19 | mm |
| Minimum cathode width | 11.5 | mm |
| Minimum cathode length | 20.5 | mm |
| Minimum projected cathode area | 2.3 | sq.cm |

MOUNTING POSITION—Unrestricted

BASE-B7G

3 0 5 2 0 6

Viewed from free end of pins

CONNECTIONS

| Pin 1 | Cathode | k |
|-------|---------|---|
| Pin 2 | Cathode | k |
| Pin 3 | Anode | a |
| Pin 4 | Anode | a |
| Pin 5 | Anode | a |
| Pin 6 | Cathode | k |
| Pin 7 | Cathode | k |
| | | |

§ The cathode connection should be made to pins 1,2,6 and 7 connected together and the anode connection to pins 3,4 and 5 connected together.


December, 1961

ADVANCE DATA, Page 2




27J12 PHOTO-CELL

TENTATIVE



All dimensions in mm.



VIEW OF FREE END.






PHOTO-CELL

GENERAL

The PE50 is a miniature gas-filled photo-cell with a Caesium-Oxygen-Silver cathode surface, having maximum sensitivity in the red and infra-red region of the spectrum. The bulb is blackened except for a window 21×11.6 mm opposite the cathode.

RATING—Absolute Values

| Approximate Overall Sensitivity (av) | 120* | μA/L |
|---|-------|--------------------|
| Approximate Primary Sensitivity (av) | 20** | |
| Maximum Gas Amplification Factor | 10† | |
| Maximum Working Voltage | 90 | V |
| Maximum Average Cathode Current | 2.5 | μΑ |
| Maximum Averaging Time | 30 | S |
| Maximum Peak Cathode Current | 8.0 | μΑ |
| Maximum Peak Cathode Current Density | 15 | μA/cm ² |
| Maximum Dark Current | 0.11 | . , |
| Minimum Insulation resistance between electrodes | 1,000 | МΩ |
| | | |

NOTES

- * Measured at 0.02 lumens with lamp colour temperature 2700°K and a cell series resistance of 1.0 M Ω . Anode Voltage = 90 volts.
- † Gas Amplification Factor is the ratio of current at 90 volts to current at 25 volts under the conditions mentioned above.
- ‡ Measured at 90 volts with 1.0 M Ω series resistance, zero illumination.
- ** The Primary sensitivity is measured at an anode voltage of 25 volts at which ionisation has not taken place.



PHOTO-CELL

| INTER-ELECTRODE | CAPACITANCE (pF) | |
|-----------------|------------------|-----|
| Anode/Cathode | ca-k | 3.0 |


DIMENSIONS Maximum Overall Length 69.0 mm 60.5 mm Maximum Seated Height Light Centre from Seat (nominal) 42.5 mm Maximum Bulb Diameter 16-25 mm 16-15 mm Maximum Base Diameter 21-0 mm Cathode Length (nominal) 11.6 mm Effective Cathode Width 2.4 cm² Window Area 2.4 cm² Projected Cathode Area 1 oz Approximate Nett Weight 43 OZ Approximate Packed Weight

MOUNTING POSITION—Unrestricted.


BASE—Miniature 4 Pin (B4B)



PHOTO-CELL



BLANK PINS NOT CONNECTED




Viewed from free end of pins.

All Dimensions in mm.



Algourenie



and some contributions

area to lark part if the blood of

and in report that the



PHOTO ELECTRIC CELL

GENERAL

The Mazda PE.51 is a Gas Filled Photo Electric Cell with a Caesium-Oxygen-Silver Cathode surface, having maximum sensitivity in the red and infra-red region of the spectrum.

RATING

| Average Overall Sensitivity (µA/lumen) | 100+ |
|--|-------|
| Average Primary Sensitivity (µA/lumen) | 20* |
| Maximum Gas Amplification Factor | 8.0\$ |
| Maximum Working Voltage (volts) | 90 |
| Maximum Average Cathode Cutrent (µA) | 5.04 |
| Maximum Peak Cathode Current (µA) | 15 |
| Maximum Peak Cathode Current Density (µA/sq cm) | 15 |
| Maximum Dark Current (µA) | 0.1= |
| Minimum Insulation resistance between electrodes (M.A.) | ,000 |
| | |

NOTES

- + Measured at 0.05 lumens with lamp colour temperature 2700°K and a cell series resistance of 0.5.Ma. Anode Voltage = 90 volts
- \$ Gas Amplication Factor is ratio of current at 90 volts to current at 25 volts under the conditions mentioned above.
- = Measured at 90 volts with 0.5.Ma series resistance: zero illumination.
- The Primary sensitivity is measured at an anode voltage of 25 volts at which ionisation has not taken place.
- & Average over a period not greater than 30 secs.

All Maximum Ratings are Absolute values not Design Centres.

INTER-ELECTRODE CAPACITANCE

Anode to Cathoce (ppF)

1.9




PHOTO ELECTRIC CELL

| D IMENSIONS | |
|---|------------|
| Max. Overall Length (mm) | 78.0 |
| Max. Seated Height (mm) | 63.5 |
| Light Centre from Seat (mm) (nominal) | 41.0 ± 2.5 |
| Max. Bulb Diameter (mm) | 28.5 |
| Max. Base Diameter (mm) | 32.0 |
| Cathode Length (mm) | 22.0 |
| Effective Cathode Width (mm) | 21.5 |
| Projected Cathode Area (sq.cm) | 4.7 |
| Approximate Nett Weight (oz) | 1 |
| Approximate packed weight (oz) | 45 |
| 300 | 8 |
| Viewed from free | of of pins |
| CONNECTIONS | of of pins |
| CONNECTIONS Pin 1 Cathode | c |
| CONNECTIONS Pin 1 Cathode Pin 2 +Internal Connection | |
| CONNECTIONS Pin 1 Cathode Pin 2 +Internal Connection Pin 3 | c |
| CONNECTIONS Pin 1 Cathode Pin 2 +Internal Connection Pin 3 - Pin 4 - | c |
| CONNECTIONS Pin 1 Cathode Part of the connection Part of the connection | c |
| CONNECTIONS Pin 1 Cathode Part of the connection Part of the connection | c |
| CONNECTIONS Pin 1 Cathode Part of the connection Part of the connection | c |
| CONNECTIONS Pin 1 Cathode Pin 2 +Internal Connection Pin 3 - Pin 4 - | |



PE5I
PHOTO ELECTRIC CELL



All dimensions in mm.



tory

must of suglements of A

OF SHIP ST



PE52 PHOTO-ELECTRIC CELL

GENERAL

The Mazda PE.52 is a vacuum Photo-Electric Cell with a Caesium-Oxygen-Silver Cathode Surface, having maximum sensitivity in the red and infrared region of the spectrum.

RATING

| Approximate Sensitivity (µA/lumen) | 20 + |
|--|------|
| Max. Working Voltage (volts) | 250 |
| Max. Dark Current (µA) | 0.1= |
| Max. Average Cathode current (µA) | 8 • |
| Maximum Peak Cathode Current (µA) | 25 |
| Max. Peak Cathode Current Density (µA/sq.cm) | 15 |
| Min. Insulation resistance between electrodes (Ma) | 1800 |

NOTES

- Measured at 0.05 lumen with 90 volts applied, and a 0.5 M n. series resistance: Lamp at colour temperature 2700°K,
- Measured at 90 volts, with 0.5 M. series resistance: zero illumination.
- Averaged over a period not greater than 30 secs.

All Maximum Ratings are absolute values not Design Centres.

INTER-ELECTRODE CAPACITANCE

Anode to Cathode (µµF)

1.9



EDISWAN

PE52 PHOTO-ELECTRIC CELL

| DIMENSIONS | | |
|---|--|-----------------------|
| Maximum Overall | | 78.0 |
| Maximum Seated H | ALCOHOL: NO MARKET DE PARTICIONAL DE LA COLUMNIA DEL LA COLUMNIA DE LA COLUMNIA DE LA COLUMNIA DEL COLUMNIA DEL COLUMNIA DE LA | 63.5 |
| Light Centre from | | 41.0 ± 2.5 |
| Maximum Bulb Dia | meter (mm) | 28.5 |
| Maximum Base Dia | meter (mm) | 32.0 |
| Cathode Length | (mm) | 22.0 |
| Effective Cathod | e Width (mm) | 21.5 |
| Projected Cathod | e Area (Sq.cm) | 4.7 |
| Approximate Nett Approximate pack | | 1 45 |
| VOIDIMENO DOCEMEN | N - Unrestricted | |
| | al (B.O.8) Direction | n of light |
| | Tanai - May - No. | of light |
| BASE - Mazda Oct | al (B.0.8) Direction | n of light |
| | Viewed from fr | of of of pins |
| BASE - Mazda Octo | al (B.0.8) Direction | oee end of pins |
| BASE - Mazda Octo | Viewed from for | oee end of pins |
| BASE - Mazda Octo | Viewed from for | oee end of pins |
| BASE - Mazda Octo CONNECTIONS Pin 1 Pin 2 \$ Pin 3 | Viewed from for | oee end of pins |
| BASE - Mazda Octo | Viewed from for Cathode Internal Connection | oee end of pins |
| CONNECTIONS Pin 1 Pin 2 \$ Pin 3 Pin 4 Pin 5 | Viewed from for Cathode Internal Connection | ree end of pins k i.c |



PHOTO ELECTRIC CELL

GENERAL

The Mazda PE54 is a Gas Filled Photo Electric Cell with a rectangular wire anode and a Caesium Antimony Cathode surface, having maximum sensitivity in the blue region of the spectrum.

RATING

| Average Overall Sensitivity (approx) µA/Lumen | 901 |
|---|-------|
| Average Primary Sensitivity (approx) (µA/Lumen) | 30\$ |
| Maximum Gas Amplification Factor | 61 |
| Maximum Working Voltage (volts) | 90 |
| Maximum Average Cathode Current (µA) | 66 |
| Maximum Peak Cathode Current (µA) | 20 |
| Maximum Peak Cathode Current | 20 |
| Density (µA/sq.cm) | 15 |
| Maximum Dark Current (µA) | 0.11 |
| Minimum Insulation Resistance | 0.11 |
| between Electrodes (Megohms) | 1,000 |

NOTES

- Measured at 0.085 lumens with lamp at colour temperature
 2,700 K and a cell series resistance of I Megohm.
- \$ The Primary Sensitivity is measured at an anode voltage of 25, at which ionisation has not taken place.
- ‡ Gas Amplification factor is a ratio of current at 90 volts to current at 25 volts under conditions of the overall sensitivity measurement.
- § Averaged over a period not greater than 30 seconds.
- \uparrow Measured at 90 volts and 1 Megohm series resistance, zero illumination.

All Maximum Ratings are absolute values, not design centres.



EDISWAN

PE54 PHOTO ELECTRIC CELL

INTER-ELECTRODE CAPACITANCES (pF)

| | 15 | |
|----------|---------|-----|
| Anode to | Cathode | 1.6 |

DIMENSIONS

| | 00.0 |
|---------------------------------|-------|
| Maximum Overall Length (mm) | 98.0 |
| Maximum Seated Height (mm) | 83.0 |
| Light Centre from Seat (mm) | 51-57 |
| Maximum Bulb Diameter (mm) | 26.5 |
| Maximum Base Diameter (mm) | 30.5 |
| Cathode Length (nominal) (mm) | 35.0 |
| Effective Cathode Width (mm) | 18.0 |
| Projected Cathode Area (sqcm.) | 6.3 |
| Approximate Nett Weight (ozs) | 11 |
| Approximate Packed Weight (ozs) | 21/2 |

MOUNTING POSITION—Unrestricted

BASE-British 4 Pin.



Viewed from free end of pins Direction of light

CONNECTIONS

| Pin I | Anode | |
|-------|---------|----|
| Pin 2 | Cathode | k |
| Pin 3 | No Pin | NP |
| Pin 4 | No Pln | NP |

December, 1961



PHOTO ELECTRIC CELL

GENERAL

The Ediswan PE55 is a Gas Filled Photo Electric Cell with a rectangular wire anode and Caesium-Oxygen-Silver Cathode Surface having Maximum sensitivity in the red and infra-red regions of the spectrum.

RATING

| Average Overall Sensitivity (approx) (µA/L | umen) | 901 |
|--|------------------|------|
| Average Primary Sensitivity (µA/lumen) | au ama mu | 20* |
| Maximum Gas Amplification Factor | Ag(max) | 9\$ |
| Maximum Working Voltage (volts) | 01 | 90 |
| Maximum Average Cathode Current (µA) | k(av)max | 61 |
| Maximum Peak Cathode Current (µA) | k(pk)max | 20 |
| Maximum Peak Cathode Current | 33 May 23 Common | |
| Density (µA/sq.cm) | | 15 |
| Maximum Dark Current (µA) | dark(max) | 0.18 |
| Minimum Insulation Resistance | TENDER CONTINUE | |
| between electrodes (megohms) | | 10 |

NOTES

- ‡ Measured at 0.085 lumens with lamp at colour temperature 2,700° K and a cell series resistance of 1 Megohm.
- \$ Gas Amplification factor is a ratio of current at 90 volts to current at 25 volts under the above conditions.
- § Measured at 90 volts and 1 Megohm series resistance; zero illumination.
- The Primary Sensitivity is measured at an anode voltage of 25, at which ionisation has not taken place.
- † Averaged over a period not greater than 30 seconds.

All Maximum Ratings are absolute values, not Design Centres.

PE55 PHOTO ELECTRIC CELL

| INTERELECTRODE CAPACIT | TANCE (pF) | |
|---------------------------|------------------|------|
| Anode to Cathode | c _{a-k} | 3.1 |
| DIMENSIONS | | |
| Maximum Overall Length | (mm) | 109 |
| Maximum Seated Height | (mm) | 94 |
| Light Centre from Seat | (mm) | 60+3 |
| Maximum Bulb Diameter | (mm) | 26.5 |
| Maximum Base Diameter | (mm) | 30.5 |
| Cathode Length | (mm) | 35 |
| Cathode Width | (mm) | 18 |
| Projected Cathode Area | (sq.cm) | 6.3 |
| Approximate Nett Weight | (ozs) | 11 |
| Approximate Packed Weight | (ozs) | 21/2 |

MOUNTING POSITION—Unrestricted

BASE-British 4 Pin.

Viewed from free end of pins



CAP-CT1

Direction of light

VALVE HOLDER-Ediswan Clix VH42/4

CONNECTIONS

| Pin 1 | Anode | a |
|---------|---------------|----|
| Pin 2 | No Connection | NC |
| Pin 3 | No Connection | NC |
| Pin 4 | No Connection | NC |
| Top Cap | Cathode | k |

December, 1961



EDISWAN



PHOTOMULTIPLIERS

I. GENERAL NOTES

A photomultiplier is a device containing a photo-sensitive cathode, a number of secondary cathodes with good secondary emission characteristics, and an anode. When light or similar radiation falls on the cathode, electrons are emitted, and these are accelerated by a suitable electric field to strike the first secondary cathode and produce a larger number of secondary electrons. This amplification is repeated at successive secondary cathodes and the current finally arriving at the anode is very many times larger than that leaving the cathode.

AEI photomultipliers use an antimony-caesium layer for the sensitive photosurface and also for the secondary emitting surfaces. This layer is sensitive in the visible and ultra-violet range of the spectrum. The electrodes are arranged in a compact manner and the focusing of the electron streams is accomplished by the electrostatic fields between the electrodes. (Secondary cathodes are sometimes known as dynodes.)

2. CONDITIONS OF USE

To obtain optimum amplification the voltage between the cathode and the first secondary cathode, and between all consecutively numbered pairs of secondary cathodes should be equal. This is most conveniently carried out by connecting a chain of equal valued resistors across a suitable power supply unit the junction of each pair of resistors being connected to the appropriate electrode. The current flowing through the resistor chain should preferably be at least 15 times the maximum current to be drawn from the photomultiplier.

The anode current can be read from a suitable meter in the anode circuit or the voltage developed across an anode load resistor can be amplified using a conventional electronic circuit.

It should be noted that a particularly stable power supply should be used for a photomultiplier, since for a given cathode illumination the output current varies very rapidly with changes in voltage: a change of 1% in power supply voltage produces a change of about 6.5% in anode current. A suitable supply unit specially designed for use with photomultipliers is the AEI R1184.

3. PRECAUTIONS

Provisions should be made to vary the supply voltage and/or the intensity of illumination over a wide range because of variations in characteristics between valves, see Para 4.

Continued

March, 1962

Page 1



PHOTOMULTIPLIERS

Precautions—continued

It is advisable to enclose these valves in an enclosure which is lightproof except for access to the cathode window area.

To obtain long life, stability and to keep dark current (i.e. the current that flows in the absence of any illumination) to a minimum, it may be advisable to run photomultipliers well below their maximum ratings.

These valves should never be exposed to bright light while potentials are being applied to the electrodes. Even when no potentials are applied, such exposure can cause a subsequent period of instability. It is therefore recommended that after any exposure to bright light a period of about 30 minutes under normal working conditions is allowed for the multiplier to become stable before starting to use it.

In some circumstances it may be found necessary to shield photomultipliers from strong electrostatic or magnetic fields.

4. CHARACTERISTICS

(a) Cathode Sensitivity

The cathode sensitivity of a photomultiplier is usually measured by applying a voltage of 30 to 100 volts between the cathode and all the other electrodes connected together. The value of the sensitivity is practically independent of voltage over this range.

The antimony-caesium photo-cathode has its maximum sensitivity at the blue end of the spectrum and it is not very sensitive to red light. The spectral response curves are shown for the individual types, they vary with the transmission characteristics of the envelope.

While the sensitivity does not vary greatly over the surface of the cathode, the anode current produced by one electron emitted from a point on the cathode varies very considerably with the position of this point. This means, of course, that when the cathode is illuminated by a beam of light of small cross-section, the overall sensitivity of the tube will vary very much with the location of the illuminating beam. If the distance along the cathode is measured from the end nearer the base, then the relative anode current is 20%, 90%, 100%, 90% and 20% at approximate distances of 2, 7, $12 \cdot 5$, 18 and 23 mm respectively and the corresponding figures across the cathode are 3, 4, $5 \cdot 5$, 7 and $8 \cdot 5$ mm. In measuring across the cathode from left to right it is assumed the grid is towards the observer with the base down and the cathode width is projected normal to the plane of the grid; measurements are made from the inside edge of the grid support wire.

Continued

March, 1962

Page 2

EDISWAN



PHOTOMULTIPLIERS

Characteristics-continued

(b) Anode Sensitivity

The average sensitivity figures quoted are very approximate. In the case of a photomultiplier with n stages and a given value of cathode photo-sensitivity, the anode sensitivity will vary as the nth power of the secondary emission coefficient of the secondary cathodes. Thus small changes in this coefficient will produce large changes in the sensitivity.

(c) Transit Time

The transit time of a photomultiplier is the time that elapses between the arrival of a pulse of light at the cathode and the arrival of a pulse of electrons at the anode. The spread in transit times is the increase in width of the output pulse over that of the pulse of light.

In this compact type of construction the transit time and the spread of transit times are very small. The response of the photomultiplier at frequencies of tens of megacycles per second is very little different from the static response.

(d) Signal to Noise Ratio

When ever a current flows in a photomultiplier it always contains a noise component. This mainly originates from the fact that the photo-electric emission from the cathode is not a continuous stream but consists of electrons whose emission varies in a random manner. At very low currents, the anode current, when examined by means of a C.R.O., can be seen to consist of individual pulses of varying amplitude; each pulse corresponding to the emission of an electron from the cathode. The variations in amplitude are caused by random variations in the multiplication factor at the individual secondary cathodes. This effect augments the original noise.

As mentioned overleaf, photomultipliers give a good signal to noise ratio compared with a photo-cell and amplifier for low levels of illumination. The value of the signal to noise ratio does not vary over a very wide range as the supply voltage is varied but it is preferable to work below the maximum rating for best performance in this respect: (If the overall voltage is reduced to a very low value (say below 20V per stage) the signal to noise ratio will rise due to poor efficiency of collection of electrons from the cathode.)

At very low light levels, the dark current becomes the limiting factor. It is possible to reduce the dark current very considerably by maintaining the photomultiplier at a low temperature e.g. partially surrounding it by solid carbon dioxide. This has the effect of reducing thermionic emission from the cathode and also reducing leakage current through semiconducting films on the insulators. Precautions must be taken to avoid electrical leakage due to moisture condensation.

Continued

March, 1962

Page 3



PHOTOMULTIPLIERS

5. APPLICATIONS

The main use of photomultipliers is for the detection and measurement of very low intensities of illumination. The main advantages of a photomultiplier over a simple photo-cell are:—

- (i) The high signal to noise ratio for small light levels.
- (ii) The high internal amplification.

A photomultiplier is usually preferred to a photo-cell and amplifier because of the ease with which high frequency and pulse outputs are obtained.

For these reasons photomultipliers are often used in scintillation counting of alpha and gamma rays in conjunction with a suitable phosphor.



NINE STAGE PHOTO-ELECTRIC MULTIPLIER

RATING

Maximum Supply Voltage Secondary Cathode K.10
to Cathode K.1 (D.C. or Peak A.C.) (Volts)

Maximum Potential Anode/Secondary Cathode
K.10 (Volts)

Maximum Anode Current (mA)
Cathode kl sensitivity (µA/lumen)
(Vkl = 0, all secondary cathodes joined at 100 volts)

† The sensitivity is on the basis of a lamp colour temperature of 2700°K and a light area of 5mm. x 20mm.

Note: It is recommended that the bleeder current in the potentiometer providing the secondary cathode voltages should be of the order of 10 times the maximum working current output of the tube.

GENERAL

The 27.M.1 is a high vacuum photo-cell with high response in the visible region. The photo electric current produced at the Cathode is multiplied many times by secondary emission occurring at successive cathodes within the valve.

It is capable of multiplying very small currents produced under weak illumination by an average value of one million times, when operated at 100 volts per stage.

The resultant output current is a linear function of the exciting illumination, under normal operating conditions. Since secondary emission occurs simultaneously, the frequency response is flat up to the frequencies at which transit time becomes a limiting factor.

Because of its great sensitivity, low noise level low dark current end freedom from distortion the 27.M.1 may be used for light operated relays, for film scanning, fascimile transmission and in scientific research involving low light levels; and in many applications its small size is an advantage.

It should be appreciated that with photo-electric multipliers, large variations in overall sensitivity may be present between individual valves.

Indicates a change

✓
Issue 1, Page 1



NINE STAGE PHOTO-ELECTRIC MULTIPLIER


TYPICAL OPERATION Voltage between anode and secondary 50 cathode kl0 (volts) Voltage difference per stage (volts) 100 1 0.25 Anode dark current (max)(µA) 20 Luminous sensitivity (amps/lumen) § 106 Current amplification The sensitivity is on the basis of a lamp colour temperature of 2700°K and a light area of 5mm x 20mm. Ratio of anode sensitivity/cathode sensitivity. With 100 volts between anode and secondary cathode k10. INTER-ELECTRODE CAPACITANCES. 6.7 Anode to all other electrodes (nuF) Anode to cathode klo (uuf) 4.1 DIMENSIONS. Maximum Overall Length (mm) 94.0 Maximum Bulb diameter (mm) 28.5 Maximum Base diameter (mm) 33.4 Light centre from seat (mm) 49.2 ± 2.4 Cathode Length (mm) 24 Cathode Width (mm) BASING. - Special 11 pin Sub Magnal CONNECTIONS. Pin 1 Cathode 2 Pin 2 Cathode 3 Pin 3 Cathode 4 Pin 4 Cathode 5 Pin 5 Cathode 6 Pin 6 Cathode 7 Pin 7 Cathode 8 Pin 8 Cathode 9 Pin 9 Cathode 10 Direction of light. Pin 10 Anode Pin 11 Cathode 1 Viewed from free end of pins. Note: Pin 1 is taken as the first pin to the left of the keyway. Similarly pin 11 which is connected to the photo emitting cathode kl is taken as the first pin to the right of the

Indicates a change
Issue 1, Page 2

keyway.



NINE STAGE PHOTO-ELECTRIC MULTIPLIER




December, 1961



NINE STAGE PHOTO-ELECTRIC MULTIPLIER

AVERAGE CHARACTERISTIC CURVES

ANODE CURRENT IN MA




December, 1961



27MI NINE STAGE PHOTO-ELECTRIC MULTIPLIER

AVERAGE CHARACTERISTIC CURVES



December, 1961

AVI TO DESCRIPTION OF THE PARTY OF THE PARTY



NINE STAGE PHOTO-ELECTRIC MULTIPLIER

GENERAL

The 27.M.2 is a high vacuum photo-cell with high response in the visible region. The photo electric current produced at the Cathode is multiplied many times by secondary emission occuring at successive cathodes within the valve.

It is capable of multiplying very small currents produced under weak illumination by an average value of 250,000 times, when operated at 80 volts per stage.

The resultant output current is a linear function of the exciting illumination, under normal operating conditions. Since secondary emission occurs simultaneously, the frequency response is flat up to the frequencies at which transit time becomes a limiting factor.

Because of its sensitivity, low noise level, low dark current and freedom from distortion the 27.M.2 may be used for light operated relays and in experiments involving low light levels and in many applications where its small size is an advantage.

It should be appreciated that with photo-electric multipliers large variations in overall sensitivity may be present between individual valves

RATING

Maximum Anode Supply Voltage (volts) 900
Maximum Potential Anode/Secondary cathode k10 100
(volts) 100
Maximum Anode Current (mA) 1.0
Cathode k1 sensitivity (µA lumen) 10

- · With respect to cathode.
- The sensitivity is on the basis of a lamp colour temperature of 2700° K and a light area of 4mm x 20mm. Vkl = 0, all secondary cathodes joined at 100 Volts.

NOTES

- It is recommended that the bleeder current in the potentiometer providing the secondary cathode voltages should be of the order of 10 times the maximum working current output of the tube.
- (2) The 27.M.2 is similar to the 27.M.1 except for the wider tolerance on the anode dark current which necessitates a lower anode supply voltage.

December, 1961



NINE STAGE PHOTO-ELECTRIC MULTIPLIER

TYPICAL OPERATION

Voltage between anode and secondary eathode k10 (volts) 50
Voltage Difference per stage (volts) 80
Anode dark current (max) (µA) 0.25
Luminous sensitivity (amps/lumen) 2 2
Current amplification †250x10³

- . With 80 volts between anode and secondary cathode K10.
- † Ratio of anode sensitivity/cathode sensitivity.
- The sensitivity is on the basis of a lamp colour temperature of 2700°K and a light area of 4.0mm x 20mm.

NOTE

By joining together Pins 8, 9 and 10 the cell may be used as a 7 stage multiplier. Volts per stage not to exceed 80 volts

By joining together pins 6, 7, 8, 9 and 10 the cell may be used as a 5 stage multiplier. Volts per stage not to exceed 80 volts.

INTER-ELECTRODE CAPACITANCES

Anode to all other electrodes (ppF) 6.7 Anode to cathode k10 (ppF) 4.1

DIMENSIONS

| Maximum Overall length (mm) | 94.0 |
|-----------------------------|----------|
| Maximum Seated Height (mm) | 80.0 |
| Maximum Bulb Diameter (mm) | 28.5 |
| | |
| Maximum Base Diameter (mm) | 33.4 |
| Light centre from seat (mm) | 49.212.4 |
| Cathode Length (mm) | 24 |
| | E/T |
| Cathode Width (mm) | 8 |

BASING Special 11 pin Sub Magnal


| Pin 1 | Cathode | 2 | THE WINDOWS AND THE PARTY OF THE |
|--------|---------|----|----------------------------------|
| Pin 2 | Cathode | 3 | (5 . 6 . 7) |
| Pin 3 | Cathode | 4 | 400007 |
| Pin 4 | Cathode | 5 | (40 08) |
| Pin 5 | Cathode | 6 | (30 00) |
| Pin 6 | Cathode | 7 | 20000 |
| Pin 7 | Cathode | 8 | 6000 |
| Pin 8 | Cathode | 9 | |
| Pin 9 | Cathode | 10 | |
| Pin 10 | Anode | | |
| Pin 11 | Cathode | 1 | Viewed from free end of pins. |

NOTE: Pin 1 is taken as the first pin to the left of the keyway. Similarly pin 11 which is connected to the photo emitting cathode k1 is taken as the first pin to the right of the keyway.

December, 1961



NINE STAGE PHOTO-ELECTRIC MULTIPLIER TENTATIVE CHARACTERISTIC CURVES D.C. OPERATION




December, 1961



27M2 NINE STAGE PHOTO-ELECTRIC MULTIPLIER


TENTATIVE CHARACTERISTIC CURVES

ANODE CURRENT IN mA






27M2 NINE STAGE PHOTO-ELECTRIC MULTIPLIER





27M2 NINE STAGE PHOTO-ELECTRIC MULTIPLIER





NINE STAGE PHOTO-ELECTRIC MULTIPLIER (U.V. SENSITIVE)

RATING.

Vaximum Supply voltage Secondary K10 to Cathode
K1, (DC or Feak AC) volts
Vaximum Potential Anode/Secondary cathode k10 (volts)
Vaximum Anode Current (mA)
Cathode k1 sensitivity (µA/lumen)
(Vk1 = 0, all secondary cathodes joined at 100 volts)

 The Sensitivity is on the basis of a lamp colour temperature of 2700°K and a light area of 4mm x 20mm.

Note: It is recommended that the bleeder current in the potentiometer providing the secondary cathode voltages should be of the order of 15 times the maximum working current output of the tube.

GENERAL.

The 27M3 is a high vacuum photo-cell with high response in the visible and ultra-violet region. The photo electric current produced at the Cathode is multiplied many times by secondary emission occuring at successive cathodes within the valve.

It is capable of multiplying very small currents produced under weak illumination by an average value of one million times, when operated at 100 volts per stage.

The resultant output current is a linear function of the exciting illumination, under normal operating conditions. Since secondary emission occurs simultaneously, the frequency response is flat up to the frequencies at which transit time becomes a limiting factor.

Fecause of its great sensitivity, low noise level, low dark current and freedom from distortion the 27M3 may be used for light operated relays, for film scanning, facsimile transmission and in scientific research involving low light levels: and in many applications its small size is an advantage.

It should be appreciated that with photo-electric multipliers, large variations in overall sensitivity may be present between individual valves.





NINE STAGE PHOTO-ELECTRIC MULTIPLIER (U.V. SENSITIVE)


| ondary cathode (volts) (volts) |
|---|
| (volts) q 0.25 q 0.25 q 0.25 q 106 the basis of a lamp 2700 °K and a light ivity/cathode sensitivity. n anode and secondary ins 8,9 and 10, the cell age multiplier. Volts ed 100 volts. (upf) 6.7 |
| 2700 °K and a light ivity/cathode sensitivity. n anode and secondary ins 8,9 and 10, the cell age multiplier. Volts ed 100 volts. ins 6, 7, 8, 9, and 10 the 5, stage multiplier. Volts ed 100 volts. |
| n anode and secondary ins 8,9 and 10, the cell age multiplier. Volts ed 100 volts. ins 6, 7, 8, 9, and 10 the 5 stage multiplier. Volts ed 100 volts. |
| ins 8,9 and 10, the cell age multiplier. Volts ed 100 volts. ins 6, 7, 8, 9, and 10 the 5 stage multiplier. Volts ed 100 volts. |
| age multiplier. Volts ed 100 volts. ins 6, 7, 8, 9, and 10 the 5 stage multiplier. Volts ed 100 volts. |
| 5; stage multiplier. Volts ed 100 volts. |
| |
| |
| |
| |
| 99.0 28.5 33.4 49.2±2.4 24 |
| Magnal. |
| |
| Direction of light. |
| |

December, 1961 Issue 1, Page 2



27M3

NINE STAGE PHOTO-ELECTRIC MULTIPLIER CHARACTERISTIC CURVE (D.C. OPERATION)




December, 1961



27M3 NINE STAGE PHOTO-ELECTRIC MULTIPLIER

TENTATIVE CHARACTERISTIC CURVE





NINE STAGE PHOTO-ELECTRIC MULTIPLIER

GENERAL

The 27M12 is a nine stage photo multiplier cell for use in aircraft, being especially resistant to shock and vibration. It has a blue sensitive caesium antimony coated cathode and is fitted with flying leads.

RATING

| Maximum Dynode k10 to Cathode Voltage (DC or | | Television and | 1971 |
|--|------------|----------------------------------|------|
| Pk AC) | (volts) | Vk10-k1(max | 585 |
| Maximum Anode to Dynode k10 Voltage | (volts) | Va-k10(max) | 65 |
| Maximum Anode Current | (mA) | a(max) | 1.0 |
| Average Cathode Sensitivity | (μA/lumen) | Sk1(av) | 20* |
| Maximum Ambient Working Temperature | | a spile it sage i Događaja po | 70 |

^{*} Vk1 = 0, all Dynodes joined at 100 volts. Colour temperature of lamp 2,700°K.

DIMENSIONS

| Maximum Overall Length | (mm) | 77 |
|---------------------------------|-------|------|
| Nominal Seated Height | (mm) | 63 |
| Light Centre from Top (nominal) | (mm) | 27.8 |
| Maximum Bulb Diameter | (mm) | 29.5 |
| Cathode Length | (mm) | 24 |
| Cathode Width | (mm) | 8 |
| Approximate Nett Weight | (ozs) | 11 |
| Approximate Packed Weight | (ozs) | 4 |

December, 1961

27M12

NINE STAGE PHOTO-ELECTRIC MULTIPLIER

MOUNTING POSITION Unrestricted

| TYPICAL OPERATION | | |
|--|-------------------|----------|
| Anode to Dynode k10 Voltage | (volts) Va-k10 | 65 |
| Voltage per stage | (volts) | 65 |
| Anode Dark Current from Dynode k10(max) | (μΑ) | 0.1** |
| Luminous Sensitivity from Dynode k10 | (A/lumen) | 0.4‡ |
| Average Current Amplification | About to the real | 20,000‡‡ |

- **With Anode to Dynode k10 and Dynode to Dynode Voltages 100 volts per stage.
- Measured with a lamp colour temperature 2,700° K and a light area of 5 x 20 mm.
- tt Ratio of k10 sensitivity to cathode sensitivity.

NOTES.—The bleed current in the potentiometer chain should be at least ten times the maximum output current.

December, 1961


Issue 1, Page 2



27M12

NINE STAGE PHOTO-ELECTRIC MULTIPLIER

BASE-Flying Leads.



Direction of Light Viewed from free end

CONNECTIONS


| Pin 1 | Secondary Cathode 2 | k2 |
|--------|--------------------------|------|
| Pin 2 | Secondary Cathode 3 | k3 |
| Pin 3 | Secondary Cathode 4 | k4 |
| Pin 4 | Secondary Cathode 5 | k5 |
| Pin 5 | Secondary Cathode 6 | k6 |
| Pin 6 | Secondary Cathode 7 | k7 |
| Pin 7 | Secondary Cathode 8 | k8 |
| Pin 8 | Secondary Cathode 9 | k9 |
| Pin 9 | Secondary Cathode 10 | k10 |
| Pin 10 | Anode | a |
| Pin 11 | Photo cathode, Shield | k1,s |

may of profession his his

December, 1961

Issue 1, Page 3

27M12 NINE STAGE PHOTO-ELECTRIC MULTIPLIER



6-27 MI2-90-1


Leads on 17,2 mm P.C.D.

All dimensions in mm.



27M12 NINE STAGE PHOTO-ELECTRIC MULTIPLIER

AVERAGE CHARACTERISTIC CURVE: S/λ For equal values of radiant flux at all wavelengths.



December, 1961


Issue 1, Page 5



-

RESIDENCE DISTRIBUTE OF THE STATE OF THE

THE STATE STREET STATE OF STATE AND ADDRESS OF THE STATE OF THE STATE





27M12A

NINE STAGE PHOTOMULTIPLIER

GENERAL

The 27M12A is an improved version of the 27M12, having improved vibration performance. It is a nine stage photomultiplier for use in Aircraft, being especially resistant to shock and vibration. It has a blue sensitive caesium antimony coated cathode and is fitted with flying leads.

| Vk10-k1(max) | 585 | V |
|--------------|-----|---|
| | 65 | V |
| la(max) | 1.0 | mA |
| Sk1(av) | 20* | ιA/L |
| | | V _{a-k10(max)} 65 I _{a(max)} 1.0 |

^{*} $V_{k1} = 0$, all dynodes joined at 100 volts. Colour temperature of tungsten lamp = 2,700°K.

DIMENSIONS

| Maximum Overall Length (excluding leads) | 77 | mm |
|--|------|-----|
| Nominal Seated Height | 63 | mm |
| Light Centre from Top (nominal) | 27-8 | mm |
| Maximum Bulb Diameter | 29.5 | mm |
| Cathode Length | 24 | mm |
| Cathode Width | 8 | mm |
| Approximate Nett Weight | 11 | ozs |
| Approximate Packed Weight | 4 | ozs |

MOUNTING POSITION—Unrestricted



27M12A

NINE STAGE PHOTOMULTIPLIER

TYPICAL OPERATION


| Anode/Dynode k10 Voltage | Va-k10 | 65 | ٧ |
|--|--------------------|----------|-----|
| Voltage per stage | | 65 | V |
| Anode Dark Current from Dyr k10 (max) | ode la(dark)max | 0.1** | μΑ |
| Luminous Sensitivity from Dyn | ode k10 | 0.4‡ | A/L |
| Average Current Amplification | ı | 20,000† | |
| Luminous Sensitivity from Ano | de | 0.6‡ | A/L |
| Average Current Amplification | 1 | 30,000†† | |

- ** With Anode/Dynode k10 and Dynode/Dynode voltages 100 volts per stage.
- $\ ^{\updownarrow}$ Measured with a tungsten lamp colour temperature of 2,700°K and a light area of 5 \times 20mm.
- † Ratio of k10 sensitivity to Cathode sensitivity.
- †† Ratio of anode sensitivity to Cathode sensitivity.

NOTES

The bleed current in the potentiometer chain should be at least ten times the maximum output current.

BASE—Flying Leads



DIRECTION OF LIGHT

Viewed from free end.

December, 1961

ADVANCE DATA, Page 2



27M12A

NINE STAGE PHOTOMULTIPLIER

| CONNECTION | 45 | |
|------------|----------------------|-------|
| Pin 1 | Secondary Cathode 2 | k2 |
| Pin 2 | Secondary Cathode 3 | k3 |
| Pin 3 | Secondary Cathode 4 | k4 |
| Pin 4 | Secondary Cathode 5 | k5 |
| Pin 5 | Secondary Cathode 6 | k6 |
| Pin 6 | Secondary Cathode 7 | k7 |
| Pin 7 | Secondary Cathode 8 | k8 |
| Pin 8 | Secondary Cathode 9 | k9 |
| Pin 9 | Secondary Cathode 10 | k10 |
| Pin 10 | Anode | a |
| Pin 11 | Photo Cathode Shield | 1/1 e |

(200

be right inveloped benishment have read-



27MI3

SEVEN STAGE PHOTO-MULTIPLIER

GENERAL

The 27M13 is a seven stage Photo-multiplier having a blue sensitive cathode and twin anodes. Its sensitivity in typical operation is 2.5 amps/lumen. The cathode surface is of Caesium Antimony.

RATING

| Supply Voltage, Secondary Cathode k8 to photo-catho k1 (DC or Peak AC) (max) | | Vk8-k1 (max | 900 | |
|--|--|-----------------|--------|---|
| Supply Voltage, Anodes to Secondary Cathode k8 (max | x) (volts) | Va-k8(max) | 125 | |
| Maximum Anode Current | (mA) | la(max) | 1.0 | |
| Photo Cathode Sensitivity (average) | (μA/lumen) | . , | 20.0* | + |
| * All secondary cathodes and of 100 volts to photo-catho 5.0 mm × 20 mm and a colour temperature of 2,70 | anodes joined ode, measured tungsten filam | l, and at a pot | t area | |
| All Maximum ratings are Abs | olute values n | ot Design Ce | ntres. | |

DIMENSIONS

| Maximum Overall Length | (mm) | 94 |
|---------------------------|-------|------------|
| Maximum Seated Height | (mm) | 80 |
| Light Centre to Seat | (mm) | 49·2 ± 2·4 |
| Maximum Bulb Diameter | (mm) | 29.5 |
| Maximum Base Diameter | (mm) | 33-4 |
| Cathode Length | (mm) | 24 |
| Cathode Width | (mm) | 8 |
| Approximate Nett Weight | (ozs) | 13 |
| Approximate Packed Weight | (ozs) | 43 |

MOUNTING POSITION—Unrestricted

Indicates a change

✓
Issue 1, Page 1

27MI3

SEVEN STAGE PHOTO-MULTIPLIER

TYPICAL OPERATION

| Voltage between Anodes and Secondary Cathode k8 | (volts) | Va-k8 | 50 |
|--|-----------|--------------------|--------------------|
| Voltage per Stage | (volts) | V_{stage} | 125 |
| Maximum Anode Dark Current (per Anode) | (μA) | | 0-25* |
| Luminous Sensitivity (per Anode) | (A/lumen) | | 2.5↑ ← |
| Average Current Amplification (per Anode) | | | 125,000‡† ← |

- * With 125 volts between Anode and Secondary Cathode k8
- † With a colour temperature of 2,700°K and a light area of 5.0 mm \times 20 mm.
- † Ratio of anode to photo-cathode sensitivities.

NOTE.—The Secondary Cathode voltage potentiometer should have a bleed current of at least ten times the maximum output current.

BASE—B11A (11 pin sub-Magnal)

Viewed from free end of pins



Direction of Light

December, 1961

Indicates a change

←
Issue 1, Page 2




27MI3 SEVEN STAGE PHOTO-MULTIPLIER

CONNECTIONS

| Pin 1 | Secondary Cathode 2 | k2 | |
|--------|---------------------|----|---|
| Pin 2 | Secondary Cathode 3 | k3 | |
| Pin 3 | Secondary Cathode 4 | k4 | |
| Pin 4 | Secondary Cathode 5 | k5 | |
| Pin 5 | Secondary Cathode 6 | k6 | |
| Pin 6 | Secondary Cathode 7 | k7 | |
| Pin 7 | Secondary Cathode 8 | k8 | |
| Pin 8 | Anode 1 | a1 | |
| Pin 9 | Anode 2 | a2 | |
| Pin 10 | Internal Connection | IC | + |
| Pin 11 | Photo-cathode | k1 | |
| | | | |



27M13
SEVEN STAGE PHOTO-MULTIPLIER




37441-00-c

All dimensions in mm.



27M13 SEVEN STAGE PHOTO-MULTIPLIER.

AVERAGE CHARACTERISTIC CURVE: S/\(\lambda\) Spectral Response of Photo-Cathode for equal values of Radiant Flux at all Wavelengths.




December, 1961

Issue 1, Page 5

27MI3 SEVEN STAGE PHOTO-MULTIPLIER

CHARACTERISTIC CURVES (D.C. OPERATION)
Sensitivity and current amplification for each anode



December, 1961

Issue 1, Page 6

Cathode Ray Tubes



Details of Cathode-ray Tube Phosphors

| Phosphor | Persistence* | Kelly Chart Colour | | Tourisant |
|----------|-------------------------------|-------------------------|----------------------|--|
| Number | (Approx) I Foot Lambert to I% | Fluorescence | Phosphores- cence | Typical use |
| TI | 60ms | Yellowish Green | Yellowish Green | General oscillography and photography |
| Т2 | 5 to 50s | Green | Green | Visual and photography |
| Т3 | 50μs† | Purplish Blue | Purplish Blue | Oscillography and photography |
| T4 | _ | _ | _ | Television |
| T5 | 10 <i>μ</i> s | Green | Green | Flying spot scanning |
| Т6 | 50s‡ | Varies blue to white | Yellowish Green | Radar and oscillography |
| T7 | 100 to 300s | Orange | Orange | Radar display |
| Т8 | 2 to 10s | Yellow | Yellow | General oscillography |
| Т9 | 100s | Orange | Orange | Large screen oscillography |
| TIO | _ | Yellow Green | Yellow Green | Visual and photography |
| TII | 30ms | Orange | Orange | Anti Flicker display |
| TI2 | 100ms | Orange | Orange | Anti Flicker display |

^{*} Persistence is defined as the time taken from the cessation of continuous excitation for the luminance to decay from 1 Foot Lambert to approximately 1% of that value.


Most AEI cathode-ray tubes can be supplied with any one of the screen phosphors described above but it should be noted that, for various reasons, not all tubes are available with all phosphors listed. Information on specific cases is available on request. Certain tubes with phosphors other than those listed can be supplied to special order. When ordering, the type of screen phosphor required should be indicated by adding the appropriate suffix to the number of the cathode-ray tube, e.g. 31E12/T6.

August, 1962

Page 1, Issue 2


[†] Time to 10%.

[‡] Yellow component.






RELATIVE SPECTRAL ENERGY DISTRIBUTION OF TYPICAL CRT SCREEN



August, 1962


PERSISTENCE CHARACTERISTICS of typical CRT screen

(Characteristics are substantially independent of operating conditions.)






RELATIVE SPECTRAL ENERGY DISTRIBUTION OF TYPICAL CRT SCREEN




August, 1962

PERSISTENCE CHARACTERISTICS of typical CRT screen. **Excitation**—Continuous, focused, 405 line, interlaced raster, 100 mm \times 100 mm Final Anode Voltage—5 kV.






RELATIVE SPECTRAL ENERGY DISTRIBUTION OF TYPICAL CRT SCREEN



August, 1962


Page 1, Issue 2

PERSISTENCE CHARACTERISTICS (Range) of typical CRT screen.






RELATIVE SPECTRAL ENERGY DISTRIBUTION OF TYPICAL CRT SCREEN




August, 1962



PERSISTENCE CHARACTERISTICS (Range) of typical CRT screen.



RELATIVE SPECTRAL ENERGY DISTRIBUTION OF TYPICAL CRT SCREEN




PERSISTENCE CHARACTERISTICS (of yellow component).


Excitation—Continuous, focused, 405 line, interlaced raster, 150 mm × 150 mm

Final Anode Voltage—10 kV.





RELATIVE SPECTRAL ENERGY DISTRIBUTION OF TYPICAL CRT SCREEN




August, 1962

Page 1, Issue 2

PERSISTENCE CHARACTERISTICS of typical aluminised CRT screen. **Excitation**—Continuous, focused, 405 line, interlaced raster, 150 mm \times 150 mm **Final Anode Voltage**—10 kV


Note—This screen is liable to burn if a stationary or slow-moving spot is used even with low values of mean current.






PERSISTENCE CHARACTERISTICS of typical aluminised CRT screen. Excitation—Continuous, focused, 405 line, interlaced raster, 150 mm × 150 mm Initial Luminance—1 Foot Lambert.

Note—This screen is liable to burn if a stationary or slow-moving spot is used even with low values of mean current.



August, 1962


Page 3, Issue 1





Reference Line Gauge No. 6

For C.R. Tubes having a Nominal Neck Diameter of 34.5 mm.



IO:I ENLARGMENT OF MOUTH FORM

All dimensions in mm. unless otherwise stated.

NOTE 1-Deflector Yoke Design

The internal dimensions of the yoke must never be smaller than the maximum internal dimensions of the gauge.

NOTE 2—Tolerances

The tolerances shown are initial manufacturing limits. The figures given below are the maximum allowable limits for wear:


(A) + 0.059

(B) + 0.075

Reference Line Gauge No. 7 (AEI



For C.R. Tubes having a Nominal Neck Diameter of 34-5 mm. Deflection Angle 67-5° approx. (Picture Diagonal).



All dimensions in mm. unless otherwise stated.

NOTE 1-Deflector Yoke Design

The inner surface of the yoke must not extend into the shaded region and the internal dimensions of the yoke must never be smaller than the maximum internal dimensions of the gauge.

NOTE 2—Tolerances

The tolerances shown are initial manufacturing limits. The figures given below are the maximum allowable limits for wear:


(A) + 0.059


(B) + 0.075



Reference Line Gauge No. 12

For C.R. Tubes having a Nominal Neck Diameter of 36.5mm.





All dimensions in mm.


NOTE 1-Deflector Yoke Design

The inner surface of the yoke must not extend into the shaded region and the internal dimensions of the yoke must never be smaller than the maximum internal dimensions of the gauge.

Reference Line Gauge No. 13 (AEI



For C.R. Tubes having a Nominal Neck Diameter of 36.5 mm




NOTE 1—Deflector Yoke Design
The inner surface of the yoke must not extend into the shaded region and the internal dimensions of the yoke must never be smaller than the maximum internal dimensions of the gauge.



Reference Line Gauge No. 16

For C.R. Tubes having a nominal Neck Diameter of 28.5 mm. Deflection Angle 110° approx. (Picture Diagonal)



NOTE 1.—Deflector Yoke Design.

The inner surface of the yoke must not extend into the shaded region and the internal dimensions of the yoke must never be smaller than the maximum internal dimensions of the gauge.

NOTE 2.—Reference Line.

The Reference Line is determined by the plane "A-A" when the gauge is seated against the funnel.

aperge i Alemania i mastra properti e i se tradicioni. Per per all'area e la compania di l



30BI

CATHODE RAY TUBE—ALL ELECTROSTATIC 3½" Dia. Indirectly heated high grade precision measurement cathode ray tube with a polished flat face

| RATING | | | |
|---|-----------|--------------|-----------|
| Heater Voltage (volts) | v_h | | 4.0 |
| Heater Current (amps) | Ih | | 0.72 |
| Maximum 1st Anode Voltage (volts) | Val(m | 120 | 2,500 |
| Maximum 2nd Anode Voltage (volts) | Va2(m | | 1,000 |
| Maximum 3rd Anode Voltage (volta) | Va3(m | ex) | 6,000 |
| Average Sensitivity of "X" Plates (mm/V) | "ao(m | ex) | |
| Average Sensitivity of "Y" Plates (max/V) | | | # 420/V |
| (mag/ v) | | | ⇒ 840/∇ |
| Where "V" denotes the voltage | on the | 3rd Anode | 9 |
| and bulb coating. | | | |
| INTER-ELECTRODE CAPACITANCES | | | |
| A Deflecting Plate/All other electrodes | (nur) | Cxl,all | 15.0 |
| X2 Deflecting Plate/All other electrodes | (uuF) | Cz2,all | 15.0 |
| Yl Deflecting Plate/All other electrodes | (mF) | Cyl,ell | 14.5 |
| | (uuF) | | 14.5 |
| X Deflecting Plate/Yl Deflecting Plate | (uuF) | Cy2,all | 1.5 |
| XI Deflecting Plate/Y2 Deflecting Plate | | Cxl,yl | |
| X2 Deflecting Plate/Y1 Deflecting Plate | (mr) | Cx1,y2 | 1.0 |
| As Deliecting Plate/II Dellecting Plate | (unf) | Cx2,y1 | 1.0 |
| X2 Deflecting Plate/Y2 Deflecting Plate Control Grid (Wehnelt)/All other electrods | (unit) | C_12, y2 | 1.25 |
| (uuF) | | Cg,all | 9.5 |
| DIMENSIONS | | | |
| Maximum Overall Length (mm) | | | 340 |
| Maximum Diameter (mm) | | | 90 |
| Nominal Screen Diameter (inches) | | | 90 3 3 |
| Approximate Nett Weight (ozs) | | | ອາ |
| Approximate Packed Weight (1bs) | | | 21 103 |
| 7,200,000 | | | 104 |
| NOTES | | | |
| For general measurement work the 30.B.1/Pl | is re | comended. | |
| This has a screen with a medium persistend special applications, however, the tube meany of the standard phosphors described or | e gree | phosphor | . For |
| to this section. | . 0.00 11 | 102 0446 101 | A Lega |
| Final Anode and Bulb coating are brought of order to anable a finer spot or a higher we obtained by increasing the Final Anode vol- set for the let Anode Voltage. | riting | anged to | ha |
| In use the 3rd Anode and bulb coating are | normall | y joined. | |
| | | | |

Indicates a change←

CATHODE RAY TUBE—ALL ELECTROSTATIC $3\frac{1}{2}''$ Dia. Indirectly heated high grade precision measurement cathode ray tube with a polished flat face

| PICAL OPERATION | | | | | |
|--|-------------------------------------|-------|-------|----------------|---|
| d Anode Voltage (volta | | 2,000 | 3,000 | 5,000 | |
| d Anode Voltage - appro | | 360 | 540 | 900 | |
| imate, for focus (volta | | | 2,000 | 2,000 | |
| erage Bias on Control (for Cut-off of Beam Cur | Fid | 2,000 | 2,000 | 2,000 | |
| (volts) | .V. | - 60 | -60 | -60 | |
| erage Working Bias for Beam (volts) | 20114 | - 47 | -47 | -47 | |
| proximate Sansitivity | of | | | | |
| "X" Plates (wm/V) | | 0.21 | 0.14 | 0.084 | |
| proximate Sensitivity ("Y" Plates (mm/V) | of . | 0.42 | 0.28 | 0.168 | |
| , , , | | | | | |
| SE 12 Contact Key Bar | se (BS.448) | | | | |
| HEW OF EDE | EBID | 1 | KEY | / | |
| HEW OF FRE | SEND | . 1 | 國 | | |
| | | | No. | // | |
| | | | 2 1 | X | |
| | | //11 | 1 9 | 1/5 | - |
| | | +10 | | | |
| | | T10 | 1 | 37 | |
| | | 1-19 | ٨ | all | |
| | | 8/ | /:\ s | | - |
| | | 1 70. | 7/1/0 | X/ | |
| PERMISSIBLE ANGUI | | X | 1/i/9 | / X | |
| VARIATION OF MOUNT | 8 ± 10° | | THE | | |
| | | | TH | \ | |
| | | / | L 1 1 | 1 | |
| | | | 1 | | |
| NNEXTONS | | | | | |
| n 1 Contro | ol Grid | | | 6 | |
| n 2 Catho | | | | k | |
| n 3 Heater | r | | | h | |
| n 4 Heate: | | | | h | |
| n 5 Anoda | | | | al | |
| n 6 Anode | | | | a2 | |
| | al Coating | | | ¥12 | |
| | sting Plate Y2 | | | A5 | |
| | ting Plate X3 | | | 72 | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| n 11 Deflec | 3 sting Plate A sting Plate A | | | a3 xl yl | |


Indicates a change

←
Issue 1, Page 2



30BI

CATHODE RAY TUBE—ALL ELECTROSTATIC $3\frac{1}{2}$ " Dia. Indirectly heated high grade precision measurement cathode ray tube with a polished flat face



All dimensions in mm.

I MIT



District Floring A chickely contained



$5\frac{1}{2}$ " MEASUREMENT CATHODE RAY TUBE ELECTROSTATIC FOCUS AND DEFLECTION

GENERAL

The 30C2 is a precision Measurement Cathode Ray Tube having a $5\frac{1}{2}^{\#}$ diameter polished flat face.

| R | A | т | IN | 10 | G |
|---|---|---|----|----|---|
| | _ | | и. | ъ, | • |

| Heater Voltage (volts) | Vh | 4.0 |
|---------------------------------------|----------|---------|
| Heater Current (amps) | lh. | 0.72 |
| Maximum 1st Anode Voltage (volts) | Va1(max) | 2,500 |
| Maximum 2nd Anode Voltage (volts) | Va2(max) | 1,000 |
| Maximum 3rd Anode Voltage (volts) | Va3(max) | 6,000 |
| Average Sensitivity of "X" Plates (mr | n/V) | 600/V* |
| Average Sensitivity of "Y" Plates (mr | n/V) | 1100/V* |

^{*} Where "V" denotes the voltage on the 3rd Anode and bulb coating.

INTER-ELECTRODE CAPACITANCES (pF)

| X1 Plate/All other electrodes | cx1-all | 15.0 |
|-------------------------------|---------|------|
| X2 Plate/All other electrodes | cx2-all | 15.0 |
| Y1 Plate/All other electrodes | cy1-all | 14.5 |
| Y2 Plate/All other electrodes | cy2-all | 14.5 |
| X1 Plate/Y1 Plate | cx1-y1 | 1.5 |
| X1 Plate/Y2 Plate | cx1-y2 | 1.0 |
| X2 Plate/Y1 Plate | cx2-y1 | 1.0 |
| X2 Plate/Y2 Plate | cx2-y2 | 1.25 |
| Grid/All other electrodes | cg-all | 9.5 |
| | | |

DIMENSIONS

| Maximum Overall Length | (mm) | 430 |
|---------------------------|-------|------|
| Maximum Diameter | (mm) | 142 |
| Nominal Screen Diameter | (ins) | 51/2 |
| Approximate Nett Weight | (ozs) | 30 |
| Approximate Packed Weight | (lbs) | 111 |

December, 1961 Issue 1, Page 1

5½" MEASUREMENT CATHODE RAY TUBE ELECTROSTATIC FOCUS AND DEFLECTION

NOTES

For general measurement work the 30C2/T1 is recommended. This has a screen with a medium persistence green phosphor. For special applications, however, the tube may be supplied with any of the standard phosphors described on the Introductory Page to this Section, except T7.

The Final Anode and the Bulb coating are brought out separately from the First Anode in order that a finer spot or a high writing speed may be obtained by increasing the Final Anode Voltage above the limit set for the First Anode Voltage.

In use the Third Anode and Bulb coating are normally joined.

All Maximum Ratings are Absolute Values, not Design Centres.

| TYPICAL OPERATION | | | |
|---|------------------|-------|-------|
| 3rd Anode Voltage (volts) | V _a 3 | 2,000 | 5,000 |
| 2nd Anode Voltage for focus (approx.) (volts) | V _{a2} | 440 | 800 |
| 1st Anode Voltage (volts) | Va1 | 2,000 | 2,000 |
| Average Bias on Control Grid for Cut-off of Beam Current (volts) | Vg | 60 | 60 |
| Average Working Bias for $20\mu A$ Beam (volts) | | —33 | —33 |
| Approximate Sensitivity of "X" Plates (mm/V) | | 0.30 | 0.12 |
| Approximate Sensitivity of "Y" Plates (mm/V) | | 0.57 | 0.23 |
| | | | |



5½" MEASUREMENT CATHODE RAY TUBE ELECTROSTATIC FOCUS AND DEFLECTION

BASE-B12D

* Permissible angular variation of mounts $\pm 10^{\circ}$




View from free end of base.

CONNECTIONS

| Control Grid | g |
|---------------------|--|
| Cathode | k |
| Heater | h |
| Heater | h |
| Anode 1 | a1 |
| Anode 2 | a2 |
| Internal Coating | m |
| Deflecting Plate Y2 | y2 |
| Deflecting Plate X2 | ×2 |
| Anode 3 | a3 |
| Deflecting Plate X1 | x1 |
| Deflecting Plate Y1 | у1 |
| | Cathode Heater Heater Anode 1 Anode 2 Internal Coating Deflecting Plate Y2 Deflecting Plate X2 Anode 3 Deflecting Plate X1 |

30C2

5½" MEASUREMENT CATHODE RAY TUBE ELECTROSTATIC FOCUS AND DEFLECTION



All Dimensions in mm.

* Two movable Bakelite bands are fitted to support a Mu-Metal shield.

Electronic Components Division
Tel.: GERrard 9797



5½" MEASUREMENT CATHODE RAY TUBE ELECTROSTATIC FOCUS AND DEFLECTION

GENERAL

The 30C3 is a precision Measurement Cathode Ray Tube having a $5\frac{1}{2}$ " diameter polished glass face. The Deflector Plates are connected through side arms to achieve low values of lead inductance and capacitance.

RATING

| Heater Voltage (volts) | Vh | 4.0 |
|---------------------------------------|----------------|----------|
| Heater Current (amps) | l _h | 0.72 |
| Maximum 1st Anode Voltage (volts) | Va1(max) | 2,500 |
| Maximum 2nd Anode Voltage (volts) | Va2(max) | 1,000 |
| Maximum 3rd Anode Voltage (volts) | Va3(max) | 6,000 |
| Average Sensitivity of "X" Plates (mr | n/V) | 600/V† |
| Average Sensitivity of "Y" Plates (mn | n/V) | 1,100/V† |

 $[\]dagger$ Where "V" denotes the voltage on the 3rd Anode and Bulb Coating.

INTER-ELECTRODE CAPACITANCES (pF)

| X1 Plate/All other electrodes | cx1-all | 6.0 |
|-------------------------------|---------|------|
| X2 Plate/All other electrodes | cx2-all | 6.0 |
| Y1 Plate/All other electrodes | cy1-all | 8.6 |
| Y2 Plate/All other electrodes | cy2-all | 8.6 |
| X1 Plate/Y1 Plate | cx1-y1 | 0.25 |
| X1 Plate/Y2 Plate | cx1-y2 | 0.25 |
| X2 Plate/Y1 Plate | cx2-y1 | 0.25 |
| X2 Plate/Y2 Plate | cx2-y2 | 0.25 |
| Grid/All other electrodes | cg-all | 8.2 |
| X1 Plate/X2 Plate | cx1-x2 | 2.5 |
| Y1 Plate/Y2 Plate | cy1-y2 | 3.2 |

December, 1961



5½" MEASUREMENT CATHODE RAY TUBE ELECTROSTATIC FOCUS AND DEFLECTION

DIMENSIONS

| Maximum Overall Length | (mm) | 430 |
|---------------------------|-------|------|
| Maximum Diameter | (mm) | 142 |
| Nominal Screen Diameter | (ins) | 51/2 |
| Approximate Nett Weight | (ozs) | 30 |
| Approximate Packed Weight | (lbs) | 1114 |

NOTES

The connections to the deflector plates are brought out to side contacts on the neck of the tube in order to reduce the inductance and capacitance of the leads, and the coupling between the X and Y plates. It is intended, particularly, for H.F. and pulse measurements.

For general measurement work the 30C3/T1 is recommended. This has a screen with a medium persistence green phosphor. For special applications, however, the tube may be supplied with any of the standard phosphors described on the Introductory Page to this section, except T7.

The Final Anode and the Bulb coating are brought out separately in order that a finer spot or a higher writing speed may be obtained by increasing the Final Anode voltage above the limit set for the First Anode Voltage.

In use the Third Anode and Bulb coating are normally joined.
All Maximum Ratings are Absolute Values not Design Centres.

TYPICAL OPERATION

| 3rd Anode Voltage (volts) | V _a 3 | 2,000 | 6,000 |
|--|---------------------------|-----------|-------|
| 2nd Anode Voltage for focus (approx.) (volts) | V_{a2} | 440 | 960 |
| 1st Anode Voltage (volts) | V_{a1} | 2,000 | 2,000 |
| Average Bias on Control Grid for of Beam Current (volts) | Cut-off V _g | <u>60</u> | 60 |
| Average Working Bias for 20μA Beam (volts) | 1001 | —33 | —33 |
| Approximate Sensitivity of "X" (mm/V) | Plates | 0.30 | 0.1 |
| Approximate Sensitivity of "Y" | Plates (mm/V) | 0.57 | 0.19 |
| | | | |

December, 1961

Issue 1, Page 2




$5\frac{1}{2}$ " MEASUREMENT CATHODE RAY TUBE ELECTROSTATIC FOCUS AND DEFLECTION

CAPS—CT2

BASE-B12D

*Permissible angular variation of mounts $\pm 10^{\circ}$



Viewed from free end of base.

CONNECTIONS


| Pin 1 | Control Grid | g |
|--------|---------------|----|
| Pin 2 | Cathode | k |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |
| Pin 5 | Anode 1 | a1 |
| Pin 6 | Anode 2 | a2 |
| Pin 7 | No Connection | NC |
| Pin 8 | No Connection | NC |
| Pin 9 | No Connection | NC |
| Pin 10 | Anode 3 | a3 |
| Pin 11 | No Connection | NC |
| Pin 12 | No Connection | NC |

December, 1961

Issue 1, Page 3



30C3
5½" MEASUREMENT CATHODE RAY TUBE
ELECTROSTATIC FOCUS AND DEFLECTION



All Dimensions in mm.



CATHODE RAY TUBE—ALL ELECTROSTATIC 7" Dia. Indirectly heated—for measurements

| RATING | | |
|---|--|--|
| Heater Voltage (volts) | v _h | 4.0 |
| Heater Current (amps) | Ih | 0.72 |
| Maximum 1st Anode Voltage (volts) | Val(max) | 500 |
| Maximum 2nd Anode Voltage (volts) | Va2(max) | 1,000 |
| Maximum 3rd Anode Voltage (volts) | Va3(max) | 4,000 |
| Average Sensitivity of "X" plates (mm | | *520/V |
| Average Sensitivity of "Y" plates (mm | √V) | * 520/V |
| * Where "V" denotes the voltage | on the 3rd An | ode. |
| All Maximum Ratings are Absolute | values not De | sign |
| INTER-ELECTRODE CAPACITANCES | | |
| X1 Deflecting Plate/all other electro X2 Deflecting Plate/all other electro Y1 Deflecting Plate/all other electro Y2 Deflecting Plate/all other electro X1 Deflecting Plate/all other electro X1 Deflecting Plate/X2 Deflecting Plat Y1 Deflecting Plate/Y2 Deflecting Plat X1+X2 Deflecting Plates/Y1+Y2 Deflect Plates (µµF) Control Grid (Wehnelt)/All other elect (µµF) | des (puf) Cy1, des (puf) Cy2, te (puf) Cx1, te (puf) Cy1, | all 14.0 all 14.9 all 13.8 x2 4.5 y2 4.4 +X2 +X2 +Y2) 2.7 |
| D IMENS IONS | 8,4 | |
| Maximum Overall Length (mm) Maximum Diameter (mm) Nominal Screen Diameter (inches) Approximate Nett Weight (lbs) Approximate Packed Weight (lbs) | 495 175 7 21 118 | |
| NOTES | | |
| The 30.C.9 is a precision contru for applications where the accuracy o tion employed in compass tubes is req provision of scales. | f the gun cont | ruct- |
| The gun system is capable of provideam currents when pulse modulation of required. | viding the high | h |
| For general measurement work the recommended. This has a screen with a ence green phosphor. For special appliche tube may be supplied with any of t described on the introductory page in | medium persia | OTTO W |

December, 1961

Issue 1, Page 1



CATHODE RAY TUBE—ALL ELECTROSTATIC 7" Dia. Indirectly heated—for measurements


| TYPICAL OPER | | | |
|---|---|-----------------------|---------|
| 3rd Anode Vo | ltage (volts) | Va3 | 2,200 |
| 2nd Anode Vo | ltage-approximate for cus (volts) # | Va2 | 440 |
| 1st Anode Vo | ltage (volts) | Val | 450 |
| Negative Bia cut-off of B | s on Control Grid for eam Current (volts) | Vg | 30-90 |
| 7 | The voltage required of for focus decreases with of beam current and the gives the voltage requirent. | ith an increase | |
| BASE 12 con | tact Key Base | \ KEY | / |
| (| BS.448) | | / |
| | | X 12 1 | X |
| VIEW O | F FREE END | 11 2 | |
| | | 1 | 3 |
| | | 1 9 A | 4 |
| | | 11 11 | |
| PERMIS | SIBLE ANGULAR | 87/65 | 1 |
| | SIBLE ANGULAR | 8 /1 5 | X |
| | SSIBLE ANGULAR N OF MOUNTS ± 10° | 8 /1 5 | 人 |
| | | 8 /1 5 | X |
| VARIATIO | | 8 /1 5 | X |
| | | 8 /1 5 | X |
| VARIATIO | | 8 /1 5 | X- |
| VARIATIO | N OF MOUNTS ± 10° | 87/65 | X |
| CONNECTIONS Pin 1 | N OF MOUNTS ± 10° | 8 7 6 5 | X . |
| CONNECTIONS Pin 1 Pin 2 | N OF MOUNTS ± 10° Control Grid Cathode | 8 7 6 5 s | X . |
| CONNECTIONS Pin 1 Pin 2 Pin 3 | Control Grid Cathode Heater | 8 7 6 5 k | X . |
| CONNECTIONS Pin 1 Pin 2 Pin 3 Pin 4 | Control Grid Cathode Heater | 8 7 6 5 8 k h h | X . |
| CONNECTIONS Pin 1 Pin 2 Pin 3 Pin 4 Pin 5 | Control Grid Cathode Heater Heater Anode 1 | s k h | X |
| CONNECTIONS Pin 1 Pin 2 Pin 3 Pin 4 Pin 5 Pin 6 | Control Grid Cathode Heater Heater Anode 1 | 8 7 6 5 k h h al a2 - | X . |
| CONNECTIONS Pin 1 Pin 2 Pin 3 Pin 4 Pin 5 Pin 6 Pin 7 | Control Grid Cathode Heater Heater Anode 1 Anode 2 | 8 7 6 5 k h h al a2 - | <u></u> |
| CONNECTIONS Pin 1 Pin 2 Pin 3 Pin 4 Pin 5 Pin 6 Pin 7 Pin 8 | Control Grid Cathode Heater Heater Anode 1 Anode 2 Deflecting Plate | 8 7 6 5 k h h al a2 - | <u></u> |
| CONNECTIONS Pin 1 Pin 2 Pin 3 Pin 4 Pin 5 Pin 6 Pin 7 Pin 8 Pin 9 | Control Grid Cathode Heater Heater Anode 1 Anode 2 Deflecting Plate Deflecting Flate | 8 | |

December, 1961

Issue 1, Page 2



30C9
CATHODE RAY TUBE—ALL ELECTROSTATIC 7" Dia.
Indirectly heated—for measurements



.3060.0-2

All dimensions in mm.

9007



PANAGE

100

home property to



CATHODE RAY TUBE-ALL ELECTROSTATIC 12" Dia.

For measurement purposes

RATING

| Heater Voltage (volts) | Vh | 4.0 |
|--|-----------|--------|
| Heater Current (amps) | lh | 0.72 |
| Maximum 1st Anode Voltage (volts) | Va1 (max) | 500 |
| Maximum 2nd Anode Voltage (volts) | Va2(max) | 1,400 |
| Maximum 3rd Anode Voltage (volts) | Va3(max) | 6,000 |
| Average Sensitivity of "X" Plates (mm/ | (V) | *900/V |
| Average Sensitivity of "Y" Plates (mm/ | V) | *900/V |

^{*} Where "V" denotes the voltage on the 3rd Anode.

DIMENSIONS

| Maximum Overall Length | (mm) | 640 |
|---------------------------|----------|------|
| Maximum Diameter | (mm) | 312 |
| Maximum Neck Diameter | (mm) | 65 |
| Nominal Screen Diameter | (inches) | 12 |
| Approximate Nett Weight | (lbs) | 71/2 |
| Approximate Packed Weight | (lbs) | 40 |

NOTES

For general measurement work the 30E6/T1 is recommended. This has a screen with a medium persistence green phosphor. For special applications, however, the tube may be supplied with any of the standard phosphors described in the Introductory page to this Section except T7.

All Maximum Ratings are Absolute values not Design Centres.

CATHODE RAY TUBE-ALL ELECTROSTATIC 12" Dia.

For measurement purposes

TYPICAL OPERATION

| 3rd Anode Voltage (volts) | V _a 3 | 5,000 | 6,000 |
|--|------------------|-------|-------|
| *2nd Anode Voltage—approximate for focus (volts) | V _{a2} | 1,000 | 1,200 |
| 1st Anode Voltage (volts) | Va1 | 400 | 450 |
| Negative Bias on Control Grid for Cut-off beam Current (volts) | Vg | 30-60 | 34-64 |

* The voltage required on the 2nd Anode for focus decreases with an increase of beam current and the above figure gives the voltage required at low currents.

BASE-B12D

* Permissible angular variation of mounts ±10°



View from free end of base.



CATHODE RAY TUBE-ALL ELECTROSTATIC 12" Dia.

For measurement purposes

CONNECTIONS

| Pin 1 | Control Grid | g | |
|--------|---------------------------|------|---|
| Pin 2 | Cathode | k | |
| Pin 3 | Heater | h | |
| Pin 4 | Heater | h | |
| Pin 5 | Anode 1 | a1 | |
| Pin 6 | Anode 2 | a2 | |
| Pin 7 | No Connection | NC | 4 |
| Pin 8 | Deflecting Plate Y2 | y2 | |
| Pin 9 | Deflecting Plate X2 | ×2 | |
| Pin 10 | Anode 3, Internal Coating | a3,m | |
| Pin 11 | Deflecting Plate X2 | x1 | |
| Pin 12 | Deflecting Plate Y1 | y1 | |




EDISWAN

30E6

CATHODE RAY TUBE-ALL ELECTROSTATIC 12" Dia.

For measurement purposes



All Dimensions in mm.



CATHODE RAY TUBE—LONG AFTERGLOW 12 inch Diameter Indirectly heated—for Marine Radar

GENERAL

The 30E11 is a 12" aluminised cathode ray tube, having a special long-afterglow screen, suitable for P.P.I. display. A double layer type screen is employed which gives a blue flash with a yellow afterglow. The focusing is electrostatic and the deflection magnetic.

RATING

| Heater Voltage (volts) | Vh | 4.0 |
|--------------------------------------|----------|---------|
| Heater Current (amps) | lh | 0.75 |
| Maximum 1st Anode Voltage (volts) | Va1(max) | 1,700 |
| Maximum 2nd Anode Voltage (volts) | Va2(max) | 1,700 |
| Maximum 3rd Anode Voltage (volts) | Va3(max) | *10,000 |

^{*} The maximum rating of 10kV is a design centre rating. The absolute maximum of 12,000 volts must not be exceeded.

NOTE. The 1st Anode must always be at least 50 volts positive with respect to the 2nd Anode.

DIMENSIONS

| Maximum Overall Length (mm) | 540 |
|--|-------|
| Maximum Bulb Diameter (mm) | 312 |
| Maximum Neck Diameter (mm) | 35 |
| Minimum Neck Diameter (mm) | 33.5 |
| Screen Face to 35.5 m/r dia. Swing Gauge (mm) | 284±3 |
| Nominal Screen Diameter (ins.) | 12 |
| Approximate Nett Weight (lbs) | 6 |
| Approximate Packed Weight (lbs) | 35 |

December, 1961 Issue 1, Page 1

CATHODE RAY TUBE—LONG AFTERGLOW 12 inch Diameter Indirectly heated—for Marine Radar

TYPICAL OPERATION

| 3rd Anode Voltage (volts) | 10,000 |
|---|--------|
| 2nd Anode Voltage (Focusing) volts (approx) | 1,500 |
| 1st Anode Voltage (volts) | 1,550 |
| Average Negative Bias on Control Grid | |
| for cut-off of Beam Current (volts) | 80 |

BASE-International Octal (108)



Viewed from free end of pins

CAP-CT2

VALVE HOLDER—Ediswan Clix VH 232/8, VH 238/8.

CONNECTIONS


| Pin 1 | No Internal Connection | 1C |
|-------|------------------------|----|
| Pin 2 | Anode 1 | 1 |
| Pin 3 | Anode 2 | 2 |
| Pin 4 | No Internal Connection | C |
| Pin 5 | Grid | |
| Pin 6 | Cathode | |
| Pin 7 | Heater | |
| Pin 8 | Heater | |
| CAP | Anode 3 | 3 |

December, 1961

Issue 1, Page 2



CATHODE RAY TUBE—LONG AFTERGLOW 12 inch Diameter Indirectly heated—for Marine Radar



.....

All dimensions in mm.

Anode Cap in line with keyway on base.

* Determined by Reference Line Gauge No. 6. See Section 3.

December, 1961

Issue 1, Page 3



ALEXE

AUCODA STEE DOOD - ALEX TO - A SECURITION

THE BANK AND A SECURITION OF THE BANK AND A SECURITIO

All dimensions by man.
Angeler Card in him with Lagrang an base.

I before man a los References also Caraga Non a companies N



CATHODE RAY TUBE—ALL ELECTROSTATIC 3½" DIA.
Post Deflection Acceleration
For High Precision Instruments

GENERAL

The 31B81 is a flat screen Cathode Ray Tube with post-deflection acceleration. It is suitable for high precision instruments.

RATING

| Heater Voltage | Vh | 6-3 V |
|--|-------------------------|--------|
| Heater Current | lh. | 0.5 A |
| Maximum Final Anode Voltage | Va4(max) | 8 kV |
| Minimum Final Anode Voltage | Va4(min) | 2 kV |
| Maximum Third Anode Voltage | V _a 3(max) | 4 kV |
| Minimum Third Anode Voltage | Va3(min) | 1 kV |
| Maximum Second Anode Voltage | Va2(max) | 2 kV |
| Maximum First Anode Voltage | Va1(max) | 2.5kV |
| Minimum First Anode Voltage | Va1(min) | 1 kV |
| Maximum Negative Grid Voltage | Vg(max) | -200 V |
| Minimum Negative Grid Voltage (cathode hot) | V _{g(min)} | 0* V |
| Maximum Positive Grid Voltage (cathode cold) | Vg(max) | 200 V |
| Maximum X1 Plate/X2 Plate Voltage | V _{x1-x2(max)} | 1 kV |
| Maximum Y1 Plate/Y2 Plate Voltage | Vy1-y2(max) | 1 kV |
| Maximum Heater/Cathode Voltage | Vh-k(max) | 150 V |
| Maximum X Plate/Third Anode Resistance | R _{x-a} 3(max) | 5 MΩ |
| Maximum Y Plate/Third Anode Resistance | Ry-a3(max) | 5 MΩ |
| Maximum Grid/Cathode Resistance | Rg-k(max) | 2 ΜΩ |
| Minimum Heater/Cathode Resistance | rh-k(min) | 2†ΜΩ |
| Minimum Grid/Cathode Resistance | rg-k(min) | 10 ΜΩ |

^{*} The Grid must not become positive with respect to cathode.

[†] Heater 100V negative to cathode.



CATHODE RAY TUBE—ALL ELECTROSTATIC 3½" DIA. Post Deflection Acceleration For High Precision Instruments

INTER-ELECTRODE CAPACITANCES (pF)

| Cathode/All other electrodes | ck-all | 8 |
|--|------------------|-----|
| Grid/All other electrodes | cg-all | 17 |
| X1 Deflecting Plate/X2 Deflecting Plate | cx1-x2 | 2.5 |
| Y1 Deflecting Plate/Y2 Deflecting Plate | cy1-y2 | 3 |
| X1 Deflecting Plate/All other electrodes except X2 | cx1-all, less x2 | 8 |
| X2 Deflecting Plate/All other electrodes except X1 | cx2-all, less x1 | 8 |
| Y1 Deflecting Plate/All other electrodes except Y2 | Cy1-all, less y2 | 7.5 |
| Y2 Deflecting Plate/All other electrodes except Y1 | Cy2-all, less y1 | 7.5 |
| Y1 Deflecting Plate/X1 or X2 Deflecting Plate (approx.) | cy1-x1 or x2 | 0-1 |
| Y2 Deflecting Plate/X1 or X2 Deflecting Plate (approx.) | | 0.2 |
| Deflecting Flace (approx.) | cy2-x1 or x2 | 0.2 |

CHARACTERISTICS

| Second Anode Voltage (focus anode) Grid Bias Voltage for cut off at | V _{a2} | 350 V |
|---|-----------------|---------------------------|
| V _{a1} =1kV | Vg | -35 V |
| $V_{a1}=2kV$ | Va | -70 V |
| $V_{a1} = 2.5kV$ | Vg Vg | -87 V |
| X Plate Sensitivity (V _a 4=V _a 3) | Sx | $\frac{800}{V_{a3}}$ mm/V |
| Y Plate Sensitivity ($V_{a4} = V_{a3}$) | Sy | $\frac{520}{V_{a3}}$ mm/V |
| X Plate Sensitivity ($V_{a4} = 2V_{a3}$) | S _X | $\frac{620}{V_{a3}}$ mm/V |
| Y Plate Sensitivity ($V_{a4} = 2V_{a3}$) | Sy | $\frac{400}{V_{a3}}$ mm/V |
| Grid Voltage (Drive) at I _a 4=25μA, V _{a1} =2kV | Vg | <32 V |

December, 1961

ADVANCE DATA, Page 2



CATHODE RAY TUBE—ALL ELECTROSTATIC 3½" DIA. Post Deflection Acceleration For High Precision Instruments

The undeflected spot will fall within a circle of 5 mm radius from the centre of the tube face.

The Plate sensitivity for a deflection of less than 75% of the useful scan will not differ from that for 25% by more than 2%.

The edges of a raster with mean dimensions which are 75% of the useful scan will not deviate from the mean rectangle by more than $2\frac{1}{2}\%$.

The minimum useful screen area is a circle of 3.7 cm radius. Orthogonality of deflection axes is $\pm 1\%$.

DEFLECTION DISTORTION

In any Cathode Ray Tube using a simple post-deflection accelerator, the application of the accelerating potential results in deflection distortion, which becomes more pronounced as the ratio of V_a4/V_a3 is increased.

It is recommended that for work involving the measurement of relative deflection amplitudes directly on the tube face this ratio should not exceed 2:1.

ORIENTATION

Looking at the screen with the splgot key upward, a positive potential applied to X1 will deflect the spot to the left and a positive potential applied to Y1 will deflect the spot upward.

MAGNETIC SHIELDING

The magnetic shield should be of high permeability material, of a thickness determined by the magnetic field at the tube position. The shield should be earthed. To obtain optimum results equipment containing Cathode Ray Tubes should always be designed to minimise the magnetic field around the tubes, as magnetic shielding can never be completely effective. In addition to the more obvious deflection effects of alternating fields, steady magnetic fields from smoothing chokes, magnetised steel components, etc., can produce spot distortion or low gun efficiency.



CATHODE RAY TUBE—ALL ELECTROSTATIC 3½" DIA. Post Deflection Acceleration For High Precision Instruments

DIMENSIONS

| Maximum Overall Length | 360mm |
|-------------------------|-------|
| Maximum Screen Diameter | 92mm |
| Maximum Neck Diameter | 52mm |

MOUNTING

The tube should not be supported by the base alone, but should preferably be held in a rubber-lined clamping ring at the screen end together with a similar clamp round the magnetic screen close to the base.

The socket should have sufficient freedom of movement to accommodate the tube overall length tolerance and a small amount of lateral float to ensure good pin contact without straining the base.

SCREEN PHOSPHORS

| Type | Colour | Persistence | Application |
|------|------------------|--------------|-------------------------|
| T1 | Green | Medium | Visual |
| T3 | Blue Actinic | Short | Photographic |
| T4 | White | Medium Short | Visual/ Photographic |
| T6 | Yellow Afterglow | Long | Visual |
| T7 | Orange Afterglow | Very Long | Visual |

TYPICAL OPERATION

| Final Anode Voltage | Va4 | 4 kV |
|----------------------|------------------|-------|
| Third Anode Voltage | V _a 3 | 2 kV |
| Second Anode Voltage | V _{a2} | 350 V |
| First Anode Voltage | V _{a1} | 2 kV |
| Grid Voltage | Vo | -60 V |
| Third Anode Current | Vg Ia3 | 1 μΑ |
| Final Anode Current | | |
| (= screen) | la4 | 2 μΑ |

The Line width at I screen = $0.5\mu A$ is 0.3mm measured on a circle 50mm diameter.

December, 1961

ADVANCE DATA, Page 4



CATHODE RAY TUBE—ALL ELECTROSTATIC 3½" DIA.

Post Deflection Acceleration

For High Precision Instruments

SIDE CONTACT-CT8

BASE-B14A (Diheptal)



Viewed from free end of pins.

CONNECTIONS


| Pin 1 | Heater | h |
|--------|--------------------|----|
| Pin 2 | Cathode | k |
| Pin 3 | Grid | g |
| Pin 4 | First Anode | a1 |
| Pin 5 | Second Anode | a2 |
| Pin 6 | No pin | NP |
| Pin 7 | Deflector Plate Y1 | Y1 |
| Pin 8 | Deflector Plate Y2 | Y2 |
| Pin 9 | Third Anode | a3 |
| Pin 10 | Deflector Plate X2 | ×2 |
| Pin 11 | Deflector Plate X1 | x1 |
| Pin 12 | No Connection | NC |
| Pin 13 | No Pin | NP |
| Pin 14 | Heater | h |
| Cap | Final Anode | a4 |

31B81

CATHODE RAY TUBE—ALL ELECTROSTATIC 3½" DIA.

Post Deflection Acceleration

For High Precision Instruments



All Dimensions in mm.



CATHODE RAY TUBE—ALL ELECTROSTATIC 5" DIA.
Helical Post Deflection Acceleration
For High Performance Oscillography

GENERAL

The 31B82 is a precision Cathode Ray Tube designed for high performance oscillography. It has high deflection sensitivity and a helical post-deflection accelerator which allows the application of high p.d.a, ratios. The screen is aluminised and the deflector plates are brought out to side arms.

RATING

| MAINING | | | | |
|----------------------------------|-----------|-----------------------|------|-----|
| Heater Voltage | | $V_{ m h}$ | 6.3 | ٧ |
| Heater Current | | lh entered | 0-6 | Α |
| Maximum Final A Voltage | Anode | V _{a4(max)} | 12 | kV |
| Maximum Second Voltage | d Anode | Va2(max) | 800 | ٧ |
| Maximum First a Anode Voltage | | Va1,a3(max) | 2 | kV |
| Maximum Negati Voltage | ive Grld | V _{g(max)} | -200 | V |
| Maximum Positiv Voltage | e Grid | V _{g(max)} | 0* | ٧ |
| Maximum Third | | ne arrange t | 500 | V |
| plates | | √a3(pk)max | 300 | ٧ |
| Maximum Heater Voltage | -/Cathode | V _{h-k(max)} | 180 | ٧ |
| Maximum Isolatin Voltage | ng Shield | V _{is(max)} | 2.1 | lkV |
| Maximum Deflect Shield Voltage | tor Plate | Vdef(max) | 2.1 | lkV |
| | | | | |

^{*} The grid must not become positive with respect to cathode.

CATHODE RAY TUBE—ALL ELECTROSTATIC 5" DIA.
Helical Post Deflection Acceleration
For High Performance Oscillography

INTER-ELECTRODE CAPACITANCES (pF)†

| Cathode/All other electrodes | ck-all | 4.6 |
|--|---------|-----|
| Grid/All other electrodes | cg-all | 6-4 |
| X1 Deflecting Plate/X2 Deflecting Plate | cx1-x2 | 1.9 |
| Y1 Deflecting Plate/Y2 Deflecting Plate | cy1-y2 | 1.5 |
| X1 Deflecting Plate/All other electrodes | cx1-all | 3-5 |
| X2 Deflecting Plate/All other electrodes | cx2-all | 3.5 |
| Y1 Deflecting Plate/All other electrodes | Cy1-all | 2.8 |
| Y2 Deflecting Plate/All other electrodes | cy2-all | 2.8 |

[†] With holder balanced out.

POST DEFLECTION ACCELERATOR-Helical

| Resistance | Rpda | 200-600 | MΩ |
|------------|-------|---------|-------|
| Resistance | · paa | 200-000 | 1.175 |

ORIENTATION

Looking at the screen with the p.d.a. contact to the left, a positive potential applied to X1 will deflect the spot to the left and a positive potential applied to Y1 will deflect the spot upward.



CATHODE RAY TUBE—ALL ELECTROSTATIC 5" DIA.
Helical Post Deflection Acceleration
For High Performance Oscillography

DIMENSIONS

| Maximum Overall Length | 469 mm |
|-------------------------|----------|
| Maximum Screen Diameter | 135-4 mm |
| Maximum Neck Diameter | 52-55mm |

MOUNTING

straining the base.

The tube should not be supported by the base alone, but should preferably be held in a rubber-lined clamping ring at the screen end together with a similar clamp round the magnetic screen close to the base.

The socket should have sufficient freedom of movement to accommodate the tube overall length tolerance and a small amount of lateral float to ensure good pin contact without

SCREEN PHOSPHORS

| Туре | Colour | Persistence | Application |
|------|------------------|--------------|-------------------------|
| T1 | Green | Medium | Visual |
| T3 | Blue Actinic | Short | Photographic |
| T4 | White | Medium Short | Visual/ Photographic |
| T6 | Yellow Afterglow | Long | Visual |
| T7 | Orange Afterglow | Very Long | Visual |
| T8 : | Yellow Afterglow | Medium Long | Visual |

December, 1961

ADVANCE DATA, Page 3

CATHODE RAY TUBE—ALL ELECTROSTATIC 5" DIA.
Helical Post Deflection Acceleration
For High Performance Oscillography

TYPICAL OPERATION

| Final Anode Voltage | Va4 | 10 kV |
|-----------------------------------|-----------------------------------|----------------|
| Second Anode Voltage | Va2 | 180 to 590 V |
| First and Third Anode Voltage | Va1.a3 | 1-67kV |
| Grid Bias Voltage for cut-off | Vg | -50 to -80 V |
| Isolation Shield Voltage | V _g V _{is} | 1.57 to 1.7*kV |
| Deflector Plate Shield Voltage | Vdef | 1.57 to 1.7‡kV |
| | | |

- * The inner end of the helix and the isolation shield are connected together inside the tube. With the correct potential on these electrodes, barrel and pin-cushion effects are minimised.
- ‡ Adjustment of the deflection plate shield potential controls the linearity of the Y deflection by variation of the edge effect of the Y deflection plates.

For many purposes the deflection plate shield (pin 12) may be connected externally to the isolation shield.

DEFLECTION CHARACTERISTICS—Under above conditions

| Sensitivity of X Plates | S _X | 560 V _{a3} mm/V |
|-------------------------|----------------|-----------------------------|
| Sensitivity of Y Plates | Sy | 2800 mm/V |
| Useful X Plate Scan | | 10 cm |
| Useful Y Plate Scan | | 4 cm |

The undeflected spot will fall within a circle of 5 mm radius from the centre of the tube face.

Orthogonality of deflection axes: ± 1%

The edges of a raster the size of the useful scan will not deviate from the mean rectangle by more than 1.5%.

December, 1961

ADVANCE DATA, Page 4




31B82

CATHODE RAY TUBE—ALL ELECTROSTATIC 5" DIA.
Helical Post Deflection Acceleration
For High Performance Oscillography

SIDE CONTACT—CT8

BASE-B14A (Diheptal)



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | Heater | h |
|---------|------------------------|--------|
| Pin 2 | Cathode | k |
| Pin 3 | Grid | g |
| Pin 4 | No Connection | NC |
| Pin 5 | Second Anode | a2 |
| Pin 6 | No Pin | NP |
| Pin 7 | No Connection | NC |
| Pin 8 | No Connection | NC |
| Pin 9 | First and Third Anode | a1, a3 |
| Pin 10 | No Connection | NC |
| Pin 11 | No Connection | NC |
| Pin 12* | Deflector Plate Shield | S1 |
| Pin 13 | No Pin | NP |
| Pin 14 | Heater | h |
| Cap | Final Anode | a4 |
| * | Isolation Shield | S2 |


December, 1961

ADVANCE DATA, Page 5



31B82

CATHODE RAY TUBE—ALL ELECTROSTATIC 5" DIA.
Helical Post Deflection Acceleration
For High Performance Oscillography



All Dimensions in mm.

The 31C12 is an electrostatically focused and magnetically deflected cathode-ray tube intended for use in Radio DF Compass equipment. The tube is aluminised, has a 6'' diameter flat face, and is available with a "T2" screen which gives a blue-green trace of long persistence.

RATINGS

| Heater voltage | V_h | 6.3 | ٧ |
|---|-------------------------|-----------|----|
| Heater current | I _h | 0.6 | Α |
| Maximum first and third anode voltage | $V_{a1,a3(max)}$ | 14* | kV |
| Minimum first and third anode voltage | V _{a1,a3(min)} | 10 | kV |
| Maximum second anode voltage | $V_{a2(max)}$ | \pm 700 | V |
| Maximum heater/cathode voltage, d.c. (heater negative) | V _{h-k(max)} | 180 | ٧ |
| Maximum peak heater/cathode voltage, d.c. (heater negative) | Vh-k(pk)max | 400†‡ | ٧ |

^{* 14}kV is a design centre rating, the absolute rating of 15.5kV must not be exceeded.

INTER-ELECTRODE CAPACITANCES

| Grid/All other electrodes | C _{g-all} | 5.5 | pF |
|------------------------------|--------------------|-----|----|
| Cathode/All other electrodes | Ck-all | 6.0 | pF |

These capacitances include an AEI duodecal holder type CRT92/7.


TYPICAL OPERATION

| First and third anode voltage | $V_{a1,a3}$ | 12 | kV |
|--|-------------|----------------|----|
| Second anode voltage for focus (range) | V_{a2} | -100 to $+300$ | V |
| Grid bias voltage for cut-off of raster | V_g | -30 to -72 | V |
| Maximum peak to peak modulating voltage for modulation of limit cathode-ray tube up to $50\mu A$ | | 25 | ٧ |

Page 1, Issue 1

[†] Absolute rating.

[#] During a warming-up period not exceeding 1 minute.



All dimensions in millimetres. Not to be scaled.



CATHODE RAY TUBE Indirectly heated—for Radio DF Compass

TENTATIVE

GENERAL

The 31C13 is a magnetically focused and deflected cathode ray tube. The tube is aluminised, has a 6" diameter flat face, and is available with a "T1" screen which gives a green trace of medium persistence. It has an internal compass scale graduated with octantal correction and its face is treated to reduce specular reflection.

RATING

| Heater Voltage | Vh | 6.3 | V |
|---|---------------------|-----|----|
| Heater Current | lh | 0.6 | A |
| Maximum Anode Voltage | V _{a(max)} | 10* | kV |
| Minimum Anode Voltage | Va(min) | 7.5 | kV |
| Maximum Heater/Cathode Voltage d.c. (heater negative) | Vh-k(max) | 150 | ٧ |

^{* 10}kV is a design centre rating. The absolute rating of 12.5kV maximum must not be exceeded.

INTER-ELECTRODE CAPACITANCES

| Grid/All other electrodes | cg-all | 4.7 pF |
|------------------------------|--------|--------|
| Cathode/All other electrodes | ck-all | 5-3 pF |

These capacitances include an Ediswan Clix wafer type duodecal holder.

TYPICAL OPERATION

| Anode Voltage | Va | 9.5 | kV |
|---|----|------------|----|
| Grid Bias Voltage for cut-off of | Vg | -43 to -93 | ٧ |
| Average Peak to Peak Modulating Voltage for Modulation up to $150~\mu\text{A}$ | | 30 | V |
| Maximum Peak to Peak Modulating Voltage for Modulation of limit Cathode Ray Tube up to 150 µA | | 35 | |
| Cachode Nay Tube up to 130 µA | | 33 | V |

A resistance should be inserted in the anode circuit in order to limit the discharge current to 100 mA(max), in the event of a flash-over inside the tube.

December, 1961

ADVANCE DATA, Page 1



CATHODE RAY TUBE

Indirectly heated-for Radio DF Compass

TENTATIVE

DIMENSIONS

| Maximum Overall Length | 458 | mm |
|---------------------------|------|-----|
| Maximum Face Diameter | 160 | mm |
| Maximum Neck Diameter | 35 | mm |
| Approximate Nett Weight | 21/4 | Ibs |
| Approximate Packed Weight | 161 | Ibs |

CAP—Cavity CT8

BASE—B12A (5 Pin)



Viewed from free end of pins

CONNECTIONS

| 00111120110110 | | |
|----------------|---------------|-----|
| Pin 1 | Heater | h |
| Pin 2 | Grid | g |
| Pin 3 | No Pin | NP |
| Pin 4 | No Pin | NP |
| Pin 5 | No Pin | NP |
| Pin 6 | No Pin | NP |
| Pin 7 | No Pin | NP |
| Pin 8 | No Pin | NP |
| Pin 9 | No Pin | NP |
| Pin 10 | No Connection | NC |
| Pin 11 | Cathode | k |
| Pin 12 | Heater | h h |
| Cap | Anode | a |

December, 1961

ADVANCE DATA, Page 2

Electronic Components Division Tel.: GERrard 9797



CATHODE RAY TUBE

Indirectly heated-for Radio D.F. Compass

GENERAL

The 31C14 is a magnetically focused and deflected cathode ray tube. The tube is aluminised, has a 6" diameter flat face, and is available with a screen type T1 which gives a green trace of medium persistence. It has an internal compass scale uniformly graduated and its face is treated to reduce specular reflection.

RATING

| Heater Voltage | Vh | 6.3 | V |
|--------------------------------|----------------|-----|----|
| Heater Current | lh. | 0-6 | A |
| Maximum Anode Voltage | Va(max) | 10* | kV |
| Minimum Anode Voltage | Va(min) | 7.5 | kV |
| Maximum Heater/Cathode Voltage | , , , | | |
| d.c. (heater negative) | $V_{h-k(max)}$ | 150 | V |

^{* 10} kV is a design centre rating. The absolute rating of 12.5 kV maximum must not be exceeded.

INTER-ELECTRODE CAPACITANCES

| Grid/All other electrodes | cg-all | 4.7 | pF |
|------------------------------|--------|-----|----|
| Cathode/All other electrodes | Ck-all | 5.3 | pF |

These capacitances include an AEI wafer-type duodecal holder.

TYPICAL OPERATION

| Anode Volt | tage | Va | 9.5 | kV |
|------------|--|----|------------|----|
| | oltage for cut-off of ocused line | ٧g | -43 to -93 | ٧ |
| | ak to Peak Modulating or Modulation up to | | 30 | ٧ |
| Voltage f | Peak to Peak Modulating for Modulation of limit Ray Tube up to 150µA | | 35 | V |

A resistance should be inserted in the anode circuit in order to limit the discharge current to 100mA (max), in the event of a flash-over inside the tube.

February, 1962

Issue 1, Page 1

31CI4

CATHODE RAY TUBE


Indirectly heated-for Radio D.F. Compass

DIMENSIONS

| Martine Original Laurah | 458 | mm |
|---------------------------|-----|-------|
| Maximum Overall Length | 430 | mm |
| Maximum Face Diameter | 160 | mm |
| Maximum Neck Diameter | 35 | mm |
| Approximate Net Weight | 2 | 1 lb. |
| Approximate Packed Weight | 16 | ¹ lb. |

CAP—Cavity (CT8)

BASE-B12A (5 Pin)



Viewed from free end of pins

CONNECTIONS

| Pin 1 | Heater | h |
|--------|---------------|----|
| Pin 2 | Grid | g |
| Pin 3 | No Pin | NP |
| Pin 4 | No Pin | NP |
| Pin 5 | No Pin | NP |
| Pin 6 | No Pin | NP |
| Pin 7 | No Pin | NP |
| Pin 8 | No Pin | NP |
| Pin 9 | No Pin | NP |
| Pin 10 | No Connection | NC |
| Pin 11 | Cathode | k |
| Pin 12 | Heater | h |
| Cap | Anode | a |

February, 1962

Issue 1, Page 2



CATHODE RAY TUBE-ALL ELECTROSTATIC 6" DIA. Post Deflection Acceleration For High Precision Instruments

GENERAL

The 31C81 is a flat screen Cathode Ray Tube with post-deflection acceleration. It is suitable for high precision instruments.

| о. | | | |
|----|---|--------|---|
| R | ~ | IN | u |
| | | | |

| Heater Voltage | Vh | 6. | 3 V |
|---|-------------------------|------|------|
| Heater Current (approx) | lh | 0.5 | 5 A |
| Maximum Final Anode Voltage | Va4(max) | 8 | kV |
| Minimum Final Anode Voltage | Va4(min) | 2 | kV |
| Maximum Third Anode Voltage | Va3(max) | 4 | kV |
| Minimum Third Anode Voltage | Va3(min) | 1 | kV |
| Maximum Second Anode Voltage | Va2(max) | 2 | kV |
| Maximum First Anode Voltage | Va1(max) | 2.5 | 5 kV |
| Minimum First Anode Voltage | Va1(min) | 1 | kV |
| Maximum Negative Grid Voltage | Vg(max) | -200 | V |
| Minimum Negative Grid Voltage (Cathode Hot) | Vg(min) | 0* | V |
| Maximum Positive Grid Voltage (Cathode Cold) | V _{g(max)} | 200 | ٧ |
| Maximum X1 Plate/X2 Plate | V | | 1.17 |
| Voltage | Vx1-x2(max) | - 1 | kV |
| Maximum Y1 Plate/Y2 Plate Voltage | ^v y1-y2(max) | 1 | kV |
| Maximum Heater/Cathode Voltage | Vh-k(max) | 150 | V |
| Maximum X Plate/Third Anode Resistance | R _{x-a3(max)} | 5 | МΩ |
| Maximum Y Plate/Third Anode Resistance | Ry-a3(max) | 5 | МΩ |
| Maximum Grid/Cathode Resistance | Rg-k(max) | 2 | ΜΩ |
| Minimum Heater/Cathode Resistance | rh-k(min) | 2† | МΩ |
| Minimum Grid/Cathode Resistance | rg-k(min) | 10 | MΩ |
| + TI C !! ! | 1.1 | | |

^{*} The Grid must not become positive with respect to cathode.

[†] Heater 100V Negative with respect to cathode.



CATHODE RAY TUBE-ALL ELECTROSTATIC 6" DIA. Post Deflection Acceleration For High Precision Instruments

INTER-ELECTRODE CAPACITANCES (pF) Cathode/All other electrodes Ck-all Grid/All other electrodes cg-all X1 Deflecting Plate/X2 Deflecting Plate 2.5 cx1-x2 Y1 Deflecting Plate/Y2 Deflecting Plate Cy1-y2 X1 Deflecting Plate/All other electrodes except X2 Cx1-all, less X2 X2 Deflecting Plate/All other electrodes except X1 cx2-all, less X1 Y1 Deflecting Plate/All other electrodes except Y2 cy1-all, less Y2 Y2 Deflecting Plate/All other electrodes except Y1 cy2-all, less Y1 Y1 Deflecting Plate/X1 or X2 Deflecting Plate (approx.) cy1-xl or x2 Y2 Deflecting Plate/X1 or X2 Deflecting Plate (approx.) 0.2 cy2-xl or x2

DEFLECTION DISTORTION

In any Cathode Ray Tube using a simple post-deflection accelerator, the application of the accelerating potential results in deflection distortion, which becomes more pronounced as the ratio of the V_24/V_3 3 is increased. It is recommended that for work involving the measurement of relative deflection amplitudes directly on the tube face this ratio should not exceed 2:1.

ORIENTATION

Looking at the screen with the spigot key upward, a positive potential applied to X1 will deflect the spot to the left and a positive potential applied to Y1 will deflect the spot upward.



CATHODE RAY TUBE-ALL ELECTROSTATIC 6" DIA. Post Deflection Acceleration For High Precision Instruments

MAGNETIC SHIELDING

The magnetic shield should be of high permeability material, of a thickness determined by the magnetic field at the tube position. The shield should be earthed. To obtain optimum results, equipment containing Cathode Ray Tubes should always be designed to minimise the magnetic field around the tubes, as magnetic shielding can never be completely effective. In addition to the more obvious deflection effects of alternating fields, steady magnetic fields from smoothing chokes, magnetised steel components, etc., can produce spot distortion or low gun efficiency.

DIMENSIONS

| Maximum Overall Length | Alle spekil den | 500mm |
|-------------------------|-----------------|-------|
| Maximum Screen Diameter | 20 | 163mm |
| Maximum Neck Diameter | | 52mm |

MOUNTING

The tube should not be supported by the base alone, but should preferably be held in a rubber-lined clamping ring at the screen end together with a similar clamp round the magnetic screen close to the base. The socket should have sufficient freedom of movement to accommodate the tube overall length tolerance and a small amount of lateral float to ensure good pin contact without straining the base.

SCREEN PHOSPHORS

| Type | Colour | Persistence | Application |
|------|------------------|--------------|-------------------------|
| T1 - | Green | Medium | Visual |
| T3 | Blue Actinic | Short | Photographic |
| T4 | White | Medium Short | Visual/ Photographic |
| T6 | Yellow Afterglow | Long | Visual |
| T7 | Orange Afterglow | Very Long | Visual |

December, 1961



CATHODE RAY TUBE-ALL ELECTROSTATIC 6" DIA. Post Deflection Acceleration For High Precision Instruments

| TYPICAL OPERATION | | |
|---|------------------------|-----------------------|
| Final Anode Voltage | V _a 4 | 4 kV |
| Third Anode Voltage | V _a 3 | 2 kV |
| Second Anode Voltage | V _a 2 | 350 V |
| First Anode Voltage | V _{a1} | 2 kV |
| Grid Voltage | | -60 V |
| Third Anode Current | Vg la3 | 1μΑ |
| Final Anode Current | warm and all marries a | 1 1 27 1 |
| (=Screen Current) | 124 | 2μΑ |
| mg 11 15 15 15 15 15 15 15 15 15 15 15 15 | 0 . 4 . 0 | and the second second |

The line width at $I_{screen} = 0.5 \mu A$ is 0.5 mm. measured on a circle of 50 mm. diameter.

CHARACTERISTICS

| Second Anode Voltage (focus anode) | V _{a2} | 350 V |
|---|----------------------------------|--|
| Grid Bias Voltage for cut-off at V _{a1} = 1kV V _{a1} = 2kV V _{a1} = 2·5kV X Plate Sensitivity (V _{a4} = V _{a3}) | Vg Vg Vg S _X | -35 V -70 V -87 V |
| Y Plate Sensitivity (V _{a4} =V _{a3}) | Sy | 860 |
| X Plate Sensitivity (V _{a4} =2V _{a3}) | Sx | V ₂₃ mm/V V ₂₃ mm/V |
| Y Plate Sensitivity ($V_{a4}=2V_{a3}$) | Sy | $\frac{710}{V_{a3}} \text{ mm/V}$ |
| Grid Voltage (drive) at $I_{a4}=25\mu A$, $V_{a1}=2kV$ | Vg | <32 V |

The Plate sensitivity for a deflection of less than 75% of the useful scan will not differ from that for 25% by more than 2%. The undeflected spot will fall within a circle of 7 mm radius from the centre of the tube face.

The minimum useful screen area is a circle of 7 cm radius. Orthogonality of deflection axes is \pm 1°.


The edges of a raster with mean dimensions which are 75% of the useful scan will not deviate from the mean rectangle by more than $2\frac{1}{2}\%$.



CATHODE RAY TUBE-ALL ELECTROSTATIC 6" DIA. Post Deflection Acceleration For High Precision Instruments

SIDE CONTACT—CT8

BASE-B14A (Diheptal)




Viewed from free end of pins

CONNECTIONS


| Pin 1 | 85.01.8 | Heater | h |
|--------|-----------------------|--------------------|--------|
| Pin 2 | | Cathode | k |
| Pin 3 | | Grid | g |
| Pin 4 | | First Anode | a1 |
| Pin 5 | | Second Anode | a2 |
| Pin 6 | | No Pin | NP |
| Pin 7 | | Deflector Plate Y1 | Y1 |
| Pin 8 | | Deflector Plate Y2 | Y2 |
| Pin 9 | | Third Anode | a3 |
| Pin 10 | | Deflector Plate X2 | X2 |
| Pin 11 | | Deflector Plate X1 | X1 |
| Pin 12 | Auto to make the com- | No Connection | NC |
| Pin 13 | | No Pin | NP |
| Pin 14 | | Heater | h |
| Cap | | Final Anode | a4 |



CATHODE RAY TUBE-ALL ELECTROSTATIC 6" DIA. Post Deflection Acceleration For High Precision Instruments



All Dimensions in mm.



The 31D12 is an $8\frac{1}{2}$ " diagonal rectangular tube with 90° magnetic deflection and low voltage electrostatic focusing. It is suitable for use in industrial monitoring equipment.

RATINGS

| Heater voltage | V_h | 6.3 | V |
|---|-----------------------|-----------|----|
| Heater current | l _h | 0.3* | A |
| Maximum second and fourth anode voltage | $V_{a2,a4(max)}$ | 15** | kV |
| Minimum second and fourth anode voltage | Va2,a4(min) | 8.0 | kV |
| Maximum third anode voltage | V _{a3(max)} | \pm 700 | V |
| Maximum first anode voltage | Va1(max) | 400 | V |
| Maximum heater/cathode voltage, d.c. (heater negative) | V _{h-k(max)} | 200 | ٧ |
| Maximum peak heater/cathode voltage, d.c. (heater negative) | Vh-k(pk)max | 400†‡ | ٧ |

^{*} The cathode-ray tube heater should always be connected at the chassis end if used in a series heater chain.

INTER-ELECTRODE CAPACITANCES

| Grid/all other electrodes | Cg-all | 7-0§ | pF |
|---|----------|------|----|
| Cathode/all other electrodes | Ck-all | 3.0§ | pF |
| Anode 2 and anode 4/external conductive | | | |
| coating (approx.) | Ca2,a4-M | 400 | pF |

§ Inter-electrode capacitances with holder capacitance balanced out.

TYPICAL OPERATION


| THICAL OF ENAMEDIN | | | |
|---|-------------|--------------|----|
| Second and fourth anode voltage | $V_{a2,a4}$ | 12 | kV |
| First anode voltage | V_{a1} | 300 | V |
| Third anode voltage for focus (range) | V_{a3} | \pm 200 | V |
| Grid bias voltage for cut-off of raster | V_g | -30 to -72 | V |
| Average peak to peak modulating voltage for modulation up to 150μ A | | 24 | V |

August, 1962 Page 1, Issue 1

^{** 15}kV is a design centre rating, the absolute rating of 18kV must not be exceeded.

[†] Absolute rating.

[‡] During a warming up period not exceeding one minute.



All dimensions in millimetres. Not to be scaled.

Notes

- * During the face sealing operation the glass in this area (total 22 mm) may be disturbed. As the shape of the contour within this area may be either convex or concave the bulb should not be gripped within this region unless special precautions are taken (such as the use of resilient packing material).
- ** The socket for the B9A/D button base should not be rigidly mounted, it should have flexible leads and be allowed to move freely. The design of the socket should be such that the wiring cannot impress lateral strains through the socket contacts on the base.



The 31D13 is an $8\frac{1}{2}$ diagonal rectangular tube with 90° magnetic deflection and low voltage electrostatic focusing. It is intended for use in television studio monitoring equipment.

RATINGS

| Heater voltage | V_h | 6.3 | V | |
|---|-------------------------|-----------|----|--|
| Heater current | l _h | 0.3* | Α | |
| Maximum second and fourth anode voltage | $V_{a2,a4(max)}$ | 16** | kV | |
| Minimum second and fourth anode voltage | V _{a2,a4(min)} | 8.0 | kV | |
| Maximum third anode voltage | $V_{a3(max)}$ | \pm 500 | V | |
| Maximum first anode voltage | $V_{a1(max)}$ | 500 | V | |
| Maximum heater/cathode voltage, heater negative (d.c.) | V _{h-k(max)} | 200 | ٧ | |
| Maximum peak heater/cathode voltage, heater negative (d.c.) | Vh-k(pk)max | 400†‡ | ٧ | |

^{*} The cathode-ray tube heater should always be connected at the chassis end in a series heater chain.

INTER-ELECTRODE CAPACITANCES§

| Grid/All other electrodes | Cg-all | 9.0 | pF |
|------------------------------|--------|-----|----|
| Cathode/All other electrodes | Ck-all | 7.0 | pF |

[§] These capacitances include an AEI duodecal holder type CRT92/7.

TYPICAL OPERATION


| Second and fourth anode voltage | $V_{a2,a4}$ | 12 | kV |
|---|-------------|----------------|----|
| First anode voltage | V_{a1} | 300 | V |
| Third anode voltage for focus (range) | V_{a3} | -300 to $+300$ | V |
| Grid bias for cut-off of raster | V_g | -30 to -72 | V |
| Average peak to peak modulating voltage for modulation up to $150\mu A$ | | 24 | ٧ |

August, 1962 Page 1, Issue 1

^{** 16}kV is a design centre rating, the absolute rating of 18kV must not be exceeded.

[†] Absolute rating.

[#] During a warming-up period not exceeding one minute.



All dimensions in millimetres. Not to be scaled.

Notes

- * During the face sealing operation the glass in this area (total 22 mm) may be disturbed. As the shape of the contour within this area may be either convex or concave the bulb should not be gripped within this region unless special precautions are taken (such as the use of resilient packing material).
- † Determined by Reference Gauge No. 13.



The 31D15 is an $8\frac{1}{2}$ diagonal rectangular tube with 90° magnetic deflection and low voltage electrostatic focusing. It is intended for use in industrial monitoring equipment.

RATINGS

| Heater voltage | V_h | 6.3 | V |
|---|------------------|----------|----|
| Heater current | I _h | 0.3* | A |
| Maximum second and fourth anode voltage | $V_{a2,a4(max)}$ | 15** | kV |
| Minimum second and fourth anode voltage | $V_{a2,a4(min)}$ | 8.0 | kV |
| Maximum third anode voltage | $V_{a3(max)}$ | ±700 | V |
| Maximum first anode voltage | $V_{a1(max)}$ | 500 | V |
| Maximum heater/cathode voltage, | | | |
| heater negative (d.c.) | $V_{h-k(max)}$ | 200 | V |
| Maximum peak heater/cathode voltage, | , | | |
| heater negative (d.c.) | Vh-k(pk)max | 400†‡ | V |

^{*} The cathode-ray tube heater should always be connected at the chassis end if used in a series heater chain.

INTER-ELECTRODE CAPACITANCES

| | 3 | 33 | |
|----------|--------------------|------------------------|--|
| Cg-all | 7.0 | 8.5 | pF |
| Ck-all | 3.0 | 3.5 | pF |
| | | | - |
| Ca2,a4-M | 4 | 00 | pF |
| | C _{k-all} | c _{k-all} 3·0 | c _{g-all} 7·0 8·5 c _{k-all} 3·0 3·5 |

[§] Inter-electrode capacitances with holder capacitance balanced out.

TYPICAL OPERATION

| Second and fourth anode voltage | $V_{a2,a4}$ | 12 | kV |
|---------------------------------------|-------------|--------------|----|
| First anode voltage | V_{a1} | 400 | V |
| Third anode voltage for focus (range) | V_{a3} | \pm 200 | V |
| Grid bias for cut-off of raster | Vg | -30 to -72 | V |
| Average peak/peak modulating voltage | | | |
| for modulation up to $150\mu A$ | | 24 | V |

August, 1962


Page 1, Issue 1

^{** 15}kV is a design centre rating, the absolute rating of 18kV must not be exceeded.

[†] Absolute rating.

[‡] During a warming-up period not exceeding one minute.

^{§§} Inter-electrode capacitances including an AEI B8H holder VH68/81 (8-pin).



All dimensions in millimetres. Not to be scaled.

Notes

- * During the face sealing operation the glass in this area (total 22 mm) may be disturbed. As the shape of the contour within this area may be either convex or concave the bulb should not be gripped within this region unless special precautions are taken (such as the use of resilient packing material).
- ** The socket for the B8H button base should not be rigidly mounted, it should have flexible leads and be allowed to move freely. The design of the socket should be such that the wiring cannot impress lateral strains through the socket contacts on the base.



31E12

12" RADAR CATHODE RAY TUBE Electrostatic Focus—Magnetic Deflection

GENERAL

The 31E12 is a 12" aluminised cathode ray tube having a long afterglow T6 or T7 aluminised screen suitable for radar PPI display. The tube has a substantially flat face.

RATING

| Heater Voltage (volts) | Vh | 6.3 |
|--------------------------------------|------------|-----|
| Heater Current (amps) | lh | 0.6 |
| Maximum Final Anode Voltage (kV) | Va2+4(max) | 12* |
| Minimum Final Anode Voltage (kV) | Va2+4(min) | 8 |
| Maximum First Anode Voltage (volts) | Va1(max) | 400 |
| Maximum Heater/Cathode Voltage (Heat | er | |
| Negative) (D.C.) (volts) | Vh-k(max) | 150 |

^{*} The maximum rating of 12kV is a Design Centre Rating. The Absolute Maximum of 14kV must not be exceeded.

INTER-ELECTRODE CAPACITANCES (pF)

| Grid/Earth | cg-E | 9 |
|----------------------------------|---------|------|
| Cathode/Earth | ck-E | 7 |
| Second and Fourth Anode/External | | |
| Conductive Coating | C-2+4 M | 1500 |

These Capacities include an Ediswan Clix holder CRT 92/7.

DIMENSIONS

| Maximum Overall Length | (mm) | 485 |
|---------------------------|-------|------|
| Maximum Diameter | (mm) | 307 |
| Maximum Neck Diameter | (mm) | 35.5 |
| Approximate Nett Weight | (lbs) | 113 |
| Approximate Packed Weight | (lbs) | 231 |

December, 1961

Issue 1, Page 1



31E12

12" RADAR CATHODE RAY TUBE

Electrostatic Focus—Magnetic Deflection


TYPICAL OPERATION

| $V_{a2}+4$ | 12 |
|------------------|--------------------------------------|
| Va1 | 300 |
| V _a 3 | 0 |
| Vg | 33—77 |
| 100 | 24 |
| | 50† |
| | 175† |
| | V _a 1 V _a 3 |

- † Persistence is defined as the time taken from the cessation of continuous excitation for the luminance to decay from 1 Foot-Lambert to approximately 1% of that value.
- * The T7 screen is liable to burn if a stationary or slowly moving spot is used even with low values of mean current.

The 31E12 is available with either a T6 Long Yellow Afterglow Screen or a T7 Very Long Orange Afterglow Screen.

BASE—Duodecal (B12A)



Viewed from free end of pins.

CAP-Cavity (CT8)

December, 1961

Issue 1, Page 2




31E12 12" RADAR CATHODE RAY TUBE Electrostatic Focus—Magnetic Deflection

CONNECTIONS

| Pin 1 | Heater | h |
|--------|-------------------------|------|
| Pin 2 | Grid | g |
| Pin 3 | No Pin | NP |
| Pin 4 | No Pin | NP |
| Pin 5 | No Pin | NP |
| Pin 6 | Third Anode | a3 |
| Pin 7 | Internal Connection | IC |
| Pin 8 | No Pin | NP |
| Pin 9 | No Pin | NP |
| Pin 10 | First Anode | a1 |
| Pin 11 | Cathode | k |
| Pin 12 | Heater | h |
| Сар | Second and Fourth Anode | a2+4 |

31EI2
12" RADAR CATHODE RAY TUBE
Electrostatic Focus—Magnetic Deflection



| * Ring Gauge (mm) | Distance from centre of Screen (mm) |
|----------------------|-------------------------------------|
| 280 | 93 ± 10 |
| 230 | 150 ± 9 |
| 180 | 191 ± 8 |
| 130 | 222 ± 7 |
| 80 | 249 ± 6 |
| 36 | 272 ± 3.5 |

All dimensions in mm



The 31E13 is a magnetically focused and deflected cathode-ray tube primarily designed for PPI applications. This aluminised tube has a 12" diameter flat face and is available with a T6 or T7 screen. It has a straight tetrode gun, and conforms to the British Service specification CV429.

RATINGS

| Heater voltage | V_h | 6.3 | V |
|---------------------------------|----------------------|-------|----|
| Heater current | l _h | 0.6 | Α |
| Maximum second anode voltage | $V_{a2(max)}$ | 15.5* | kV |
| Minimum second anode voltage | V _{a2(min)} | 9.0 | kV |
| Maximum first anode voltage | $V_{a1(max)}$ | 600* | V |
| Maximum heater/cathode voltage, | | | |
| heater negative (d.c.) | $V_{h-k(max)}$ | 150 | V |
| | | | |

^{*} The maximum ratings are absolute maximum values.

INTER-ELECTRODE CAPACITANCES**

| Grid/Earth | c _{g-E} | <8.0 | pF |
|---------------|------------------|------|----|
| Cathode/Earth | c _{k-E} | <8.0 | pF |

^{**} With holder capacity balanced out.

TYPICAL OPERATION

| Second anode voltage | V_{a2} | 15 | kV |
|--|----------------|------------|----|
| First anode voltage | V_{a1} | 300 | V |
| Grid bias for cut-off | Vg | -60 to -90 | V |
| Average peak/peak modulating voltage for modulation up to 50 μ A | | 24 | ٧ |
| Deviation of unfocused and undeflected spot from centre of screen | | <15 | mm |
| Maximum unfocused spot diameter for 50 μ | A beam current | 15 | mm |
| Maximum line width for $50\mu A$ beam curren | t | 0.5 | mm |
| Persistence of T6 screen (long yellow afterg | low) | 50‡ | S |
| Persistence of T7 screen (very long orange a | afterglow) | 200‡§ | S |


^{† 100} μ s pulse at 100 p/s. 100 μ s line scan 250 mm long.

August, 1962

Issue 1, Page 1

[‡] Persistence is defined as the time taken from the cessation of continuous excitation for the luminance to decay from 1 foot lambert to approximately 1% of that value.

[§] The T7 screen is liable to burn even at low values of beam current if operated with stationary or slow moving spot.




All dimensions in millimetres.

Cap

† Beginning of curvature point at which 36.1 dia. ring gauge is stopped.

| * Ring Gauge (mm) | Distance from centre of Screen (mm) |
|----------------------|-------------------------------------|
| 280 | 93+10 |
| 230 | 150 ± 9 |
| 180 | 191 <u>±</u> 8 |
| 130 | 222 ± 7 |
| 80 | 249± 6 |
| 36.1 | 272 ± 3⋅5 |



Second anode (a2)

CONNECTIONS

| Pin 1 | Heater (h) | Pin 10 | First anode (a1) |
|-------|--------------------------|--------|------------------|
| Pin 2 | Grid (g) | Pin 11 | Cathode (k) |
| Pin 6 | Internal Connection (IC) | Pin 12 | Heater (h) |

Anode cap in line with spigot $\pm 15^{\circ}$

Internal Connection (IC)

Pin 7

The 31E14 is a 14" diagonal rectangular tube with 70° magnetic deflection and low voltage electrostatic focusing. It is intended for use in television studio monitoring equipment.

RATINGS

| Heater voltage | V_h | 6.3 | V |
|---|------------------|-----------|----|
| Heater current | l _b | 0.3* | A |
| Maximum second and fourth anode voltage | $V_{a2,a4(max)}$ | 16** | kV |
| Minimum second and fourth anode voltage | $V_{a2,a4(min)}$ | 10 | kΥ |
| Maximum third anode voltage | $V_{a3(max)}$ | \pm 500 | V |
| Maximum first anode voltage | $V_{a1(max)}$ | 500 | V |
| Maximum heater/cathode voltage, | , | | |
| d.c. (heater negative) | $V_{h-k(max)}$ | 180 | V |
| Maximum peak heater/cathode voltage, | , | | |
| d.c. (heater negative) | Vh-k(pk)max | 400†‡ | V |

^{*} The cathode-ray tube heater should always be connected at the chassis end in a series heater chain.

INTER-ELECTRODE CAPACITANCES

| Grid/All other electrodes Cathode/All other electrodes | C _{g-all} | 9·0 7·0 | pF |
|---|--------------------|------------|----|
| Anode 2 and Anode 4/External conductive | C _{k-all} | 7-0 | ы |
| coating (approx) | Ca2,a4-M | 1,300 | pF |

[§] These capacitances include an AEI duodecal holder type CRT92/7.

TYPICAL OPERATION

| Second and fourth anode voltage | Va2.a4 | 12 | kV |
|---|-------------------------|----------------|----|
| First anode voltage | $V_{a2,a4}$ V_{a1} | 300 | V |
| Third anode voltage for focus (range) | V_{a3} | -300 to $+300$ | V |
| Grid bias voltage for cut-off of raster | Vg | -30 to -72 | V |
| Average peak to peak modulating voltage | | | |
| for modulation up to 150μA | | 24 | V |

Note

If this tube is operated at voltages in excess of 16 kV, x-ray radiation shielding may be necessary to avoid possible danger of personal injury from prolonged exposure at close range. The normal glass protective viewing window may provide such a safeguard. If the radiation measured in contact with this window does not exceed 0.5 milliroentegens per hour, the window will normally provide adequate protection.


August, 1962

Page 1, Issue 1

^{** 16}kV is a design centre rating, the absolute rating of 20kV must not be exceeded.

[†] Absolute rating.

[#] During a warming-up period not exceeding one minute.



All dimensions in millimetres. Not to be scaled.

Notes

- * During the face sealing operation the glass in this area (total 30 mm) may be disturbed. As the shape of the contour within this area may be either convex or concave the bulb should not be gripped within this region unless special precautions are taken (such as the use of resilient packing material).
- † Determined by reference gauge No. 12.

The 31F12 is an electrostatically focused and magnetically deflected cathode ray tube intended for use in large screen oscilloscopes. It has a 17" diagonal and a deflection angle of 70° . The grey glass face of the aluminised tube is rectangular and has a total light transmission at the centre of approximately 72%. A screen type T9 is employed which has a long orange afterglow.

RATINGS

| Heater voltage | V_h | 6.3 | V |
|---|----------------------|-------|----|
| Heater current | I _h | 0.6 | Α |
| Maximum second and fourth anode voltage | $V_{a2,a4(max)}$ | 16* | kV |
| Minimum second and fourth anode voltage | $V_{a2,a4(min)}$ | 12 | kV |
| Maximum third anode voltage | V _{a3(max)} | +700 | V |
| Maximum first anode voltage | V _{a1(max)} | 400 | V |
| Maximum heater/cathode voltage, | a. (a., | | |
| (d.c.) heater negative | $V_{h-k(max)}$ | 180 | V |
| Maximum peak heater/cathode voltage, | n K(max) | | |
| (d.c.) heater negative | Vh-k(pk)max | 400†‡ | V |

^{* 16}kV is a design centre rating, the absolute rating of 17.6kV must not be exceeded.

INTER-ELECTRODE CAPACITANCES

| Grid/All other electrodes | C _{g-all} | 9.0 | ρF |
|------------------------------|--------------------|-----|----|
| Cathode/All other electrodes | C _{k-all} | 6.5 | pF |

These capacitances include an AEI duodecal holder type CRT92/7.

TYPICAL OPERATION

| Second and fourth anode voltage | $V_{a2,a4}$ | 14—15 | kV |
|---|-----------------|----------------|----|
| First anode voltage | V _{a1} | 300 | V |
| Third anode voltage for focus (range) | V_{a3} | -100 to $+300$ | V |
| Grid bias voltage for cut-off of raster | Vg | -30 to -72 | V |
| Average peak to peak modulating voltage | | | |
| for modulation up to $150\mu A$ | | 24 | V |
| Centring magnet flux density | | 0—10 | G |
| Maximum distance of centre of centring | | | |
| field from reference line | | 56 | mm |
| Persistence of T9 screen | | 100§ | S |

[§] Persistence is defined as the time taken, from the cessation of continuous excitation, for the luminance to decay from 1 Foot Lambert to approximately 1% of that value.

Note


The T9 screen is liable to burn, even at low values of beam current, if operated with stationary or slow moving spot.

August, 1962

Page 1, Issue 1

[†] Absolute rating.

[‡] During a warming-up period not exceeding 1 minute.



All dimensions in millimetres. Not to be scaled.

Notes

- * During the face sealing operation the glass in this area (total 30mm) may be disturbed. As the shape of the contour within this area may be either convex or concave the bulb should not be gripped within this region unless special precautions are taken (such as the use of resilient packing material).
- † Determined by Reference Gauge No. 7.



31G12

CATHODE RAY TUBE

Indirectly heated—for large screen Oscilloscopes

TENTATIVE

BASE-B12A(7 Pin)



Viewed from free end of pins

CONNECTIONS

| Pin 1 | Heater | h |
|--------|-------------------------|-------|
| Pin 2 | Grid | g |
| Pin 3 | No Pin | NP |
| Pin 4 | No Pin | NP |
| Pin 5 | No Pin | NP |
| Pin 6 | Third Anode | a3 |
| Pin 7 | Internal Connection | IC |
| Pin 8 | No Pin | NP |
| Pin 9 | No Pin | NP |
| Pin 10 | First Anode | a1 |
| Pin 11 | Cathode | k |
| Pin 12 | Heater | h |
| Cap | Second and Fourth Anode | a2,a4 |



SHEED CATHOLIC DAY TURE CATHOLIC DAY TURE CATHOLIC DAY REPORTED AT SERVICE REPORT OF THE SAME OF THE S

7136



and the last section of the section of

The 31G12 is an electrostatically focused and magnetically deflected cathode-ray tube intended for use in large screen oscilloscopes. It has a 21" diagonal and a deflection angle of 90°. The grey glass face of the aluminised tube is rectangular and has a total light transmission at the centre of approximately 72%. A screen type T9 is employed which has a long orange afterglow.

RATINGS

| Heater voltage | Vh | 6.3 | V |
|---|----------------------|-----------|----|
| Heater current | l _b | 0.6 | A |
| Maximum second and fourth anode voltage | Va2,a4(max) | 16* | kV |
| Minimum second and fourth anode voltage | Va2,a4(min) | 12 | kV |
| Maximum third anode voltage | V _{a3(max)} | \pm 700 | V |
| Maximum first anode voltage | $V_{a1(max)}$ | 400 | V |
| Maximum heater/cathode voltage, | | | |
| d.c. (heater negative) | $V_{h-k(max)}$ | 180 | V |
| Maximum peak heater/cathode voltage, | , | | |
| d.c. (heater negative) | Vh-k(pk)max | 400†‡ | V |

^{* 16}kV is a design centre rating, the absolute rating of 17.6kV must not be exceeded.

† Absolute rating.

INTER-ELECTRODE CAPACITANCES

| Grid/All other electrodes | Cg-all | 9.0 | pF |
|------------------------------|--------------------|-----|----|
| Cathode/All other electrodes | C _{k-all} | 6.5 | pF |

These capacitances include an AEI duodecal holder type CRT92/7.

TYPICAL OPERATION

| Second and fourth anode voltage | $V_{a2,a4}$ | 14—15 | kV |
|--|-----------------|------------|----|
| First anode voltage | V _{a1} | 300 | V |
| Third anode voltage for focus (mean) | V_{a3} | +100 | V |
| Grid bias voltage for cut-off of raster | Vg | -30 to -72 | V |
| Average peak to peak modulating voltage | | | |
| for modulation up to 150μ A | | 24 | V |
| Centring magnet flux density | | 0—10 | G |
| Maximum distance of centre of centring field | | | |
| from reference line | | 56 | mm |
| Persistence of T9 screen | | 100§ | s |

 $[\]S$ Persistence is defined as the time taken from the cessation of continuous excitation for the luminance to decay from 1 Foot Lambert to approximately 1% of that value.


Note

The T9 screen is liable to burn, even at low values of beam current, if operated with a stationary or slow-moving spot.

August, 1962 Page 1, Issue 1

Tel: GERrard 9797

[‡] During a warming-up period not exceeding one minute.



All dimensions in millimetres.

Notes

- * During the face sealing operation the glass in this area (total 30 mm) may be disturbed. As the shape of the contour within this area may be either convex or concave the bulb should not be gripped within this region unless special precautions are taken (such as the use of resilient packing material).
- † Determined by reference line gauge No. 13.



APPLICATION NOTES ON VACUUM THERMAL DELAY SWITCHES

Vacuum Thermal Delay Switches find application in the delayed automatic switching required to protect certain types of thermionic valves or circuit elements, and may also be used for sequential switching operations not requiring precise timing.

The closing delay time after applying heater voltage lies between 30 and 90 seconds. In some cases the delay may be increased to a maximum of 180 seconds by a reduction of the heater voltage, achieved with resistor fitted preferably in the primary of the heater transformer. This is not, however, recommended, since it results in slower contact movement with reduced contact throw and pressure. The consequence of these effects is greater sensitivity to ambient temperature change and vibration, with a greater liability to intermittency at the moment of contact. Similarly the delay may be reduced by increase of the heater voltage provided that the increased emission from the heater produces no ill-effects. However, it should be noted that increases of more than 50 per cent. above the normal heater voltage rating will result in a significant reduction in life expectancy.

Where reactive circuits are switched or the contact current may exceed the rated maximum, and where the maximum switching delay time must be maintained under all conditions a secondary relay system should be operated by the thermal delay switch. This relay should be of the self-holding type and should when operated simultaneously break the switch heater supply and switch the main circuit.

The non-compensated switches will not be affected greatly by reasonable changes in ambient temperature but when consistent operation is required in the temperature range -40° C. to $+85^{\circ}$ C., a temperature compensated switch should be selected. This latter type of switch is unsuited to variation of the closing time by alteration of the heater voltage.

The heater should be neutral or positive with respect to the Moving Contact. Where the heater must be negative or where an A.C. voltage exists, the switch duty should be as low as possible since danger of ionic discharge increases with heater-contact voltage and contact current under these conditions.

December, 1961

issue 1, Page 1



DEPUTATION MOTES ON THERMAL DELAY SWITCHOLD WAS A STREET OF THE STREET

And the second of the second o



DLSI0

VACUUM THERMAL DELAY SWITCH

GENERAL

The DLS10 is a Vacuum Thermal Delay Switch with an AC switch rating of 6 amps at 250 volts, or 200 mA at 1,000 volts. It has a heater rating of 1.5 amps at 4 volts, and switch closure delay times of from 30 to 90 seconds, the switch being open when cold.

RATING

| Heater Voltage | (volts) | V_h | 4.0 |
|---|---------|-----------|-------|
| Heater Current | (amps) | lh | 1.5 |
| Minimum Delay Time | (secs) | tsd(min) | 30 |
| Maximum Delay Time | (secs) | tsd(max) | 90 |
| Maximum Switch Current at 250 volts r.m.s. (AC) | (amps) | I(rms)max | 6 |
| Maximum Switch Current at 1 kV r.m.s. (AC) | (mA) | (rms)max | 200 |
| | | | |
| DIMENSIONS | | | |
| Maximum Overall Length | (mm) | | 150 ← |
| Maximum Seated Height | (mm) | | 120 |
| Maximum Diameter | (mm) | | 45 |
| Approximate Nett Weight | (ozs) | | 1 1/2 |
| Approximate Packed Weight | (ozs) | | 21/2 |

MOUNTING POSITION—Unrestricted

Indicates a change



EDISWAN

DLSI0

VACUUM THERMAL DELAY SWITCH

OPERATION

See "Application notes on Vacuum Thermal Delay Switches"

BASE—British 4 pin (B4)



Viewed from free end of pins

VALVE HOLDER-Ediswan Clix VH42/4, VH300/4

CONNECTIONS

| Pin 1 | Fixed Contact | cf |
|-------|----------------|----|
| Pin 2 | Moving Contact | cm |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |



DLS15 & DLS16

DLSI5 & DLSI6 VACUUM THERMAL DELAY SWITCHES

GENERAL

The DLS.15 and DLS.16 are designed for similar applications as the DLS.10 but are intended to fill the demand for a delay switch of reduced dimensions.

RATING

DLS.15 DLS.16

6.3

Filament Voltage (volts) V_f 4

Filament Current (amps) I_f .75 .48

Delay Time (secs) min. 30 - max. 90

Maximum Mean Current (Low Voltage Rating) I_{pk} 5 amps @ 240 v.

Maximum Mean Current (High Voltage Rating) I_{Dk} 100 m/a @ 1,000 v.

DIMENSIONS

Maximum Overall Length (mm) 60 N.I.P. •
Maximum Diameter (mm) 32
Maximum Height (mm) 60 65

. Not Including Pins

MOUNTING POSITION - Unrestricted.

BASE

DLS.15
B.V.A. 4 pin
International Octal Base

Pin 1 - Fixed Contact Pin 1 - Pin 2 - Moving Contact Pin 2 - Filament

Pin 3 - Filament Pin 3 - - Pin 4 - Woving Contact Pin 5 - - Pin 5 - Pin 5 - Pin 5 - Pin 5 - - Pin 5 - Pin

Pin 6 - Fixed Contact Pin 7 - -Pin 8 - Filament

IMPORTANT NOTE


To prevent any potential difference existing between the moving contact and heater, the two should be tied externally.

December, 1961



EDISWAN

DLSI5 & DLSI6
VACUUM THERMAL DELAY SWITCHES



December, 1961



VACUUM THERMAL DELAY SWITCH

GENERAL

The DLS19 is a miniature-based Vacuum Thermal Delay Switch with an AC switch rating of 2 amps at 250 volts, or 100 mA at 500 volts. It has a heater rating of 0.5 amps at 6.3 volts, and switch closure delay times of from 35 to 70 seconds, the switch being open when cold. It is compensated to maintain a constant closure delay time in the ambient temperature range— 40°C to $+85^{\circ}\text{C}$.

RATING

| Heater Voltage | (volts) | V _h | 6.3 |
|---|---------|------------------|-----|
| Heater Current | (amps) | lh | 0.5 |
| Minimum Delay Time | (secs) | tsd(min) | 35 |
| Maximum Delay Time | (secs) | tsd(max) | 70 |
| Maximum Switch Current at 250 volts r.m.s. (AC) | (amps) | l(rms)max | 2 |
| Maximum Switch Current at 500 volts r.m.s. (AC) | (mA) | l(rms)max | 100 |
| Maximum Switch Current at | | (, , | |
| 250 volts (DC) | (amps) | I(DC)max | 1 |
| Maximum Heater to Contact Voltage | (volts) | V _{h-c} | 200 |
| DIMENSIONS | | | |
| Maximum Overall Length | (mm) | | 54 |
| Maximum Seated Height | (mm) | | 48 |
| Maximum Diameter | (mm) | | 19 |
| Approximate Nett Weight | (ozs) | | 1 |
| Approximate Packed Weight | (ozs) | | 1/2 |
| | | | |

MOUNTING POSITION—Unrestricted



EDISWAN

DLS19

VACUUM THERMAL DELAY SWITCH

OPERATION

See "Application notes on Vacuum Thermal Delay Switches"

BASE—B7G



Viewed from free end of pins

VALVE HOLDER—Ediswan Clix VH337/701 and VH437/701 series

CONNECTIONS

| Pin 1 | Heater | n |
|-------|-----------|-----------|
| Pin 2 | No Conne | ection NC |
| Pin 3 | Moving C | ontact cm |
| Pin 4 | Fixed Con | tact cf |
| Pin 5 | No Conne | ection NC |
| Pin 6 | No Conne | ection NC |
| Pin 7 | Heater | h |
| | | |

December, 1961 Issue 1, Page 2



VACUUM THERMAL DELAY SWITCH

GENERAL.

The DLS23 is a Vacuum Thermal Delay Switch with an AC switch rating of 5 amps at 240 volts, or 100 mA at 1,000 volts. It has a heater rating of 1 amp at 2.5 volts and a switch closure delay time of from 30 to 90 seconds, the switch being open when cold.

RATING

| Heater Voltage | (volts) | ٧h | 2.5 |
|---|---------|-----------|----------------|
| Heater Current | (amps) | lh | 1.0 |
| Minimum Delay Time | (secs) | tsd(min) | 30 |
| Maximum Delay Time | (secs) | tsd(max) | 90 |
| Maximum Switch Current at 240 volts r.m.s. (AC) | (amps) | l(rms)max | 5 |
| Maximum Switch Current at 1 kV r.m.s. (AC) | (mA) | l(rms)max | 100 |
| DIMENSIONS | | | |
| Maximum Overall Length | (mm) | | 65 |
| Maximum Seated Height | (mm) | | 60 |
| Maximum Diameter | (mm) | | 32 |
| Approximate Nett Weight | (ozs) | | 1 |
| Approximate Packed Weight | (ozs) | | $2\frac{1}{2}$ |

MOUNTING POSITION—Unrestricted

December, 1961



VACUUM THERMAL DELAY SWITCH

OPERATION

See "Application Notes on Vacuum Thermal Delay Switches"

BASE-International Octal



Viewed from free end of pins

VALVE HOLDER

Ediswan Clix VH330/8, VH238/8, VH248/8

CONNECTIONS

| Pin 1 | No Connection | NC |
|-------|----------------|----|
| Pin 2 | Heater | h |
| Pin 3 | Heater | h |
| Pin 4 | No Connection | NC |
| Pin 5 | Fixed Contact | cf |
| Pin 6 | No Connection | NC |
| Pin 7 | Moving Contact | cm |
| Pin 8 | No Connection | NC |

December, 1961

Issue 1, Page 2

Electronic Components Division
Tel.: GERrard 9797



VACUUM THERMAL DELAY SWITCH REVERSE ACTION

GENERAL

The DLS24 is a Miniature based Reverse Action Vacuum Thermal Delay Switch having AC switch ratings of 1 amp at 240 volts or 200 mA at 500 volts. It has a heater rating of 0.5 amps at 6.3 volts and a switch opening delay time of from 30 to 90 seconds, the switch being closed when cold. It is compensated to maintain a constant opening delay time in the ambient temperature range —40°C to -+85°C.

RATING

| Heater Voltage (volts) | Vh | 6.3 |
|--|------------------|------|
| Heater Current (amps) | lh | 0.5 |
| Minimum Delay Time (secs) | tsd(min) | - 30 |
| Maximum Delay Time (secs) | tsd(max) | 90 |
| Maximum Switch Current at 240 volts (r.m.s.) (AC) (amps) | I(r.m.s.) max | 1.0 |
| Maximum Switch Current at 500 volts (r.m.s.) (AC) (mA) | l(r.m.s.) max | 200 |
| Maximum Heater to Contact Voltage (volts) | V _{h-c} | 200 |
| Heater Resistance (cold) (ohms) | rh (min) | 1.3 |
| | , | |
| DIMENSIONS | | |
| Maximum Overall Length | (mm) | 54 |
| Maximum Seated Height | (mm) | 48 |
| Maximum Diameter | (mm) | 19 |
| Approximate Nett Weight | (ozs) | 1 |
| Approximate Packed Weight | (ozs) | 1 |
| | | |

MOUNTING POSITION—Unrestricted

OPERATION

See 'Application notes on Vacuum Thermal Delay Switches.'

December, 1961



EDISWAN

DLS24

VACUUM THERMAL DELAY SWITCH REVERSE ACTION

BASE-B7G



Viewed from free end of pins

VALVE HOLDER—Ediswan Clix VH337/702 and VH437/702 series.

CONNECTIONS

| Pin 1 | Heater | h |
|-------|----------------|-----|
| Pin 2 | No Connection | NC |
| Pin 3 | Moving Contact | cm |
| Pin 4 | Fixed Contact | cf |
| Pin 5 | No Connection | NC |
| Pin 6 | No Connection | NC. |
| Pin 7 | Heater | h |

Electronic Components Division Tel.: GERrard 9797



24T12

VACUUM THERMAL DELAY SWITCH REVERSE ACTION TENTATIVE

GENERAL

The 24T12 is a Vacuum Thermal Delay Switch with an a.c. switch rating of 1 amp at 240 volts. It has a filament rating of 0.5 amps at 6.3 volts and switch closure delay times of from 15 to 45 seconds, the switch being closed when cold.

RATING

| Filament Voltage | Vf | 6.3 | ٧ |
|---|-----------------------|-----|---|
| Filament Current | If | 0.5 | A |
| Maximum Switch Current at 240 volts r.m.s. (A.C.) | I _{(rms)max} | 1.0 | Α |
| Maximum Switch Voltage at 200 mA | | 500 | V |
| Minimum Switch Closing Time | tsd(min) | 15 | S |
| Maximum Switch Closing Time | tsd(max) | 45 | S |

DIMENSIONS

| Maximum Overall Length | 54.5 mm |
|------------------------|---------|
| Maximum Diameter | 19·0 mm |
| Maximum Seated Height | 47.5 mm |

MOUNTING POSITION—Unrestricted

OPERATION

See "Application notes on Vacuum Thermal Delay Switches".

BASE-B7G



Viewed from free end of pins

December, 1961

ADVANCE DATA, Page 1



24T12

VACUUM THERMAL DELAY SWITCH REVERSE ACTION

TENTATIVE

CONNECTIONS

| Pin 1 | Heater | h |
|-------|----------------|----|
| Pin 2 | No Connection | NC |
| Pin 3 | Moving Contact | cm |
| Pin 4 | Fixed Contact | cf |
| Pin 5 | No Connection | NC |
| Pin 6 | No Connection | NC |
| Pin 7 | Heater | h |

Electronic Components Division
Tel.: GERRARD 9797



TELEPHONE LINE PROTECTOR

GENERAL

The DRG36/2 is a Neon/Helium filled Telephone Line Protector. It is intended for use in discharging limited surges on a pair of Telephone lines, and is especially suitable for use with underground lines.

RATING

| Vign(min) | 130 |
|-------------|----------------------|
| 1811(11111) | 250 |
| | 1-0 |
| isur(max) | 7.5 |
| (| |
| | 150 |
| | 5* |
| | Vign(min) isur(max) |

* To ensure regularity of striking, each tube contains a radioactive source for ionising purposes.

DIMENSIONS

| Maximum Overall Length | (mm) | 158 |
|---------------------------|-------|-----|
| Maximum Diameter | (mm) | 35 |
| Maximum Seated Height | (mm) | 133 |
| Approximate Nett Weight | (ozs) | 21 |
| Approximate Packed Weight | (ozs) | 31 |

December, 1961

TELEPHONE LINE PROTECTOR

MOUNTING POSITION—Unrestricted.

TYPICAL OPERATION

One protector is installed at each end of a telephone loop. The two line electrodes are connected across the pair of lines and the single electrode is earthed in the most suitable way depending on the terrain. At normal carrier plus signal voltages the tube is inert and imposes no load upon the line.

A surge of voltage from an external source (e.g. parallel power lines, electric storms, etc.) induced on the telephone lines causes the device to strike within microseconds thus providing a low impedance path to earth until the surge is cleared. Clearance of both lines is simultaneous since each is connected to the same tube. After clearing a surge the tube again becomes inert until another surge is induced.

Small surges are discharged through a red neon glow discharge carrying up to 0.5 amp.

Larger surges cause the tungsten arc to strike and currents of 0.5A to 15A are borne without damage. Larger surges giving currents greater than 15 Amps will be cleared but, if prolonged, may damage or destroy the tube.

Limiting impedance (provided the earthing is efficient) is that of the telephone line between the point where the surge strikes and the Telephone Line Protector (i.e. 300 ohms maximum for a typical loop).

When used on overhead lines the tube may be placed in parallel with a spark gap which will discharge the very heavy surges due to lightning strokes preserving the tube for the clearing of more limited surges.



TELEPHONE LINE PROTECTOR

TOP CAP-Thumb Screw Terminal 2BA.

BASE-Edison Screw.

CONNECTIONS

Screw Centre

Screw Thread

Тор Сар


Line Electrode 1

Line Electrode 2

Earth Electrode



TELEPHONE LINE PROTECTOR




6-22 DR6 36/2-90-1

All dimensions in m.m.



DRG36/2 TELEPHONE LINE PROTECTOR

AVERAGE CHARACTERISTIC CURVES: V,P/I




December, 1961



TELEPHONE LINE PROTECTOR

AVERAGE CHARACTERISTIC CURVES : V,P/I



December, 1961



6HI HEXODE Indirectly heated—for parallel operation

GENERAL

The 6H1 is a miniature based hexode intended for use as a frequency changer with a separate triode oscillator, and will operate up to a frequency of 20 Mc/s. It is also suitable for use as a gated amplifier, and may be used in equipment having AC or DC powered parallel connected heater chains.

RATING

| Heater Voltage | (volts) | Vh | 6.3 |
|---|---------|----------------------|--------|
| Heater Current | (amps) | lh. | 0.2 |
| Maximum Anode Voltage | (volts) | V _{a(b)max} | 550† |
| Maximum Operating Anode Voltage | (volts) | V _{a(max)} | 300 |
| Maximum Screen Voltage | (volts) | Vg2,4(b)max | 400† |
| Maximum Operating Screen Voltage | (volts) | Vg2,4(max) | 300 |
| Maximum Anode Dissipation Maximum Screen | (watts) | Pa(max) | 1-0 |
| Dissipation | (watts) | Pg2+4(max) | 0.7 |
| Mutual Conductance | (mA/V) | 8m | 2.1* |
| * Measured at $V_a = 250 \text{ V}$; † $I_a = 0$. | | = 100 V ; Vg1 = | –1·8V. |

All Maximum Values quoted are absolute.

INTER-ELECTRODE CAPACITANCES (pF)

| Anode/Grid 1 | ca-81 | 0.06 |
|--------------|---------|------|
| Anode/Earth | ca-E | 9.25 |
| Grid 1/Earth | cg1-E | 4.3 |
| Grid 3/All | cg3-all | 4.9 |

[&]quot;Earth" denotes all earth potential electrodes, shields and heater connected to the cathode.

These capacities are measured cold with a metal screening can fitted to the valve.

Indicates a change

✓
Issue 1, Page 1

6HI HEXODE Indirectly heated—for parallel operation

| DII | MEI | VSIC | SNC |
|-----|-----|------|-----|
|-----|-----|------|-----|

| Maximum Overall Length | (mm) | 54.5 ← |
|---------------------------|-------|--------|
| Maximum Diameter | (mm) | 19-0 |
| Maximum Seated Height | (mm) | 47.5 ← |
| Approximate Nett Weight | (ozs) | 14 |
| Approximate Packed Weight | (ozs) | 1/2 |

MOUNTING POSITION—Unrestricted.

| TYPICAL OPERATION- | requency | Changer | |
|--|-------------|----------|--------|
| Anode Voltage | (volts) | Va | 250 |
| Screen Voltage | (volts) | Vg2+4 | 100 |
| Grid 1 Bias Voltage | (volts) | Vg1 | -2.2 ← |
| Anode Current (approx) | (mA) | la | 2.3* ← |
| Screen Current (approx) | (mA) | lg2+4 | 2.7* ← |
| Conversion Conductance | $(\mu A/V)$ | gc | 560↑ ← |
| Valve Anode Resistance (δν _a /δi _a) | (ΜΩ) | ra | 1.0 ← |
| Peak Heterodyne Voltage | (volts) | Vhet(pk) | 12 ← |
| Grid 3 Resistor | $(k\Omega)$ | Rg3 | 47* |
| | | | |

 Grid 3 connected in parallel with the grid of the oscillator valve and biased by grid current through the Grid 3 resistor.

Measured with an anode circuit of low dynamic impedance.

Indicates a change

✓
Issue 1, Page 2



6HI HEXODE Indirectly heated—for parallel operation

BASE-B7G



Viewed from free end of pins

VALVE HOLDER—Ediswan Clix VH337/7, VH437/7 and VH17/7 series.

CONNECTIONS

| Pin 1 | Grid 1 | 81 |
|-------|-------------------|-------|
| Pin 2 | Cathode | k |
| Pin 3 | Heater | h |
| Pin 4 | Heater | h |
| Pin 5 | Anode | a |
| Pin 6 | Grid 3 | g3 |
| Pin 7 | Grid 2 and Grid 4 | g2+g4 |
| | | |

Indicates a change



6HI HEXODE

Indirectly heated-for parallel operation

AVERAGE CHARACTERISTIC CURVES:


gc,la,lg2,lg3,lg0/Vhet(pk) Heterodyne injected into g3

 $V_a = 250V$

 $V_{g2} = 100V$ $Z_L = 49k\Omega$

 $V_g3 = Self Bias$ $R_g3 = 47k\Omega$

 $\begin{array}{lll} V_{g1}=-2\cdot 2V & Z_L=49k\Omega & R_{g3}=47k\Omega \\ Note: \ g3 \ is \ connected \ in \ parallel \ with \ the \ grid \ of \ an \ external \end{array}$





22MI

GLOW MODULATOR

GENERAL

The 22M1 is a Glow Modulator with a cold cathode. It is intended for use as a modulated light source in facsimile equipment.

RATING

| Maximum Striking Voltage | | 225 | V |
|------------------------------|----------|-----|----|
| Maximum Peak Current | lpk(max) | 75 | mA |
| Maximum Mean Current | lav(max) | 35 | mA |
| Maximum Voltage Drop at 30mA | 3 1 | 150 | V |

DIMENSIONS

| Maximum Overall Length | 78 r | nm |
|-------------------------|------|----|
| Maximum Diameter (base) | 34 г | mm |
| Maximum Seated Height | 64 1 | mm |

MOUNTING POSITION—Unrestricted

CHARACTERISTICS

| Approximate light output at 30mA | 0.13 cd |
|---|---------------|
| Luminance | 60 cd/sq. in. |
| Average diameter of light area on screen normal to valve axis and 20mm from end of bulb | 25 mm |
| Diameter of light source (approx.) | 1.3 mm |



22MI

GLOW MODULATOR

BASE—International Octal (102)



Viewed from free end of pins.

CONNECTIONS

| Pin 1 | No Pin | NP |
|-------|---------|----|
| Pin 2 | No Pin | NP |
| Pin 3 | Cathode | k |
| Pin 4 | No Pin | NP |
| Pin 5 | No Pin | NP |
| Pin 6 | No Pin | NP |
| Pin 7 | Anode | a |
| Pin 8 | No Pin | NP |



HIGH VACUUM CONTROL DIODE

Directly heated tungsten filament—for use as the controlling element in stabiliser circuits

| RATING | | |
|--------------------------------------|----------------|-----|
| Approximate Filament Voltage (volts) | v _f | 4.0 |
| Approximate Filament Current (amps) | If | 0.8 |
| Maximum Anode Current (mA) | Ia(max) | 3.0 |
| Maximum Anode Voltage (volts) | Va(max) | 100 |
| | | |
| DIMENSIONS | | |
| Maximum Overall Length (mm) | | 80 |
| Maximum Diameter (mm) | | 32 |
| Maximum Seated Height (mm) | | €7 |
| Approximate Nett Weight (ozs) | | 11 |
| Approximate Packed Weight (ozs. |) | 21 |
| | | |
| MOUNTING POSITION - Unrestric | cted. | |
| | | |
| | | |



HIGH VACUUM CONTROL DIODE

Directly heated tungsten filament—for use as the controlling element in stabiliser circuits


| TYPICAL OPERATION | Ī | | |
|---------------------------|--------------|------------------|----------|
| Saturated Anode (| Current (mA) | Ia | 2.0 |
| Minimum Anode Vol | tage (volts) | Va(min) | 20 |
| Approximate Filam (volts) | ment voltage | Vf | 4.0 |
| Approximate Filam (amps) | ment current | If | 0.8 |
| | | | |
| BULB Clear | | | |
| BASE International | Octal (108) | | |
| | 4 | 3 | |
| | 300 | 06) | |
| | 120 | 07 | |
| | 60 | 0 ₈ / | |
| | | | |
| | | | |
| | Viewed fr | com free end | of pins. |
| CONNEXIONS | | | |
| Pins 1, 2, 4 | Filament | | f |
| Pin 3 | Blank | | - |
| Pin 5 | Anode | | а |
| Pins 6, 7, 8 | Filament | | f |
| | | | |

Electronic Components Division
Tel.: GERRARD 9797



HIGH VACUUM CONTROL DIODE Directly heated tungsten filament—for use as the controlling element in stabiliser circuits


AVERAGE CHARACTERISTIC CURVES: Ia/Vf





HIGH VACUUM CONTROL DIODE Directly heated tungsten filament—for use as the controlling element in stabiliser circuits

AVERAGE CHARACTERISTIC CURVES: Ia/I



EDISWAN



CONDENSED DATA ON OBSOLETE TYPES BARRETTERS

| Туре | Volts | Current (A) | Base | Overall Length mm | Max. Dia. mm | Remarks |
|-----------|---------|-------------|-------|-------------------------|--------------------|---------------|
| BU.10 | 50-80 | 0.117-0.143 | 4 Pin | 105 N.I.P. | 58 | Boller Set |
| BU.29/4 | 2.5-6.0 | 0.27 -0.30 | 10 | 103 14.1.1 | 30 | 301105.038 |
| BU.30/2 | 1-3 | 0.27 -0.33 | ES | 85 | 32 | 25,00,00 |
| BU.30/4 | 2.5-6 | 0.27 -0.33 | ES | 100 | 32 | 8 12 1 124 |
| BU.30/6 | 3-9 | 0.27 -0.33 | ES | 90 | 30 | FOR U. |
| BU.30/6A | 3-9 | 0.27 -0.33 | 10 | 90 | 30 | 1 007 13 |
| BU.30/8 | 4-12 | 0.27 -0.33 | ES | 100 | 32 | Bootering |
| BU.30/10 | 6-14 | 0.27 -0.33 | ES | 115 | 32 | silter of |
| BU.30/12 | 6-18 | 0.27 -0.33 | ES | 100 | 32 | PERMIT SEE |
| BU.30/50 | 25-75 | 0.27 -0.33 | ES | 120 | 38 | 5-HW 198 |
| BU.30/50A | 25-75 | 0.27 -0.33 | 4 Pin | 120 | 38 | AA6601 115 |
| BU.30/50B | 25-75 | 0.27 -0.33 | 3 Pin | 120 | 38 | 051007.01 |
| BU.30/110 | 85-170 | 0.27 -0.33 | ES | 240 | 46 | COUNTY OF |
| BU.35/14 | 10-18 | 0.315-0.385 | ES | 115 | 38 | 100-13 |
| BU.35/80 | 40-120 | 0.315-0.385 | ES | 145 | 58 | birdi ba |
| BU.40/8 | 4-12 | 0.36 -0.44 | ES | 125 | 32 | 85-manua |
| BU.43/30 | 15-45 | 0.387-0.473 | ES | 105 | 32 | WAT BEAULI |
| BU.47/6 | 3_9 | 0.323-0.517 | ES | 100 | 32 | 6 W |
| BU.50/8 | 4-12 | 0.45 -0.55 | ES | 125 | 32 | 06 1 |
| BU.50/24 | 12-36 | 0.45 -0.55 | 3 Pin | 95 N.I.P. | 32 | Centre-tapped |
| BU.50/40 | 25-50 | 0.45 -0.55 | ES | 120 | 32 | 1805 08 |
| BU.60/120 | 80-150 | 0.55 -0.65 | ES | 170 | 64 | IN FORE US |
| BU.63/30 | 15-45 | 0.567-0.693 | 4 Pin | 110 N.I.P. | 53 | 75 BOT U. |
| BU.65/10 | 6-14 | 0.585-0.715 | ES | 107 | 32 | et Ett Lie |
| BU.65/14 | 9-20 | 0.585-0.715 | ES | 105 | 32 | FILE DE |
| BU.70/8 | 4-12 | 0.63 -0.77 | 3 Pin | 75 N.I.P. | 32 | Centre-tapped |
| BU.70/12 | 8-16 | 0.63 -0.77 | 3 Pin | 80 N.I.P. | 32 | Centre-tapped |
| BU.70/16 | 10-21 | 0.63 -0.77 | 3 Pin | 80 N.I.P. | 32 | Centre-tapped |
| BU.70/22 | 16-38 | 0.63 -0.77 | 3 Pin | 90 N.I.P. | 38 | Centre-tapped |
| BU.70/28 | 16-38 | 0.63 -0.77 | 3 Pin | 100 N.I.P. | 32 | Centre-tapped |
| BU.70/35 | 20-45 | 0.63 -0.77 | 3 Pin | 100 N.I.P. | 38 | Centre-tapped |
| BU.78/10 | 8-14 | 0.72 -0.9 | B4 | 75 N.I.P. | 32 | Centre-tappe |
| BU.78/10X | 5-15 | 0.78+5% | 4 Pin | 90 N.I.P. | 38 | Centre-tappe |
| BU.80/21 | 12-30 | 0.72 -0.88 | ES | 135 | 38 | |
| BU.85/5 | 4-8 | 0.765-0.935 | ES | 105 | 32 | |

December, 1961



Issue 1, Page 2



CONDENSED DATA ON OBSOLETE TYPES BARRETTERS

| Туре | Volts | Current (A) | Base | Overall Length mm | Max. Dia. mm | Remarks |
|----------------|---------|--------------|--------|--|--------------------|--------------|
| | | | | | | |
| BU.85/8 | 4-12 | 0.765-0.935 | ES | | 32 | 10 7 48 |
| BU.90/100 | 50-150 | 0.810 -0.990 | ES | | 64 | - Williams |
| BU.100/06 | 0.4-0.8 | 0.9 -1.1 | MES | | 26 | 2,000 |
| BU.100/3 | 1.5-4.5 | 0.9 -1.1 | ES | | 32 | h U 12 |
| BU.100/4 | 2-6 | 0.9 -1.1 | ES | | 32 | arot dis |
| BU.100/6 | 3-9 | 0.9 -1.1 | ES | | 32 | auto La |
| BU.100/8 | 4-12 | 0.9 -1.1 | | 96 | 32 | 3 0b.W4 |
| BU.100/10 | 5-15 | 0.9 -1.1 | | 115 | 32 | 0,506.00 |
| BU.100/11 | 6-16 | 0.9 -1.1 | | 122 | 32 | F1,04,1/8 |
| BU.100/14 | 7-20 | 0.9 -1.1 | ES | 125 | 38 | bullion Me |
| BU.100/14A | 7-20 | 0.9 -1.1 | 3 Pin | 120 N.I.P. | 38 | A GO DILLYS |
| BU.100/20 | 15-30 | 0.9 -1.1 | ES | 100 | 38 | BURLUE, DA |
| BU.115/22 | 11-31 | 1.03 -1.26 | 3 Pin | 105 N.I.P. | 38 | Centre-tappe |
| BU.130/7 | 4-10 | 1.17 -1.43 | ES | 115 | 32 | amati.UB |
| BU.133/110 | 60-160 | 1.2 -1.46 | ES | 315 | 64 | CONTO LA |
| BU.140/28 | 18-35 | 1.26 -1.54 | 4 Pin | 115 N.I.P. | 64 | etc. (28 |
| BU.150/160 | 80-240 | 1.275-1.725 | ES | 320 | 90 | 200 |
| BU.170/28 | 15-40 | 1.53 -1.87 | 3 Pin | 110 N.I.P. | 38 | Centre-tappe |
| BU.180/5 | 3-7 | 1.62 -1.98 | MO | 75 N.I.P. | 32 | a statute |
| BU.190/24 | 15-34 | 1.71 -2.09 | 3 Pin | 120 | 38 | Centre-tappe |
| BU.200/7 | 4-10 | 1.8 -2.2 | 4 Pin | 120 | 45 | Date In |
| BU.200/14 | 8-20 | 1.8 -2.2 | 3 Pin | 100 N.I.P. | 32 | Centre-tappe |
| BU.200/20 | 11-29 | 1.8 -2.2 | ES | 130 | 38 | 00108.01 |
| BU.215/75 | 50/100 | 1.9 -2.3 | ES | 280 | 64 | ortes Les |
| BU.250/7 | 4-10 | 2.25 -2.75 | 4 Pin | 125 N.I.P. | 38 | 27/26/12 |
| BU.280/20 | 10-30 | 2,52 -3.08 | 3 Pin | 130 N.I.P. | 58 | 810% U.S. |
| BU.350/55 | 40-80 | 3.15 -3.85 | Speci. | 290 | 90 | ST 9X-US |
| BU.350/55/1 | 40-80 | 3.15 -3.85 | GES | 300 Apprx. | 90 | 31 37 48 |
| BU.400/6 | 3-9 | | ES | 145 | 51 | |
| BU.600/6 | 3_9 | | ES | 150 | 58 | 85.00.06 |
| BU.800/6 | 3-9 | 7.2 -8.8 | ES | 145 | 58 | LENOS US |
| 22.000-27 | | 5 1 1 2 | | 1.15- 25-1 | -8 | SNETUS |
| - ACC 81-11778 | | | | 28 5 | | KEIT 97.124 |
| | | | | 10 July 23 July 20 Jul | | 11103 U.S |
| | | 107 | | P.O. 2010 | | 8188.06 |

December, 1961



CONDENSED DATA ON OBSOLETE TYPES SPECIAL PURPOSE VALVES

| | 7.3 Pa, 25 W; Vg2(max) 250 volts; Pg2, 3.0 W | 1.7 \(\mu, 73 \); \(\mathrm{r}_a\), 43,000 ohms |
|---------------------------|--|---|
| gm | 7.3 | 1.7 |
| Va(max) (volts) | 200 | 250 |
| Ih (amps) | 1.2 | 0.58 |
| V _h (volts) | 6.3 | 4.0 |
| Class | Audio Beam Tetrode | V339 Voltmeter Triode |
| Туре | 11E1 | V339 |

| | | Peak | Main Gap | Pulse | Repetition | Trigger | Line & Load |
|------|-----------|--------|---------------------|----------|------------|---------|-------------|
| Туре | Class | Output | Voltage | Duration | Frequency | Voltage | Impedance |
| | | (kW) | (kV _{pk}) | (sn) | (P.P.S.) | (kVpk) | (swho) |
| 2482 | Trigatron | 150 | 7.2 | 0.5 | 1200 | 3.5 | 88 |
| 24D4 | Trigatron | 250 | -16.0 | 2.0 | 400 | 3.8 | 250 |



COMPRESSED AND AND DESCRIPTION OF TABLES

-