Ministry of Supply (S.R.D.E.) VALVES ELECTRONIC CV 2422

Specification MOS/CV 2422 Issue 1 dated 24.6.57 To be read in conjunction with K1001, ES1409 and ES448	Security Specification Valve Unclassified Unclassified				
Type of Valve Velocity-modulated coax line oscillator with expression of the control of the cont	У	Marking See K1001/4			
Rating Heater voltage (V)	6.3 <u>+</u> 5%	Note A	Base BS448/B7G Connections		
Heater current (Nom.) Grid voltage Vg1 Resonator voltage VRes Screen voltage Vg2 (V)	0.26 -30 to -50 312 <u>+</u> 3% 75 to 350 Nom. 125	A B C	Pin Electrode 1 Grid g1 2 Cathode k 3 Heater h 4 Heater h		
Anode voltage Va (V) Power output (min.) (W)		D E	5 Anode a 6 Resonator Res 7 Screen grid g2		
Mechanical Tuning range (min.) (cms) Electronic Tuning range (min.) (Mc/s) Magnetic Field (min.) (Oersteds) Maximum resonator dissipation (W) Maximum anode dissipation (WA) Maximum cathode current (MA) Maximum bulb temperature (opposite anode)	3 1,300 10 15 100	F	<u>Dimensions</u> See drawing, page 4		

NOTES

- В.
- C.
- D.

- A.C. frequencies above 65 c/s must not be used. At λ = 6.5 cms. At other frequencies V_{Res} varies as f^2 . Varied to maintain I_k constant. Operation with V_a = V_{Res} may result in increased noise in the output. Within range 6.2 to 6.8 cms. With Jessops magnet type 9501, Alcomax III, minimum flux 1300 Oersteds. All voltages are quoted with respect to cathode, (Heater voltage excepted.) excepted.)

TESTS

To be performed in addition to those applicable in K.1001

	Test Conditions					Test	Limits Min. Max.		No. Tested	Notes		
十	Ţ	/h (V)	V _{g1} (V)	Ik	V _{g2} (V)	VRes	λ		3474110	Make	resteu	
1	_		(₹)	(mA	(<u>v</u>)	(♥)	(cms)					
_	_	5.3		-	-	-	 			0.30	100%	
	-	5.3	-40		Adjust	312	<u> </u>	v_{g2} (v)	90	200	100%	1
		5-3		50	Value found in Test 'b'	350	-	I _{g2} (mA)	-	4	100%	1
	1 6	5•3	-4 0	50	Adjust	280 to 305	6.8	(1) Power output (mW) (2) Electronic tuning range between half power points (Mc/s)	300		100%	1,2,3
	e 6	5-3	-40	50	As in Test'd' (1)	As in Test 'd' (1) with 20V peak to peak A.C. superim- posed	6.8	Frequency deviation (Mc/s peak to peak)	2.0	3•2	50%	1,4
	6	. 3	-40	50	Adjust	335 to 365	6.2	(1) Power output (mW) (2) Electronic tuning range between half power points (Mc/s)	300 3	1	100% 100%	1,2,3
	3 6	• 3	-40	-	As in Test Y'(1)	As in Test 'f' (1) with 20V peak to peak A.C. superim- posed	6.2	Frequency deviation (Mc/s peak to peak)	2.6	4.0	50%	1,4
ì	16	• 3	-40	50	Adjust	330	-	Life Test (1) Life Test End Point (100 hrs.)	-	-	Note 8	1,6
	6	• 3	-40	50	Contin- uously adjusted through- out test.	330	-	Life Test (2) Life Test End Point (4,300 hrs. min.)	-	-		1,7

CV 2422/1/2

NOTES

- . With Va at $V_{\rm Res}$ + 15 volts and a magnetic field of 1,500 Oersteds maximum.
- 2. The valve to be operated in an approved circuit consisting of 2" x 1" waveguide (WG12) with the valve mounted in the centre of the broad face. On one side of the valve there is a fixed short circuit 2.5 cms. from valve centre line, and on the other side, a tuning plunger. An output loop coupling is situated in line with the valve in the centre of the narrow face, and the loop adjusted by insertion and rotation for maximum power output.
- 3. $V_{\rm Res}$ to be adjusted for maximum power output.
- 4. The resonator to be earthed, and capacitors of low impedance at modulation frequency to be connected between grid and cathode, and screen and cathode.

 The modulation to be applied between cathode and resonator.
- 5. The resonator voltage to be varied above and below the value found in test (1), until the power falls to half the value obtained in test (1).
- 6. A valve is considered to have failed if V_{g2} increases by more than 20% during the test, I_k being kept constant at 50 mA. A batch will be passed if not more than one valve fails.
- 7. The end of life is defined as when 50 mA cathode current can no longer be obtained with V_{g2} = 300V. This shall be a factory life test in accordance with K1001 13.1 and for Type Approval purposes.
- 8. A maximum of 40 valves will be tested per month. For rates of production equal to or less than 40 per month, this corresponds to a 100% test. For higher rates there will be a corresponding reduction in the percentage tested.